

UPDATE

APPENDIX B: SIGNATURE BLOCK

The following approval signature block must appear on each set of stormwater management plans and water quality management plans which are to be reviewed and approved by the Department.

Harford County Stormwater Management Billing # 99994

THESE PLANS HAVE BEEN REVIEWED BY HARFORD COUNTY AND MEET THE TECHNICAL REQUIREMENTS FOR STORMWATER QUANTITY AND/OR QUALITY MANAGEMENT ONLY.

REVIEWED FOR TECHNICAL SUFFICIENCY

STORMWATER MANAGEMENT

REVIEW AND APPROVAL RECOMMENDED

CHIEF ENGINEER

APPROVAL RECOMMENDED

DEPUTY DIRECTOR OF PUBLIC WORKS

APPROVED

DIRECTOR OF PUBLIC WORKS

HARFORD COUNTY, MARYLAND

DEPARTMENT OF PUBLIC WORKS

BID NO. 21-048

CHURCH CREEK E.S.

100% SWM AND STREAM RESTORATION

GENERAL NOTES

- SPECIFICATIONS: ALL WORK IS TO BE PERFORMED IN ACCORDANCE MARYLAND STATE HIGHWAY ADMINISTRATIONS STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS DATED MAY 2017 AND THE MOST RECENT REVISIONS THEREOF AND ADDITIONS THERETO.
- UTILITIES: UTILITY LOCATIONS SHOWN ON THE PLANS ARE BASED ON LIMITED INFORMATION AVAILABLE. HOWEVER, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF THIS INFORMATION. THE COST OF REPAIR OR REPLACEMENT OF ANY SUCH FACILITIES DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE BORNE BY HIM.
- CONTACT "MISS UTILITY" PHONE 1-800-257-7777, 48 HOURS PRIOR TO THE START OF WORK. THERE SHOULD BE NO EXCAVATION UNTIL THE LOCATIONS OF UNDERGROUND UTILITIES HAVE BEEN DETERMINED.
- STANDARD DETAILS: REFERENCE MADE TO STANDARDS ARE TAKEN FROM THE HARFORD COUNTY ROAD CODE "BOOK OF STANDARD DETAILS" AND FROM "THE MARYLAND STATE HIGHWAY ADMINISTRATION'S BOOK OF STANDARDS-HIGHWAY AND INCIDENTAL STRUCTURES". IT WILL BE THE CONTRACTOR'S RESPONSIBILITY THAT THE STANDARD DRAWINGS IN HIS POSSESSION ARE THE LATEST REVISED STANDARDS UP TO AND INCLUDING THE DATE OF THE ADVERTISEMENT OF THIS CONTRACT.
- RIGHT-OF-WAY LINES: RIGHT-OF-WAY LINES SHOWN ON THESE PLANS DO NOT INCLUDE EASEMENTS. THEY ARE FOR ASSISTANCE IN INTERPRETING THE PLANS ONLY. THESE LINES DO NOT REPRESENT THE OFFICIAL PROPERTY ACQUISITION LINES. FOR OFFICIAL FEE RIGHT-OF-WAY AND EASEMENT INFORMATION, SEE THE APPROPRIATE RIGHT-OF-WAY PLATS.
- EXISTING MAILBOXES & EXISTING SIGNS: THE CONTRACTOR SHALL NOT DISTURB EXISTING MAILBOXES AND EXISTING SIGNS: ALL EXISTING MAILBOXES, SIGNS AND PAPER BOXES DISTURBED DURING CONSTRUCTION SHALL BE TEMPORARILY RESET IMMEDIATELY AND PERMANENTLY RESET AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE INCIDENTAL TO ALL OTHER ITEMS IN THE CONTRACT.
- SURVEYS: THE HORIZONTAL DATUM FOR THIS SURVEY IS THE MARYLAND COORDINATE SYSTEM, NAD83 (2011), AS ESTABLISHED VIA THE LEICA SMARTNET REAL-TIME GPS NETWORK. PRIMARY NGS REFERENCE STATION USED FOR THIS SURVEY:

DESIGNATION: LOYR
NGS PID: DL1384
STATE/COUNTY: MD/ CECIL
NORTH: 694448.67
EAST: 159774.51

THE VERTICAL DATUM FOR THIS SURVEY IS THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88). SURVEY CONTROL STATION ELEVATIONS WERE ESTABLISHED BY GPS, BASED ON THE ELEVATION OF THE NGS CONTROL STATION LISTED ABOVE.

THE US SURVEY FOOT IS THE UNIT OF MEASUREMENT FOR THIS SURVEY.

- THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE EXISTENCE OF PROPERTY MARKERS, PIPES, MONUMENTS, STAKES, ETC. THAT SHALL NOT BE DISTURBED. IN THE EVENT THESE MARKERS ARE REMOVED, DAMAGED, OR DESTROYED BY THE CONTRACTOR, THEY SHALL BE REPLACED IN KIND BY A MARYLAND LICENSED SURVEYOR AT THE CONTRACTOR'S EXPENSE.

TRAVERSE DATA:


NO	NORTHING	EASTING	ELEV	DESCRIPTION
100	658469.5033	1524984.6483	60.98	R/C
101	658484.0492	1524730.5550	51.53	R/C
102	658642.3406	1524732.5610	51.98	R/C
103	658823.1044	1524763.6413	56.85	R/C
104	658933.2043	1524829.5145	59.77	R/C
105	659010.6618	1524791.3713	62.39	R/C
106	659151.0165	1524793.4414	66.31	R/C
107	659264.7288	1524856.6399	68.67	R/C
108	659359.7180	1524884.5522	71.81	R/C
109	659493.3762	1524936.9774	74.22	R/C
110	659664.4176	1524974.9723	78.53	R/C
111	659831.6269	1524950.7970	89.36	R/C
112	659909.0366	1525148.7332	89.52	R/C
113	660018.9577	1525303.1449	95.75	R/C
114	660297.4212	1525291.6615	99.50	R/C
115	660341.9809	1524827.5467	106.56	R/C

SHEET INDEX

SHEET NO.	TITLE	SHEET NAME
01	COVER SHEET	CV-01
02	GENERAL NOTES AND ABBREVIATIONS	GN-01
03-07	EXISTING CONDITIONS & DEMOLITION - STREAM	EC-A1 TO EC-A5
08	EXISTING CONDITIONS & DEMOLITION - SWM	EC-B1
09-13	GEOMETRY PLAN - STREAM	GE-A1 TO GE-A5
14-15	GEOMETRY PLAN - SWM	GE-B1 TO GE-B2
16-20	GRADING PLAN - STREAM	GR-A1 TO GR-A5
21-22	GRADING PLAN - SWM	GR-B1 TO GR-B2
23	SOIL BORING LOG - SWM	SB-B1
24-27	PROFILE - STREAM	PR-A1 TO PR-A4
28-43	CROSS SECTIONS - STREAM	CS-A1 TO CS-A16
44-49	DETAILS - STREAM	DE-A1 TO DE-A6
50-54	DETAILS - SWM	DE-B1 TO DE-B5
55-59	EROSION AND SEDIMENT CONTROL PLAN - STREAM	EP-A1 TO EP-A5
60-61	EROSION AND SEDIMENT CONTROL PLAN - SWM	EP-B1 TO EP-B2
62-64	SEDIMENT CONTROL DETAILS	ER-A1 TO ER-A3
70	LANDSCAPE PLAN - SWM	LS-B1
73	MAINTENANCE OF TRAFFIC NOTES	MT-A1
74-77	MAINTENANCE OF TRAFFIC	MT-A2 TO MT-A5
78	DRAINAGE AREA MAP-SWM	DA-B1

LEGEND

- SOIL BOUNDARY
- D SOIL GROUP LABEL
- PROJECT WORK ZONE



LOCATION/ SOILS MAP

SCALE: 1" = 200'

Owner:
CONTACT: GLEN HEBEL P.E.
HARFORD COUNTY DEPARTMENT OF PUBLIC WORKS
BUREAU OF WATER RESOURCES
212 S. BOND ST.
BEL AIR, MD 21014
PH: 410-638-3545 EXT. 1344

Prepared By :
A. MORTON THOMAS AND ASSOCIATES
800 KING FARM BOULEVARD, FOURTH FLOOR
ROCKVILLE, MD 20850
PH: 301-881-2545

UPDATE
Professional Certification
No. 31177
02-16-2022
EXPIRATION DATE: 02/01/2023

Professional Certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland.
License No. 31177
Expiration Date 02/01/2021
Seal:
Professional Engineer
No. 31177
3-7-19

S/C PLAN # 59832
GRADING PERMIT # 9386-2017
EG-SWMENG-000747-2016

REVIEWED AND APPROVAL RECOMMENDED:
A. Hebel 6/17/2019
PROJECT ENGINEER
REVIEWED AND APPROVAL RECOMMENDED:
O. Buell 6/17/19
CHIEF ENGINEER
APPROVAL RECOMMENDED:
S. Allen 6/17/19
DEPUTY DIRECTOR OF PUBLIC WORKS
APPROVED:
S. Allen 6-20-19
DIRECTOR OF PUBLIC WORKS

HARFORD SOIL CONSERVATION DISTRICT
SMALL POND APPROVAL
District Official: [Signature] 5/13/19
DATE: 5/13/19
TECHNICAL REVIEW FOR DISTRICT
Michael K. Bitt 5/7/19
DATE: 5/7/19
HARFORD COUNTY DEPARTMENT OF PUBLIC WORKS

UPDATE
HARFORD SOIL CONSERVATION DISTRICT SMALL POND APPROVAL
District Official: [Signature] DATE: [Signature]
TECHNICAL REVIEW FOR DISTRICT
HARFORD COUNTY DEPARTMENT OF PUBLIC WORKS DATE: [Signature]

Appendix A: Certifications

The following statements of certification must be placed on the Stormwater Management Quantity and/or Quality plans and signed/dated at the appropriate stage of plan submittal.

DEVELOPER'S/LANDOWNER'S CERTIFICATION

I/We hereby certify that all proposed work shown on these construction drawing(s) will be accomplished pursuant to these plans. I/We also understand that it is my/our responsibility to have the construction supervised and certified, including the submittal of "As-Built" plans within 30 days of completion, by a Registered Professional Engineer.

Signed: [Signature]
Print Name: J. St. Michel, PE, DIRECTOR OF DPA
Date: 7-15-19

ENGINEER'S CERTIFICATION

I hereby certify that this plan has been prepared by me, or under my supervision, and meets the minimum standards of the Harford County Department of Public Works and/or the United States Department of Agriculture, Soil Conservation Service, and/or the Maryland Department of the Environment, Water Management Administration.

Signed: [Signature]
Print Name: GREGORY FOX
Date: 02-16-2022 GNF
P.E. No.: 31177

AS-BUILT CERTIFICATION

I hereby certify that the facility shown on this plan was constructed as shown on the "As-Built" plans and meets the approved plans and specifications.

Signed: [Signature]
Print Name: [Signature]
Date: [Signature]
P.E. No.: [Signature]

Certify means to state or declare a professional opinion based upon on-site inspections and material tests which are conducted during construction. The on-site inspections and material tests are those inspections and tests deemed sufficient and appropriate by commonly accepted engineering standards. Certify does not mean or imply a guarantee by the engineer nor does an engineer's certification relieve any other party from meeting requirements imposed by contract, employment, or other means, including meeting commonly accepted industry practices.

APPENDIX B: SIGNATURE BLOCK

The following approval signature block must appear on each set of stormwater management plans and water quality management plans which are to be reviewed and approved by the Department.

Harford County Stormwater Management Billing # 99994

THESE PLANS HAVE BEEN REVIEWED BY HARFORD COUNTY AND MEET THE TECHNICAL REQUIREMENTS FOR STORMWATER QUANTITY AND/OR QUALITY MANAGEMENT ONLY.

REVIEWED FOR TECHNICAL SUFFICIENCY

STORMWATER MANAGEMENT

REVIEW AND APPROVAL RECOMMENDED

CHIEF ENGINEER

APPROVAL RECOMMENDED

DEPUTY DIRECTOR OF PUBLIC WORKS

APPROVED

DIRECTOR OF PUBLIC WORKS

FIELD VERIFICATION CERTIFICATION

I HEREBY CERTIFY THAT I COMPLETED A FIELD VERIFICATION TO THE INFORMATION SHOWN ON THE PLANS ON [Signature] AND THAT THE INFORMATION SHOWN ON THE PLANS IS IN AGREEMENT WITH THE ACTUAL FIELD CONDITIONS. DECEMBER 1, 2021

GREGORY FOX
PRINTED NAME: [Signature]
DATE: 02-16-2022
SIGNED: [Signature] GNF

STORMWATER MANAGEMENT SUMMARY TABLE (BUSH RIVER WATERSHED)

FACILITY	DRAINAGE AREA (ac.)	DISTURBED AREA (ac.)	IMPERVIOUS AREA (ac.)	EX. IMPERVIOUS AREA (ac.)
GRAVEL WETLAND	5.99	0.73	3.82	N/A
INFILTRATION TRENCH	0.95	0.23	0.42	N/A

ABBREVIATIONS

AHD	Ahead	PAV.T.	Pavement
APPROX.	Approximate	PC	Point of Curvature
B/L	Baseline	PCC	Point of Compound Curvature
BK	Back / Book	P/C	Point of Crown
BIT.	Bituminous	P/GE	Profile Grade Elevation
B.C.	Bituminous Concrete	P.G.E.	Profile Ground Elevation
B.M.	Bench Mark	P.G.L.	Profile Grade Line
BOT.	Bottom	P/GL	Profile Ground Line
C.C.	Center of Curve	P.I.	Plasticity Index
CAP	Corrugated Aluminum Pipe	PI	Point of Intersection
CAPA	Corrugated Aluminum Pipe Arch	POC	Point On Curve
CATV	Cable Television	POT	Point On Tangent
C/L	Centerline	PPWP	Polyvinyl Chloride Profile Wall Pipe
CL.	Class	PROP	Proposed
CLF	Chainlink Fence	PRC	Point of Reverse Curve
CMP	Corrugated Metal Pipe	PT	Point
C.O.	Cleanout	PT	Point of Tangency
COMB.	Combination	PVC	Polyvinyl Chloride
CONC.	Concrete	R	Radius
CONSTR.	Construction	R.F.	Rock Fragments
COR.	Corner	RT	Right
CORR.	Correction	RW OR R/W	Right of Way
CPP-S	Corrugated Polyethylene Pipe - Type 'S'	RCP	Reinforced Concrete Pipe
CSP	Corrugated Steel Pipe - Aluminized Type 2	RCPD	Reinforced Concrete Pressure Pipe
CSPA	Corrugated Steel Pipe Arch - Aluminized Type 2	R.Q.D.	Rock Quality Designation
DATR	Data According to Records	R.M.	Rootmat
DC	Degree of Curve	S	South
D.H.V.	Design Hourly Volume	SAN.	Sanitary Sewer
D.I.	Drop Inlet	SB OR S/B	Southbound
DIA.	Diameter	S.D.	Storm Drain
D.O.	Double Opening	S.D.D.	Surface Drain Ditch
E	East	SF	Silt Fence
E	Electric	SF	Square Feet
EA	Each	SHT.	Sheet
ELEV	Elevation	S.P.T.	Standard Penetration Testing
ES	End Section	SRP	Steel Spiral Rib Pipe - Aluminized Type 2
EX or EXIST	Existing	SRPA	Steel Spiral Rib Pipe arch - Aluminized Type 2
FT	Feet	SSF	Super Silt Fence
F or FL	Flowline	STD.	Standard
F.B.D.	Flat Bottom Ditch	STA.	Station
F.H.	Fire Hydrant	SO.	Single Opening
FWD.	Forward	SY	Square Yards
G	Gas	SWM	Stormwater Management
G.V.	Gas Valve	T	Tangent
H.B.	Handbox	T	Telephone
HDPE	High Density Polyethylene	T.C.	Top of Cover
HDWL.	Headwall	T.G.	Top of Grate
HERCP	Horizontal Elliptical Reinforced Concrete Pipe	T OR TL	Traverse Line
HP	High Point	T.M.	Top of Manhole
IN	Inch	TRAV.	Traverse
I.S.T	Inlet Sediment Trap	TS	Temporary Swale
INV.	Invert	T.S.	Top of Slab
J.B.	Junction Box	T.S.	Topsoil
K	K Inlet	TYP.	Typical
L	Length	U.D.	Under Drain
LF	Linear Feet	U.G.	Underground
L.L.	Liquid Limit	U.P.	Utility Pole
LP	Low Point	USDA	United States Department of Agriculture
L.P.	Light Pole	W	Water
LT.	Left	W	West
MAC.	Macadam	WB	Westbound
MAX.	Maximum	WB	Wetland Buffer
MOD.	Modified	W.M.	Water Meter
MIN.	Minimum	W.S.	Wrapped Steel
N	North	WSE	Water Surface Elevation
NB	Northbound	WUS	Waters of the United States
NE	Northeast	W.V.	Water Valve
N.P.	Non-Plastic		
O.C.	On Center		
OHE	Overhead Electric		

STORMWATER MANAGEMENT AS-BUILT CERTIFICATION REQUIREMENTS:

- THE CONSTRUCTION OF ALL STORMWATER MANAGEMENT FACILITIES SHALL CONFORM TO THE APPROVED CONTRACT DOCUMENTS AND MDE STORMWATER DESIGN MANUAL VOLUMES I&II.
- THE CONTRACTOR IS RESPONSIBLE FOR FULLY UNDERSTANDING THE DESIGN AND FUNCTION OF THE PROPOSED FACILITIES AND FOR CONSTRUCTING FACILITIES IN FULL COMPLIANCE WITH DESIGN STANDARDS.
- THE CONTRACTOR SHALL ENSURE THAT ALL OF THE REQUIRED PLAN CHECKLISTS ARE SIGNED BY THE APPROPRIATE INDIVIDUALS AT THE REQUIRED STAGES OF CONSTRUCTION.
- THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 7-DAYS ADVANCED NOTICE OF CONSTRUCTION OF THE STORMWATER MANAGEMENT FACILITY(S) TO THE OWNER AND CERTIFYING ENGINEER.
- THE CONTRACTOR SHALL VERIFY ALL CRITICAL INVERTS AND ELEVATIONS THROUGHOUT CONSTRUCTION TO VERIFY CONFORMANCE WITH THE DESIGN AND STANDARDS. THIS INFORMATION SHALL BE PROVIDED TO THE OWNER AND THE CERTIFYING ENGINEER IN THE FORM OF RED-LINED CONTRACT DRAWINGS AT THE END OF THE PROJECT.
- THE CONTRACTOR OBTAIN THE SERVICES OF A MARYLAND LICENSED SURVEYOR TO CONDUCT AN AS-BUILT SURVEY OF THE STORMWATER MANAGEMENT FACILITY(S) PRIOR TO FINAL PLANTING LANDSCAPING.
- ANY ADJUSTMENTS TO THE CONSTRUCTION OF THE FACILITIES SHALL BE REVIEWED AND APPROVED BY THE CERTIFYING ENGINEER AND OWNER. APPROVAL OF THE MODIFICATIONS IS REQUIRED PRIOR TO PROCEEDING WITH CONSTRUCTION.
- THE CONTRACTOR SHALL MAKE ANY CORRECTIONS AND ADJUSTMENTS REQUIRED TO FULLY PROVIDE REQUIRED DESIGN VOLUMES, FUNCTION, AND STRUCTURAL INTEGRITY OF FACILITIES AT NO ADDITIONAL COST TO THE OWNER.
- THE CONTRACTOR SHALL ALSO VERIFY THAT ALL SITE IMPROVEMENTS, FLOW PATHS, AND DRAINAGE AREAS TO EACH FACILITY ARE IN CONFORMANCE WITH THE APPROVED DESIGN PLANS.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT PLANS AND APPROPRIATE SUPPORT DOCUMENTATION TO THE OWNER AND CERTIFYING ENGINEER.
- THE CONTRACTOR SHALL MAKE ANY AND ALL REPAIRS AND/OR MODIFICATIONS REQUIRED TO OBTAIN AS-BUILT APPROVAL BY HARFORD COUNTY AT NO ADDITIONAL COSTS TO THE OWNER.
- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR MAINTENANCE OF ALL STORMWATER-RELATED FACILITIES UNTIL FINAL ACCEPTANCE OF THE FACILITIES BY OWNER, AND SHALL PERFORM FULL CLEANOUT AND/OR DREDGING OF FACILITIES PRIOR TO TURN OVER TO THE OWNER.

GROUND COVERS

	ZONE 1: LIVESTAKE PLANTING AND STREAMSIDE SEEDING AREA
	ZONE 2: STREAMSIDE TREE, SHRUB AND SEED PLANTING AREA
	ZONE 3: WETLAND TREE, SHRUB AND SEEDING AREA
	ZONE 4: RIPARIAN TREE, SHRUB AND SEED PLANTING
	ZONE 5: TURF SOD
	COIR FIBER MATTING
	EROSION CONTROL MATTING

EROSION & SEDIMENT CONTROL

	LOD	LIMIT OF DISTURBANCE
	SF	SILT FENCE
	SSF	SUPER SILT FENCE
	DF	DIVERSION FENCE
	TP	TREE PROTECTION FENCE
	TPA	TEMPOR. PUMP AROUND PIPE
		SANDBAG DIKE
	FB	DEWATERING FILTER BAG
	RPS	REMOVABLE PUMPING STATION
		SCREENING BASKET
	ROP1	ROCK OUTLET PROTECTION
	P	TEMPORARY PUMP
	SCE	STABILIZED CONSTR. ENTRANCE
	TB	TEMPORARY ACCESS BRIDGE
	OCF	ORANGE CONSTRUCTION FENCE
	RP	ROOT PRUNING

	425	PROPOSED MAJOR CONTOUR
	424	PROPOSED MINOR CONTOUR
		PROPOSED THALWEG
		WATER SURFACE
		TOP OF BANK
		EXISTING 100 YEAR FLOODPLAIN
	100YR	PROPOSED 100 YEAR FLOODPLAIN
	WL	WETLAND
	WB	WETLAND BUFFER
	WUS	WATERS OF THE US
		EXISTING THALWEG

	TREE
	TREE REMOVAL
	TREE PLANKING
	TEMPORARY ACCESS ROAD-HEAVY DUTY MULCH MATTING
	TEMPORARY ACCESS ROAD-WETLAND PROTECTION MATTING
	STREAM BED MIX (SBM)
	RIPRAP
	RIFFLE GRADE CONTROL
	COMPACTED FILL
	IMBRICATED RIPRAP
	EXISTING GABION
	SOIL LIFT
	ROCK SILL/TOE
	STEP POOL SYSTEM
	CROSS VANE
	J-HOOK

	STOCKPILE/ STAGING AREA
--	-------------------------

	100	EXISTING MAJOR CONTOUR
		EXISTING MINOR CONTOUR
	SS	SANITARY SEWER
	SD	STORM DRAIN
	W	WATER SUPPLY
	E	ELECTRIC
	G	GAS
	C	COMMUNICATION
		TREELINE
		PROPERTY LINE
	X	CHAIN-LINK FENCE
		WOOD FENCE
		GUARDRAIL
		BENCHMARK
		TRAVERSE POINT
	TFP	TRAFFIC POLE
	EJB	ELECTRIC JUNCTION BOX
		STORM DRAIN MANHOLE
		GAS METER
		GAS VALVE
		WATER METER
		WATER VALVE
		FIRE HYDRANT
		SEWER MANHOLE
		SEWER CLEAN OUT
		TELCO MANHOLE
	TRI	TELCO RISER
		SIGN
		LIGHT POLE
		UTILITY POLE
		GUY WIRE
		ELECTRIC MANHOLE
		TRANSFORMER
		RIPRAP
		A/C UNIT
		GRATE INLET (ROUND)
		GRATE INLET
		TELEPHONE JUNCTION BOX
		LIGHT POLE
		POWER POLE
		CLEAN OUT
		BOLLARD
		WETLAND FLAGGING

NOTE:

ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL MEET CURRENT HARFORD COUNTY STANDARDS AND DIRECTIVES.

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	GENERAL NOTES & ABBREVIATIONS	
Drawn By :	LBT	Contract No. : DP1602779
Designed By :	MCB	Scale : NO SCALE
Reviewed By :	GWF	Sheet 02 Of 78
		Date : 2/17/2022

GN-01


ADC MAP :

TAX MAP :

HCC BILLING ID No.:

HCC DWG ID No.:

SCALE: 1"=100'




GENERAL NOTES:
 1.) DEAD TREES THAT ARE CLASSIFIED AS A HAZARD TO CONSTRUCTION ACTIVITY MAY BE REMOVED OUTSIDE OF THE LOD FOR SAFETY REASONS. THE CONTRACTOR MUST NOTIFY AND GET APPROVAL FROM THE COUNTY PRIOR TO REMOVING DEAD HAZARD TREES OUTSIDE OF THE LOD.

MATCHLINE SEE SHEET 07

BOARD OF EDUCATION OF HARFORD COUNTY
 4299 CHURCH CREEK ROAD
 BELCAMP MD 21017
 TAX MAP 0062 LOT 1 PARCEL 0813
 LIBER 01858
 FOLIO 0954
 PLAT 77172

EG-SWMENG-000747-2016



Revisions	HARFORD COUNTY, MARYLAND	
	EXISTING CONDITIONS AND DEMOLITION PLAN - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=20'
Reviewed By : _____	GWF	Sheet <u>03</u> Of <u>78</u>
		Date : <u>2/22/2022</u>


EC-A1

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:



DECLARATION CIRCLE

MATCHLINE SEE SHEET 03

MATCHLINE SEE SHEET 05

MATCHLINE SEE SHEET 03


MATCHLINE SEE SHEET 08

MATCHLINE SEE SHEET 08

BOARD OF EDUCATION OF HARFORD COUNTY
4299 CHURCH CREEK ROAD
BELCAMP MD 21017
TAX MAP 0062 LOT 1 PARCEL 0813
LIBER 01858
FOLIO 0954
PLAT 7772

EG-SWMENG-000747-2016

GENERAL NOTES:
1.) DEAD TREES THAT ARE CLASSIFIED AS A HAZARD TO CONSTRUCTION ACTIVITY MAY BE REMOVED OUTSIDE OF THE LOD FOR SAFETY REASONS. THE CONTRACTOR MUST NOTIFY AND GET APPROVAL FROM THE COUNTY PRIOR TO REMOVING DEAD HAZARD TREES OUTSIDE OF THE LOD.



Revisions	HARFORD COUNTY, MARYLAND EXISTING CONDITIONS AND DEMOLITION PLAN - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=20'
Reviewed By : _____	GWF	Sheet <u>04</u> Of <u>78</u>
		Date : <u>2/22/2022</u>


ADC MAP :

TAX MAP :


HCG BILLING ID No.:

HCG DWG ID No.:

EC-A2



GENERAL NOTES:
 1.) DEAD TREES THAT ARE CLASSIFIED AS A HAZARD TO CONSTRUCTION ACTIVITY MAY BE REMOVED OUTSIDE OF THE LOD FOR SAFETY REASONS. THE CONTRACTOR MUST NOTIFY AND GET APPROVAL FROM THE COUNTY PRIOR TO REMOVING DEAD HAZARD TREES OUTSIDE OF THE LOD.




EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND EXISTING CONDITIONS AND DEMOLITION PLAN - STREAM		
Drawn By : _____	LBT	Contract No : _____	DP1602779
Designed By : _____	MCB	Scale : _____	1"=20'
Reviewed By : _____	GWF	Sheet <u>07</u> Of <u>78</u>	
		Date : <u>2/22/2022</u>	

EC-A5

HCG BILLING ID No.: _____
 HCG DWG ID No.: _____
 TAX MAP : _____
 ADC MAP : _____




BOARD OF EDUCATION OF HARFORD COUNTY
 4299 CHURCH CREEK ROAD
 BELCAMP MD 21017
 TAX MAP 0062 LOT 1 PARCEL 0813
 LIBER 01858
 FOLIO 0954
 PLAT 77172

MATCHLINE SEE SHEET 13

ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
L27	0+00.00	19.60	S44° 52' 02.26"E	660132.1144	1525251.8714	
C26	0+19.60	24.75	S21° 13' 45.74"E	660118.2198	1525265.7018	30.00
L26	0+44.36	81.66	S2° 24' 30.77"W	660095.7950	1525274.4130	
C25	1+26.01	38.57	S39° 14' 09.95"W	660014.2110	1525270.9815	30.00
L25	1+64.58	36.37	S76° 03' 49.13"W	659986.3548	1525248.2333	
C24	2+00.95	12.14	S67° 58' 21.20"W	659977.5963	1525212.9378	42.97
L31	2+13.08	50.39	S59° 52' 53.27"W	659973.0599	1525201.7251	
C30	2+63.47	11.69	S54° 17' 57.77"W	659947.7749	1525158.1388	60.00
L32	2+75.16	13.54	S48° 43' 02.27"W	659940.9634	1525148.6597	
C23	2+88.70	9.90	S53° 57' 42.84"W	659932.0315	1525138.4866	54.07

ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
L23	2+98.60	14.69	S59° 12' 23.40"W	659926.2159	1525130.4934	
C22	3+13.29	12.20	S65° 02' 01.70"W	659918.6947	1525117.8731	60.00
L22	3+25.50	27.54	S70° 51' 40.00"W	659913.5522	1525106.8279	
C29	3+53.04	20.09	S61° 16' 15.20"W	659904.5215	1525080.8059	60.00
L21	3+73.13	35.14	S51° 40' 50.40"W	659894.9119	1525063.2748	
C27	4+08.27	46.24	S35° 38' 56.97"W	659873.1236	1525035.7052	82.62
L20	4+54.50	26.52	S19° 37' 03.53"W	659836.0406	1525009.1082	
C28	4+81.02	45.47	S3° 56' 03.34"E	659811.0611	1525000.2047	55.31



EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	GEOMETRY PLAN - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=20'
Reviewed By : _____	GWF	Sheet <u>09</u> Of <u>78</u>
		Date : <u>2/17/2022</u>


GE-A1

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:



MATCHLINE SEE SHEET 09

MATCHLINE SEE SHEET 11 - GEOMETRY PLAN - STREAM


MATCHLINE SEE SHEET 09

MATCHLINE SEE SHEET 14

MATCHLINE SEE SHEET 14

ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
L19	5+26.49	6.51	S27° 29' 10.21"E	659766.9644	1525003.2374	
C31	5+33.00	59.29	S2° 09' 16.56"W	659761.1914	1525006.2409	57.31
L18	5+92.29	7.90	S31° 47' 43.34"W	659704.5490	1525004.1099	
C21	6+00.20	3.61	S23° 11' 11.73"W	659697.8303	1524999.9448	12.00
L17	6+03.80	39.63	S14° 34' 40.12"W	659694.5280	1524998.5304	
C20	6+43.43	8.19	S34° 08' 12.88"W	659656.1760	1524988.5563	12.00
L28	6+51.62	18.24	S53° 41' 45.65"W	659649.5257	1524984.0475	
C19	6+69.86	35.69	S19° 37' 03.78"W	659638.7287	1524969.3512	30.00
L29	7+05.54	19.28	S14° 27' 38.09"E	659607.0606	1524958.0637	
C18	7+24.83	23.27	S7° 45' 52.73"W	659588.3889	1524962.8788	30.00
C17	7+48.49	39.83	S8° 02' 36.27"E	659565.5613	1524959.6159	30.00
L15	7+88.32	3.23	S46° 04' 36.11"E	659528.9578	1524964.7885	

ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
C16	7+91.56	14.40	S5° 29' 30.06"W	659526.7156	1524967.1166	8.00
L14	8+05.96	3.08	S57° 03' 36.23"W	659514.2395	1524965.9171	
C15	8+09.04	9.29	S34° 52' 46.86"W	659512.5633	1524963.3300	12.00
L13	8+18.33	10.69	S12° 41' 57.49"W	659505.1304	1524958.1487	
C14	8+29.02	7.53	S19° 53' 23.63"W	659494.7045	1524955.7993	30.00
L30	8+36.55	105.18	S27° 04' 49.77"W	659487.6423	1524953.2442	
C13	9+41.72	21.41	S6° 38' 05.24"W	659393.9975	1524905.3639	30.00
L12	9+63.13	46.39	S13° 48' 39.29"E	659373.1787	1524902.9423	
C12	10+09.53	38.13	S22° 35' 59.70"W	659328.1256	1524914.0175	30.00
L11	10+47.66	3.18	S59° 00' 38.69"W	659295.2461	1524900.3312	
C11	10+50.84	16.66	S43° 06' 18.53"W	659293.6069	1524897.6018	30.00



EG-SWMENG-000747-2016


Revisions	HARFORD COUNTY, MARYLAND	
	GEOMETRY PLAN - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=20'
Reviewed By : _____	GWF	Sheet <u>10</u> Of <u>78</u>
		Date : <u>2/17/2022</u>

GE-A2

HCG BILLING ID No.: HCG DWG ID No.: TAX MAP : ADC MAP :


MATCHLINE SEE SHEET 10

MATCHLINE SEE SHEET 12



ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
L10	10+67.50	41.96	S27° 11' 58.37"W	659281.6017	1524886.3655	
C10	11+09.46	8.88	S18° 43' 01.94"W	659244.2775	1524867.1838	30.00
L9	11+18.34	53.57	S10° 14' 05.50"W	659235.8952	1524864.3438	
C9	11+71.92	19.61	S28° 57' 37.98"W	659183.1753	1524854.8249	30.00
L8	11+91.53	26.18	S47° 41' 10.47"W	659166.3218	1524845.4980	
C8	12+17.71	15.06	S33° 18' 05.85"W	659148.6974	1524826.1383	30.00
L7	12+32.77	63.95	S18° 55' 01.23"W	659136.2392	1524817.9544	
C7	12+96.72	31.33	S11° 00' 11.34"E	659075.7440	1524797.2222	30.00
L6	13+28.05	10.08	S40° 55' 23.91"E	659046.3666	1524802.9342	
C6	13+38.13	36.04	S18° 04' 19.41"E	659038.7538	1524809.5341	45.18
L5	13+74.16	3.30	S4° 46' 45.09"W	659005.3972	1524820.4187	
C5	13+77.46	12.94	S2° 47' 35.86"W	659002.1079	1524820.1437	186.64

ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
L4	13+90.40	8.36	S0° 48' 26.62"W	658989.1878	1524819.5133	
C4	13+98.77	12.35	S6° 17' 35.03"W	658980.8240	1524819.3954	64.51
L3	14+11.12	38.99	S11° 46' 43.44"W	658968.5652	1524818.0435	
C3	14+50.11	49.83	S9° 41' 23.66"E	658930.3956	1524810.0843	66.49
L2	14+99.93	11.56	S31° 09' 30.77"E	658882.4220	1524818.2758	
C2	15+11.50	16.56	S9° 30' 09.29"E	658872.5255	1524824.2596	21.91
L1	15+28.06	18.76	S12° 09' 12.19"W	658856.5780	1524826.9290	
C1	15+46.82	35.73	S36° 10' 43.50"W	658838.2339	1524822.9785	42.61
L34	15+82.56	12.72	S60° 12' 14.81"W	658810.2305	1524802.4991	
C32	15+95.27	1.19	S60° 02' 00.14"W	658803.9106	1524791.4621	200.00
C33	15+96.47	21.33	S45° 46' 05.80"W	658803.3152	1524790.4295	43.35



EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	GEOMETRY PLAN - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=20'
Reviewed By : _____	GWF	Sheet <u>11</u> Of <u>78</u>
		Date : <u>2/17/2022</u>


GE-A3

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. :



MATCHLINE SEE SHEET 11

GRAPHIC SCALE




ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
C33	15+96.47	21.33	S45° 46' 05.80"W	658803.3152	1524790.4295	43.35
L37	16+17.79	32.87	S31° 04' 31.52"W	658788.5887	1524775.3026	
C34	16+50.67	18.30	S18° 35' 30.58"W	658760.4327	1524758.3342	42.00
L38	16+68.97	41.87	S6° 06' 29.63"W	658743.2228	1524752.5452	
C35	17+10.84	20.83	S8° 05' 50.50"E	658701.5905	1524748.0899	42.00
L39	17+31.66	30.78	S22° 18' 10.63"E	658681.1822	1524750.9935	

ALIGNMENT TABLE						
NUMBER	STATION	LENGTH	LINE/CHORD DIRECTION	NORTHING	EASTING	RADIUS
C36	17+62.45	32.61	S0° 03' 36.75"E	658652.7017	1524762.6759	42.00
C37	17+95.06	2.30	S22° 10' 58.53"W	658620.9049	1524762.7092	171972.22
C38	17+97.35	30.93	S1° 04' 58.58"W	658618.7776	1524761.8419	42.00
L41	18+28.29	9.22	S20° 01' 02.73"E	658588.5433	1524761.2703	
C39	18+37.50	46.63	S11° 47' 11.08"W	658579.8848	1524764.4248	42.00
L35	18+84.13	31.53	S43° 35' 24.86"W	658536.5491	1524755.3822	

EG-SWMENG-000747-2016

Revisions 	<h2 style="margin: 0;">HARFORD COUNTY, MARYLAND</h2> <h3 style="margin: 0;">GEOMETRY PLAN - STREAM</h3>
Drawn By : _____ LBT Designed By : _____ MCB Reviewed By : _____ GWF	Contract No : _____ DP1602779 Scale : _____ 1"=20' Sheet <u>12</u> Of <u>78</u> Date : <u>2/17/2022</u>

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. : GE-A4




RIVERSIDE PARKWAY
MD RT 543

MATCHLINE SEE SHEET 09

CHAPELGATE CT PLACE
BELCAMP MD 21017
TAX MAP 0062 LOT 1
LIBER 01834
FOLIO 0101
PLAT 73/6

BOARD OF EDUCATION OF HARFORD COUNTY
4299 CHURCH CREEK ROAD
BELCAMP MD 21017
TAX MAP 0062 LOT 1 PARCEL 0813
LIBER 01658
FOLIO 0954
PLAT 77/72


EG-SWMENG-000747-2016




Revisions		HARFORD COUNTY, MARYLAND	
		GEOMETRY PLAN - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	13 Of 78
		Date :	2/16/2022

GE-A5

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: SCALE: 1"=20'



POINT TABLE			
POINT #	NORTHING	EASTING	DESCRIPTION
1	659,698.33	1,524,372.68	CORNER OF NEW INFILTRATION TRENCH
2	659,697.09	1,524,390.64	CORNER OF NEW INFILTRATION TRENCH
3	659,622.27	1,524,385.45	CORNER OF NEW INFILTRATION TRENCH
4	659,623.51	1,524,367.50	CORNER OF NEW INFILTRATION TRENCH
5	659,754.24	1,524,362.48	EXISTING 12" PVC CONNECTION TO THE EXISTING INLET




EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		GEOMETRY PLAN - SWM	
Drawn By :	JS / MTB	Contract No :	DP1602779
Designed By :	JS / MTB	Scale :	1"=20'
Reviewed By :	MAE	Sheet	15 Of 78
		Date :	2/16/2022

GE-B2

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.:




MATCHLINE SEE SHEET 20

EG-SWMENG-000747-2016

BASELINE CONTROL COORDINATES					
BL CONSTRUCTION	STRUCTURE	STATION	NORTHING	EASTING	OFFSET
CROSS VANE	CV-01	1+79	659982.8939	1525234.2863	0.0
CROSS VANE	CV-02	2+30	659964.6408	1525187.2122	0.0
RIFFLE GRADE CONTROL	RGC-01	2+95	659928.1599	1525133.5214	0.0
CROSS VANE	CV-03	3+08	659921.5823	1525122.7184	0.0


BASELINE CONTROL COORDINATES					
BL CONSTRUCTION	STRUCTURE	STATION	NORTHING	EASTING	OFFSET
CROSS VANE	CV-04	3+61	659901.2117	1525073.0688	0.0
RIFFLE GRADE CONTROL	RGC-02	4+12	659870.5465	1525032.6031	0.0
CROSS VANE	CV-05	4+26	659860.7472	1525023.0924	0.0
CROSS VANE	CV-06	4+76	659815.7803	1525001.8868	0.0



Revisions		HARFORD COUNTY, MARYLAND GRADING PLAN - STREAM	
Drawn By : <u> </u> LBT Designed By : <u> </u> MCB Reviewed By : <u> </u> GWF	Contract No : <u> </u> DP1602779 Scale : <u> </u> 1"=20' Sheet <u> 16 </u> Of <u> 78 </u> Date : <u> 2/17/2022 </u>		

GR-A1


HGC BILLING ID No.:
 TAX MAP :
 ADC MAP :



GENERAL NOTE:
 THE CONTRACTOR MUST NOTIFY THE ENGINEER AND OBTAIN APPROVAL FROM THE ENGINEER PRIOR TO PERFORMING ALL STREAM WORK BETWEEN STATIONS 7+50 AND 9+00 TO ADDRESS CHANGES IN TOPOGRAPHY AFTER THE SURVEY WAS FINALIZED.

BASELINE CONTROL COORDINATES					
BL CONSTRUCTION	STRUCTURE	STATION	NORTHING	EASTING	OFFSET
RIFFLE GRADE CONTROL	RGC-03	5+38	659756.3631	1525008.4745	0.0
CROSS VANE	CV-07	5+60	659735.4019	1525012.7057	0.0
RIFFLE GRADE CONTROL	RGC-04	6+34	659665.6716	1524991.0258	0.0
J-HOOK	JH-01	6+43	659656.1760	1524988.5563	0.0
J HOOK	JH-02	6+92	659620.0047	1524957.6129	0.0
J HOOK	JH-03	7+33	659580.0664	1524963.8177	0.0
J HOOK	JH-04	7+73	659541.7171	1524956.9340	0.0

BASELINE CONTROL COORDINATES					
BL CONSTRUCTION	STRUCTURE	STATION	NORTHING	EASTING	OFFSET
J HOOK	JH-05	8+14	659509.4236	1524960.0693	0.0
CROSS VANE	CV-08	8+54	659472.2630	1524945.3808	0.0
CROSS VANE	CV-09	8+94	659436.1230	1524926.9025	0.0
CROSS VANE	CV-10	9+34	659400.4993	1524908.6883	0.0
CROSS VANE	CV-11	9+75	659361.6549	1524905.7752	0.0
J HOOK	JH-06	10+15	659322.8820	1524914.8356	0.0
J HOOK	JH-07	10+56	659290.8115	1524893.6946	0.0



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		GRADING PLAN - STREAM	
Drawn By :	LBT	Contract No. :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet :	17 Of 78
		Date :	2/17/2022

GR-A2

MATCHLINE SEE SHEET 16

MATCHLINE SEE SHEET 18

MATCHLINE SEE SHEET 16

MATCHLINE SEE SHEET 21

MATCHLINE SEE SHEET 21


ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:


BASELINE CONTROL COORDINATES					
BL CONSTRUCTION	STRUCTURE	STATION	NORTHING	EASTING	OFFSET
CROSS VANE	CV-12	10+96	659256.5529	1524873.4924	0.0
J HOOK	JH-08	11+23	659230.8807	1524863.4384	0.0
STEP POOL	SP-01	11+43	659211.9271	1524860.0162	0.0
STEP POOL	SP-02	11+62	659192.9638	1524856.5922	0.0
J HOOK	JH-09	11+81	659174.5973	1524851.8833	0.0
J HOOK	JH-10	12+22	659145.9353	1524823.4695	0.0
STEP POOL	SP-03	12+62	659108.9287	1524808.5948	0.0
STEP POOL	SP-04	12+81	659090.8897	1524802.4059	0.0
J HOOK	JH-11	13+00	659072.6276	1524796.3390	0.0
RIFLE GRADE CONTROL	RGC-05	13+43	659034.6186	1524812.7199	0.0
J HOOK	JH-12	13+51	659028.3912	1524816.2786	0.0
STEP POOL	SP-05	13+87	658992.5080	1524819.5896	0.0
STEP POOL	SP-06	14+06	658973.3832	1524818.8591	0.0
STEP POOL	SP-07	14+25	658954.6228	1524815.1362	0.0
STEP POOL	SP-08	14+45	658935.8863	1524811.2250	0.0
STEP POOL	SP-09	14+67	658914.0608	1524808.7417	0.0
STEP POOL	SP-10	14+86	658895.3330	1524812.2531	0.0
STEP POOL	SP-11	15+05	658878.1981	1524820.8297	0.0
J HOOK	JH-13	15+24	658860.5731	1524827.4113	0.0
J HOOK	JH-14	15+60	658825.5858	1524818.0417	0.0
CROSS VANE	CV-13	15+97	658803.0236	1524789.9346	0.0



MATCHLINE SEE SHEET 17

MATCHLINE SEE SHEET 19

EG-SWMENG-000747-2016



Revisions	HARFORD COUNTY, MARYLAND	
	GRADING PLAN - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=20'
Reviewed By : _____	GWF	Sheet <u>18</u> Of <u>78</u>
		Date : <u>2/17/2022</u>

GR-A3

ADC MAP :


TAX MAP :

HCC BILLING ID No.:

HCC DWG ID No.:


BASELINE CONTROL COORDINATES					
BL CONSTRUCTION	STRUCTURE	STATION	NORTHING	EASTING	OFFSET
J-HOOK	JH-15	16+51	658759.8335	1524757.9799	0.0
CROSS VANE	CV-14	16+86	658726.5054	1524750.7562	0.0
STEP POOL	SP-12	17+26	658686.5414	1524749.2059	0.0
STEP POOL	SP-13	17+47	658666.8082	1524756.8896	0.0
CROSS VANE	CV-15	17+76	658639.9455	1524765.6972	0.0
CROSS VANE	CV-16	18+13	658603.9849	1524758.7466	0.0
CROSS VANE	CV-17	18+53	658564.9752	1524766.9587	0.0
IMBRICATED RIP RAP WALL	IRR-02	18+74	658549.3868	1524753.8518	8.9 R
IMBRICATED RIP RAP WALL	IRR-01	18+78	658536.1286	1524766.1569	8.6 L
STEP POOL	SP-14	18+89	658532.6890	1524751.7075	0.0
ROCK SILL	RS-01	19+04	658521.8464	1524741.3858	0.0
RIFFLE GRADE CONTROL	RGC-06	19+08	658518.9406	1524738.6196	0.0

MATCHLINE SEE SHEET 18



FROM	TO	SIZE	MATERIAL	CLASS	LENGTH (FT)	INV. IN	INV. OUT	SLOPE	NOTES
MH-01	EW-02	30"	RCP	IV	39.15'	48.10	47.81	0.75%	NEW PIPE

STRUCTURE NO.	STRUCTURE TYPE	Q INLET STATION	OFFSET (FT)	NORTHING	EASTING	TOP ELEV.	INVERT IN	INVERT OUT	NOTES
EW-02	TYPE C ENDWALL	16+62.07	20.89	658755.58	1524733.71	51.30	47.81 (30")		SEE DETAIL SHEET DE-A4
MH-01	TYPE A MANHOLE	16+58.11	59.30	658774.92	1524699.68	60.29	53.97 (30")	48.10 (30")	SEE DETAIL SHEET DE-A4



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		GRADING PLAN - STREAM	
Drawn By :	LBT	Contract No. :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	19 Of 78
		Date :	2/17/2022

GR-A4


ADC MAP :

TAX MAP :

HCC BILLING ID No.:

HCC DWG ID No.:


SCALE 1"=20'



CHABELGATE CT & PLACE
 BELCAMP MD 21017
 TAX MAP 0062 LOT
 LIBER 01858
 FOLIO 0954
 PLAT 7376
 PARCEL 0769

BOARD OF EDUCATION OF HARFORD COUNTY
 4299 CHURCH CREEK ROAD
 BELCAMP MD 21017
 TAX MAP 0062 LOT 1 PARCEL 0813
 LIBER 01858
 FOLIO 0954
 PLAT 7772


EG-SWMENG-000747-2016



Revisions		HARFORD COUNTY, MARYLAND	
		GRADING PLAN - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	20 Of 78
		Date :	2/16/2022

GR-A5

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.:



MAINTENANCE SCHEDULE FOR SUBMERGED GRAVEL WETLANDS		
FREQUENCY OF INSPECTION	INSPECTION REQUIREMENTS	REMEDIAL ACTION
SEASONALLY AND AFTER A MAJOR STORM	YES	REMOVE ANY DEAD OR DYING VEGETATION AND REVEGETATE.
SEASONALLY AND AFTER A MAJOR STORM	YES	REMOVE ACCUMULATED SEDIMENT FROM PRETREATMENT AREAS.
SEASONALLY AND AFTER A MAJOR STORM	YES	CLEAN INLETS AND OUTLETS OF SEDIMENT, DEBRIS, AND TRASH.
SEASONALLY AND AFTER A MAJOR STORM	YES	REPAIR EROSION AT INFLOW POINTS.
SEASONALLY AND AFTER A MAJOR STORM	N/A	CHECK THAT FLOW SPLITTERS ARE FUNCTIONING AS DESIGNED.
SEASONALLY AND AFTER A MAJOR STORM	YES	SIGNS OF UNEVEN FLOW DISTRIBUTION MAY INDICATE THAT THE GRAVEL OR UNDERDRAIN IS CLOGGED, REMOVE, CLEAN, AND REPLACE GRAVEL.

AT A MINIMUM, REGULAR INSPECTIONS SHALL BE MADE AND DOCUMENTED AT THE FOLLOWING SPECIFIED STAGES OF CONSTRUCTION:



- SUBMERGED GRAVEL WETLAND:**
- (A) DURING EXCAVATION TO SUBGRADE.
 - (B) DURING PLACEMENT OF BACKFILL OF PERFORATED INLET PIPE AND OBSERVATION WELLS.
 - (C) DURING PLACEMENT OF GEOTEXTILES AND ALL FILTER MEDIA.
 - (D) DURING CONSTRUCTION OF ANY APPURTENANT CONVEYANCE SYSTEMS SUCH AS DIVERSION STRUCTURES, INLETS, OUTLETS, AND FLOW DISTRIBUTION STRUCTURES.
 - (E) UPON COMPLETION OF FINAL GRADING AND ESTABLISHMENT OF PERMANENT STABILIZATION, AND BEFORE ALLOWING RUNOFF TO ENTER WETLAND.

SPECIFICATIONS FOR SUBMERGED GRAVEL WETLANDS

1. WETLANDS VEGETATION ESTABLISHMENT
USE OF NATIVE WETLAND PLANT STOCK OBTAINED FROM A LOCAL AQUATIC PLANT NURSERY IS RECOMMENDED FOR ESTABLISHING VEGETATION. DESIGN VARIATIONS MAY USE WETLAND MULCH OR TOPSOIL ON TOP OF THE GRAVEL, WHICH MAY ALLOW FOR SUCCESSFUL SEED GERMINATION. HOWEVER, USE OF THE ROCK MEDIA FOR ESTABLISHING WETLAND CONDITIONS REQUIRES SPECIFIC PLANTING STOCK. FREQUENT INSPECTION AND MAINTENANCE WILL BE NECESSARY UNTIL WETLAND PLANTINGS ARE WELL ESTABLISHED.
2. WETLAND SOIL MEDIA
TO CREATE GRAVEL WETLAND SOIL MEDIA, CONTRACTOR SHALL AMEND STOCKPILED ON-SITE TOPSOIL TO MEET THE FOLLOWING REQUIREMENTS:
 - SOIL TEXTURE SHALL BE SILT LOAM
 - CLAY CONTENT OF SOIL MIX SHALL NOT EXCEED 15%
 - ORGANIC CONTENT SHALL BE 15%-20% OF SOIL MIX BY MASS. ORGANIC MATTER SHALL CONSIST OF PROPERLY MATURED LEAF COMPOST.
 - CATION EXCHANGE CAPACITY (CEC) SHALL BE 20 MEQ/100 G OF SOIL MIX OR GREATER
 - PH SHALL BE 6.5-7.5.
 - CONTRACTOR SHALL SUBMIT ONE 2 LB SAMPLE PER 40 CUBIC YARDS MIXED, TO A MARYLAND CERTIFIED LABORATORY. THE TEST RESULTS FOR EACH SAMPLE SHALL BE SUBMITTED TO THE COUNTY. THE LABORATORY RESULTS SHALL CONFIRM THAT THE SOIL MIX MEETS THE REQUIREMENTS LISTED ABOVE.
3. PEA GRAVEL
PEA GRAVEL TO BE WASHED, UNCRUSHED NATURAL PEA GRAVEL, SIZE NO. 8.
4. GRAVEL MEDIA
THE AGGREGATE SHALL BE COMPOSED OF CLEAN WASHED, UNIFORMLY GRADED MATERIAL WITH A POROSITY OF 40%. APPROVED BANK RUN GRAVEL IS RECOMMENDED. AGGREGATE SHALL BE ASTM D448 #4, #5, OR #6 STONE (OR AN APPROVED EQUAL).
5. PIPE
ALL FACILITY PIPING (SURFACE DRAIN, UNDERDRAIN, RISER, CLEAN-OUT, ETC.) IS TO BE 6" DIAMETER SCHEDULE 40 OR STRONGER PVC, PERFORATIONS TO BE AS SPECIFIED ON PLANS.
- ALL OTHER PIPE TO BE SCHEDULE 40 OR STRONGER PVC OR ADS N-12 HDPE AS SPECIFIED ON PLANS.
6. GEOTEXTILE FABRIC
CONTRACTOR TO PROVIDE CLASS PE, TYPE III NON-WOVEN GEOTEXTILE FABRIC ALONG ALL SIDES OF FACILITIES.

AS-BUILT DATA FOR STORMWATER MANAGEMENT FACILITY #2 (SUBMERGED GRAVEL WETLAND #1) * TO BE COMPLETED BY THE CERTIFYING ENGINEER		
TYPE OF FACILITY: SUBMERGED GRAVEL WETLAND	DESIGN	*AS-BUILT
ESD STORAGE VOLUME (CF)	14,023	
TOP OF BERM EMBANKMENT	85.50 (MIN.)	
SURFACE ELEVATION	81.0	
SURFACE AREA (SF) / SURFACE DIMENSIONS (L x W)	5435 / 226' X 24'	
WETLAND SOIL DEPTH/BOTTOM ELEVATION	8"	
PEA GRAVEL DEPTH/BOTTOM ELEVATION	N/A	
BANK RUN GRAVEL DEPTH/BOTTOM ELEVATION	24"	
BOTTOM AREA (SF) / BOTTOM DIMENSIONS (L x W)	5435 / 226' X 24'	
INFLOW SURFACE DRAIN # 1 SIZE/ELEVATION/LENGTH	EX.24"/82.78/59 LF +/-	
INFLOW SURFACE DRAIN # 2 SIZE/ELEVATION/LENGTH	EX.12"/82.80/104 LF +/-	
INFLOW WEIR WALL OPENING	8" WEIR OPENING	
INFLOW UNDERDRAIN SIZE/ELEVATION/LENGTH	12"/78.17/191 LF	
OUTFLOW UNDERDRAIN SIZE/ELEVATION/LENGTH	12"/80.67/2 LF	
OUTFLOW CLEAN OUT SIZE/HEIGHT/PROVIDED (#)	6"/3.83'/2	
OBSERVATION WELL SIZE/HEIGHT/PROVIDED (#)	6"/4.33'/2	
OUTFLOW PIPE SIZE/ELEVATION/LENGTH	N/A	
DATE AS-BUILT ACCEPTED:		

POINT TABLE			
POINT #	NORTHING	EASTING	DESCRIPTION
1	659,489.06	1,524,745.76	12" PVC 45' HORZ. BEND
2	659,490.04	1,524,754.45	CLEANOUT
3	659,537.68	1,524,775.37	12" PVC 11 1/2' HORZ. BEND
4	659,565.80	1,524,770.95	CLEANOUT
5	659,624.89	1,524,789.19	CLEANOUT
6	659,671.29	1,524,785.06	CLEANOUT
7	659,714.04	1,524,787.21	STA. 3+68 END OF BASELINE



AS BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

NAME _____	SIGNATURE _____
MARYLAND REGISTRATION NUMBER _____	DATE _____

SUBMERGED GRAVEL WETLAND FACILITY IDENTIFICATION (NUMBER AND/OR TYPE) _____

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.

LICENSE NO. _____ EXPIRATION DATE _____

EG-SWMENG-000747-2016


HARFORD COUNTY, MARYLAND

GRADING PLAN - SWM

Drawn By : JS / MTB	Contract No : DP1602779
Designed By : JS / MTB	Scale : 1"=20'
Reviewed By : MAE	Sheet 21 Of 78
	Date : 2/16/2022

GR-B1

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. :



AS-BUILT DATA FOR LANDSCAPE INFILTRATION FACILITIES TO BE COMPLETED BY THE CERTIFYING ENGINEER

TYPE OF FACILITY: INFILTRATION	INFILTRATION TRENCH	
	DESIGN	*AS-BUILT
FACILITY AREA (LxW)/ SURFACE AREA (SF)	** (AVG.) 7.33'x260 LF/1,906	
FACILITY SURFACE ELEVATION	98.5	
WATER VOLUME (CF)	1,905	
AGGREGATE THICKNESS (IN)	2.0'	
PEA GRAVEL THICKNESS (IN)	N/A	
SAND THICKNESS (IN)	6"	
GRAVEL THICKNESS (IN)	N/A	
GEOTEXTILE FABRIC INSTALLATION (SIDES AND TOP)	YES	
DATE AS-BUILT ACCEPTED:		

AT A MINIMUM, REGULAR INSPECTIONS SHALL BE MADE AND DOCUMENTED AT THE FOLLOWING SPECIFIED STAGES OF CONSTRUCTION:

INFILTRATION TRENCHES:

- (A) DURING EXCAVATION TO SUBGRADE AND PLACEMENT AND BACKFILL OF UNDERDRAIN SYSTEMS AND GRAVEL LAYERS.
- (B) DURING PLACEMENT OF PIPING.
- (C) DURING CONSTRUCTION OF APPURTENANT CONVEYANCE. (OVERFLOW INLET)
- (D) UPON COMPLETION OF FINAL GRADING AND ESTABLISHMENT OF PERMANENT STABILIZATION.

**NEW TRENCH AREA 18' x 75'

STORM DRAIN STRUCTURE SCHEDULE

STRUCT.	TYPE	TOP ELEV.	INV. IN	INV. OUT	STANDARD DETAIL	STATION (OR NORTH)*	STATION (OR EAST)*
IN-1	DRAIN BASIN	99.50	97.50	97.50	PVC (SCH 40) DRAIN BASIN	659692.07	1524411.31
IN-2	DRAIN BASIN	99.50	97.50	97.50	PVC (SCH 40) DRAIN BASIN	659659.15	1524409.04
IN-3	DRAIN BASIN	99.50	97.50	97.50	PVC (SCH 40) DRAIN BASIN	659626.22	1524406.78
IN-4	DRAIN BASIN	100.00	97.50	97.50	PVC (SCH 40) DRAIN BASIN	659588.98	1524404.30
IN-5	DRAIN BASIN	100.00	97.50	97.50	PVC (SCH 40) DRAIN BASIN	659549.33	1524401.66

* ALL STATION OR COORDINATES (UNLESS OTHERWISE NOTED) ARE:
MANHOLES/INLETS—CENTER OF THE STRUCTURE
CURB INLETS—MIDDLE OF THE FRONT FACE



STORM DRAIN PIPE SCHEDULE

FROM	TO	SIZE	TYPE	LENGTH (L.F.)
IN-1	IN-2	12"	PVC SCH. 40	33
IN-2	IN-3	12"	PVC SCH. 40	33
IN-3	(1)	12"	PVC SCH. 40	28
IN-4	(2)	6"	PVC SCH. 40	24
IN-5	(2)	6"	PVC SCH. 40	34

STORM DRAIN PIPE SUMMARY

SIZE	TYPE	CLASS	LENGTH (L.F.)
6"	PVC	SCH. 40	58
12"	PVC	SCH. 40	94

- (1) UNDERDRAIN INFILTRATION DRAIN, SEE DETAIL PLANS SHEET DE-B3 AND DE-B4
- (2) EXISTING UNDERDRAIN PIPE



**STORMWATER MAINTENANCE SCHEDULE
INFILTRATION TRENCH**

Inspection Item	Frequency of Inspection	Inspection Requirements	Remedial Action
Filter Surface	Seasonally and after a major storm		
Dewatering		Facility must dewater within 48 hours of rainfall. Noticeable odors, stained water on the filter surface or at the outlet, or the presence of algae or aquatic vegetation are indicators of anaerobic conditions and inadequate dewatering of the facility.	Remove the top three to six inches of stone and replace with stone material per plan specifications. Follow up inspections must confirm adequate dewatering. If the facility does not function as intended after the above action, the entire facility may need maintenance. Contact MDE.
Cleanouts/ Observation wells		Check operation. Check sediment accumulation.	Repair in accordance with the approved plans.
Sediment Accumulation		Check for sediment accumulation on the trench surface.	Silt/sediment must be removed from the stone when accumulation exceeds 1 inch.
Debris and Trash Cleanout	Monthly	Check that the facility is clean of trash and debris. Inlets, outlets, and contributing areas around the facility must be checked.	Trash and debris must be disposed of in an acceptable manner according to current regulations.
Structural Components	Annually	Check for evidence of structural deterioration, spalling, or cracking. Inlet and outlet structures must be in good condition.	Repair to good condition in accordance with specifications on the approved plans.
Outlets	Seasonally and after a major storm	Check for evidence of erosion, rills, or gullying.	Stabilize all eroded areas and grade to provide stable conveyance.
		Check that Riprap outlet is in good functional condition.	Repair in accordance with approved plans.
Pretreatment Forebays	Seasonally and after a major storm		
Sediment Accumulation		Check for sediment accumulation in the forebay.	When the forebay depth is less than half the proposed design, sediment must be removed and the forebay restored in accordance with the approved design.
Grass Channel Conveyance Systems	Seasonally and after a major storm	Check for erosion, flow blockages, and stable conveyance.	Stabilize and grade in accordance with the approved plan.
Overall Function of the Facility	Annually	Check that flow splitters are functioning as designed and that bypass is operating as designed.	Construction must be in accordance with approved plans.

AS BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

NAME _____ SIGNATURE _____

MARYLAND REGISTRATION NUMBER _____ DATE _____

INFILTRATION TRENCH
FACILITY IDENTIFICATION
(NUMBER AND/OR TYPE)

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.

LICENSE NO. _____ EXPIRATION DATE _____







EG-SWMENG-000747-2016

**HARFORD COUNTY, MARYLAND
GRADING PLAN
LID BMP'S**

Revisions	Drawn By : JS / MTB	Contract No : DP1602779
	Designed By : JS / MTB	Scale : 1"=20'
	Reviewed By : MAE	Sheet 22 Of 78
		Date : 2/16/2022

GR-B2

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. : SCALE: 1"=20'



EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND
	SOIL BORING LOG - SWM
Drawn By : _____	JS / MTB
Designed By : _____	JS / MTB
Reviewed By : _____	MAE
Contract No : _____	DP1602779
Scale : _____	N/A
Sheet _____ Of _____	23 Of 78
Date : _____	2/16/2022

ADC MAP :


TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE: 1"=10'


SB-B1



SCALE: HORZ: 1"=20'
VERT: 1"=2'



GRAPHIC SCALE
(IN FEET)
1 inch = 2 ft.



GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		PROFILE - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	24 Of 78
		Date :	2/16/2022

PR-A1

MATCHLINE SEE SHEET 25 STA. 5+28

ADC MAP :

TAX MAP :


HCG BILLING ID No.:

HCG DWG ID No.:

SCALE: 1"=20'

MATCHLINE SEE SHEET 24 STA. 5+28


MATCHLINE SEE SHEET 26 STA. 10+67



SCALE: HORZ: 1"=20'
VERT: 1"=2'



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 2 ft.



HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		PROFILE - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	25 Of 78
		Date :	2/16/2022

PR-A2

ADC MAP :


TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE: 1"=20'

MATCHLINE SEE SHEET 25 STA. 10+67




MATCHLINE SEE SHEET 27 STA. 16+02

SCALE: HORZ: 1"=20'
VERT: 1"=2'



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 2 ft.




HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.

EG-SWMENG-000747-2016

<p>Revisions</p>		<p>HARFORD COUNTY, MARYLAND</p> <p>PROFILE - STREAM</p>	
<p>Drawn By : <u> </u> LBT</p> <p>Designed By : <u> </u> MCB</p> <p>Reviewed By : <u> </u> GWF</p>	<p>Contract No : <u> </u> DP1602779</p> <p>Scale : <u> </u> 1"=20'</p> <p>Sheet <u> 26 </u> Of <u> 78 </u></p> <p>Date : <u> 2/16/2022 </u></p>	<p>HCG BILLING ID No.:</p> <p>TAX MAP :</p> <p>ADC MAP :</p> <p>PR-A3</p>	


MATCHLINE SEE SHEET 26 STA. 16+02




SCALE: HORZ: 1"=20'
VERT: 1"=2'



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 2 ft.



HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.



MH-01 TO EW-02

SCALE: HORZ: 1"=20'
VERT: 1"=2'

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		PROFILE - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet :	27 Of 78
		Date :	2/16/2022


PR-A4

ADC MAP :


TAX MAP :

HCG BILLING ID No.:


HCG DWG ID No.:




CROSS SECTION - CV-01 - 1+78.95



CROSS SECTION - CS-01 - 2+00.00





CROSS SECTION - CV-02 - 2+29.86



CROSS SECTION - CS-02 - 2+50.00

NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.







EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet	28 Of 78
		Date :	2/16/2022

CS-A1

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: SCALE 1"=10'




NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.




HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016


Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No. :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet :	29 Of 78
		Date :	2/16/2022

ADC MAP :
TAX MAP :
HCG BILLING ID No. :
HCG DWG ID No. :
SCALE 1"=10'


CS-A2




CROSS SECTION - CV-05 - 4+25.97



CROSS SECTION - CS-03 - 4+50.00




CROSS SECTION - CV-06 - 4+76.01




CROSS SECTION - CS-04 - 5+00.00

NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.






HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet	30 Of 78
		Date :	2/16/2022

HCG BILLING ID No.:
HCG DWG ID No.:
TAX MAP :
ADC MAP :

CS-A3




NOTES

- ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
- CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.







GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016



Revisions		HARFORD COUNTY, MARYLAND	
CROSS SECTIONS - STREAM			
Drawn By : <u> LBT </u>	Contract No : <u> DP1602779 </u>		
Designed By : <u> MCB </u>	Scale : <u> 1"=10' </u>		
Reviewed By : <u> GWF </u>	Sheet <u> 31 </u> Of <u> 78 </u>		
		Date : <u> 2/16/2022 </u>	CS-A4

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: SCALE: 1"=10'



NOTES





- ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
- CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



EG-SWMENG-000747-2016



Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet :	33 Of 78
		Date :	2/16/2022

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: CS-A6



NOTES

- ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
- CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet	34 Of 78
		Date :	2/16/2022





CS-A7

ADC MAP :

TAX MAP :



HCG BILLING ID No.:

HCG DWG ID No.:



NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



EG-SWMENG-000747-2016


Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet	35 Of 78
		Date :	2/16/2022

CS-A8


ADC MAP : TAX MAP :

HCG BILLING ID No.:


HCG DWG ID No.:




CROSS SECTION - JH-09 - 11+81.02



CROSS SECTION - JH-10 - 12+21.55





CROSS SECTION - SP-03 - 12+61.64



CROSS SECTION - SP-04 - 12+80.73

NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.




EG-SWMENG-000747-2016


Revisions	HARFORD COUNTY, MARYLAND	
	CROSS SECTIONS - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ 1"=10'
Reviewed By : _____	GWF	Sheet <u>36</u> Of <u>78</u>
		Date : <u>2/16/2022</u>

HCG BILLING ID No.: _____
HCG DWG ID No.: _____
ADC MAP : _____
TAX MAP : _____
SCALE: 1"=10'


CS-A9




CROSS SECTION - JH-11 - 12+99.96



CROSS SECTION - CS-06 - 13+25.00



CROSS SECTION - RGC-05 - 13+43.35



CROSS SECTION - JH-12 - 13+50.53

NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.




HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016


Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet :	37 Of 78
		Date :	2/16/2022

CS-A10


HCG DWG ID No. :
HCG BILLING ID No. :
TAX MAP :
ADC MAP :




CROSS SECTION - CS-07 - 13+75.00



CROSS SECTION - SP-05 - 13+87.08




CROSS SECTION - SP-06 - 14+06.23




CROSS SECTION - SP-07 - 14+25.36

NOTES

- ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
- CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.



HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet :	38 Of 78
		Date :	2/16/2022


CS-A11

ADC MAP :


TAX MAP :

HCG BILLING ID No.:


HCG DWG ID No.:




CROSS SECTION - SP-08 - 14+44.52



CROSS SECTION - SP-09 - 14+66.54



CROSS SECTION - SP-10 - 14+85.66




CROSS SECTION - SP-11 - 15+04.87

NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.



HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet	39 Of 78
		Date :	2/16/2022





CS-A12

ADC MAP :

TAX MAP :



HCG BILLING ID No.:

HCG DWG ID No.:



NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
CROSS SECTIONS - STREAM		Contract No. : DP1602779	
Drawn By : _____	LBT	Scale : _____	1"=10'
Designed By : _____	MCB	Sheet <u>40</u> Of <u>78</u>	
Reviewed By : _____	GWF	Date : <u>2/16/2022</u>	CS-A13





TAX MAP :

ADC MAP :

HCG BILLING ID No.:



HCG DWG ID No.:

SCALE 1"=10'



NOTES

- ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
- CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No. :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet :	41 Of 78
		Date :	2/16/2022
		CS-A14	





ADC MAP :

TAX MAP :

HCG BILLING ID No.:



HCG DWG ID No.:

SCALE: 1"=10'



NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



EG-SWMENG-000747-2016


Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=10'
Reviewed By :	GWF	Sheet	42 Of 78
		Date :	2/16/2022

CS-A15

ADC MAP : TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:



CROSS SECTION - RS-01 - 19+04.43

NOTES

1. ALL CROSS SECTIONS ARE LOOKING DOWNSTREAM.
2. CONTRACTOR TO STABILIZE SOILS WITH SHA SOIL STABILIZATION MATTING (SSM), TYPE D AS DIRECTED BY THE FIELD ENGINEER. ALL POINTS WITHIN THE ACTIVE CHANNEL WILL BE MATTED WITH SOIL STABILIZATION MATTING, TYPE D. ON SLOPES RANGING FROM 5:1 TO 10:1 OUTSIDE THE ACTIVE CHANNEL, TEMPORARY SEED AND MULCH MAY BE USED FOR TEMPORARY STABILIZATION UNTIL FINAL LANDSCAPE PLANTINGS ARE IN PLACE.



VERTICAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.



HORIZONTAL GRAPHIC SCALE
(IN FEET)
1 inch = 10 ft.

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		CROSS SECTIONS - STREAM	
Drawn By : _____	LBT	Contract No : _____	DP1602779
Designed By : _____	MCB	Scale : _____	1"=10'
Reviewed By : _____	GWF	Sheet _____	43 Of 78
		Date : 2/16/2022	CS-A16

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE 1"=10'

STANDARD APRON (STD) MIX OR RIFFLE GRADE CONTROL (RGC) MIX PLACED UPSTREAM OF APEX STONES. MIX TYPE IS INDICATED UNDER APEX APRON TYPE IN CROSS VANE STRUCTURE TABLE.




NOTE: CHINK SMALLER STONES INTO GAPS TO ENSURE TIGHT FIT

CHOKE STANDARD APRON (STD) MIX OR RIFFLE GRADE CONTROL (RGC) MIX WITH SALVAGED STREAMBED MATERIAL, IF AVAILABLE. OTHERWISE USE FURNISHED STREAMBED MATERIAL (SBM) MIX.

RIFFLE GRADE CONTROL (RGC) MIX		
% MIX	SHA CLASS 0	30%
	SHA CLASS 1	60%
	SALVAGED STREAMBED MATERIAL	10%

STANDARD APRON (STD) MIX		
% MIX	SHA CLASS 0	60%
	SHA CLASS 1	40%

FURNISHED STREAMBED MATERIAL (SBM) MIX		
% MIX	SHA BANK RUN GRAVEL-BASE	30%
	1"-2" RIVER GRAVEL	40%
	3"-7" RIVER STONE	30%



NOTES:

1. ALL DIMENSION/ELEVATIONS TO BE FIELD ADJUSTED TO ENSURE STABLE INSTALLATION, FISH PASSAGE, AND TIE-IN TO BANKS.
2. ROCK SHALL BE RECTANGULAR BLOCK SHAPE.
3. THE MINIMUM ELEVATION DIFFERENCE BETWEEN ELEVATION "X" AND ELEVATION "Y" IS 4-INCHES.
4. HEADER AND FOOTER ROCKS SHALL BE APPROVED IN THE FIELD BY THE ENGINEER PRIOR TO INSTALLATION.
5. STONE PLACEMENT SHALL BE FIELD ADJUSTED TO CREATE BOWL SHAPE AND TO ENSURE STONE WILL REMAIN IN PLACE OVER FULL RANGE OF FLOW CONDITIONS.
6. REPLACEMENT OF HEADER ROCKS MAY BE REQUIRED BASED UPON INSPECTION OF COMPLETED INSTALLATION TO MEET DESIGN INTENT AND PERMIT REQUIREMENTS.
7. TIE IN SILLS SHALL EXTEND 4' MINIMUM INTO STABLE CHANNEL BANK.
8. ROCKS SHALL BE TIGHT FITTING WITH NO VOIDS/GAPS LARGER THAN 4 INCHES. VOIDS ALONG APEX AND VANE ARMS SHALL BE CHINKED IN WITH SMALLER NON-WEATHERING STONE.
9. UNLESS OTHERWISE NOTED, SALVAGED STREAMBED MATERIAL SHALL BE USED IF AVAILABLE. OTHERWISE USE FURNISHED STREAMBED MATERIAL (SBM) MIX AS NECESSARY.
10. STATION REFERENCE POINT "X" IS LOCATED AT CENTER OF CHANNEL UNLESS SPECIFIED OTHERWISE.


CROSS VANE DETAIL 1.1
NOT TO SCALE

CROSS VANE STRUCTURE SCHEDULE																							
STR. ID.	STA.	OFFSET (FT)	A (FT)	B (FT)	C (FT)	E (LEFT BANK) (FT)	F (RIGHT BANK) (FT)	Ls (FT)	X (MSL)	Y (LEFT BANK)			Y (RIGHT BANK)			Z (MSL)	APEX APRON TYPE	HEADER ROCK DIMENSIONS			FOOTER ROCK DIMENSIONS		
										ELEV (MSL)	STA.	OFFSET (FT)	ELEV (MSL)	STA.	OFFSET (FT)			LENGTH (L)	HEIGHT (H)	WIDTH (W)	LENGTH (L)	HEIGHT (H)	WIDTH (W)
CV-01	1+78.95	0.0	6.0	11.45	12.0	4.0	4.0	10.17	85.67	86.74	1+90.60	-7.75	86.65	1+90.83	8.20	85.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-02	2+29.86	0.0	6.0	15.52	12.0	4.0	4.0	15.81	85.00	85.53	2+41.70	-7.45	85.80	2+42.00	7.36	84.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-03	3+07.65	0.0	6.0	13.95	12.0	4.0	4.0	10.03	83.50	84.52	3+23.40	-8.60	84.45	3+22.80	7.50	83.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-04	3+61.46	0.0	6.0	15.85	12.0	4.0	4.0	12.77	83.00	83.90	3+76.80	-8.13	84.11	3+76.75	8.60	82.50	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-05	4+25.97	0.0	6.0	14.95	12.0	4.0	4.0	10.04	82.00	82.90	4+42.20	-11.32	83.00	4+43.25	10.15	81.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-06	4+76.01	0.0	6.0	15.07	12.0	4.0	4.0	10.04	81.00	81.73	4+87.25	-9.95	82.40	4+93.00	9.95	80.01	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-07	5+59.83	0.0	6.0	15.07	12.0	4.0	4.0	13.05	79.05	81.22	5+72.25	-8.11	80.60	5+73.12	6.75	78.40	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-08	8+53.82	0.0	6.0	14.45	12.0	4.0	4.0	10.04	72.52	73.10	8+65.00	-8.30	73.10	8+65.12	8.30	71.52	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-09	8+94.41	0.0	6.0	14.45	12.0	4.0	4.0	9.86	71.52	72.00	9+06.41	-8.75	72.00	9+05.76	8.21	70.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-10	9+34.42	0.0	6.0	15.00	12.0	4.0	4.0	10.02	70.53	71.00	9+43.64	-7.56	71.00	9+46.26	10.70	69.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-11	9+75.00	0.0	6.0	14.75	12.0	4.0	4.0	9.86	69.53	71.00	9+90.45	-10.85	70.50	9+88.30	9.46	68.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-12	10+95.66	0.0	6.0	14.50	12.0	4.0	4.0	10.04	66.53	67.00	11+12.42	-10.05	67.00	11+10.00	6.75	66.03	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-13	15+97.04	0.0	6.0	15.15	12.0	4.0	4.0	10.84	47.99	48.50	16+10.04	-8.15	49.45	16+11.10	10.00	47.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-14	16+85.78	0.0	6.0	14.00	12.0	4.0	4.0	14.09	46.00	46.60	16+98.55	-10.75	47.00	16+99.21	9.12	45.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-15	17+75.61	0.0	6.0	16.20	12.0	4.0	4.0	14.10	43.00	44.06	17+87.65	-9.11	43.80	17+83.77	6.74	42.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-16	18+12.55	0.0	6.0	16.70	12.0	4.0	4.0	17.40	42.00	42.80	18+20.03	-7.97	44.50	18+26.18	8.70	40.99	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
CV-17	18+52.71	0.0	6.0	14.30	12.0	4.0	4.0	14.88	40.99	41.60	18+61.32	-6.70	41.92	18+63.28	7.56	40.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"


EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		DETAILS - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	----
Reviewed By :	GWF	Sheet	44 Of 78
		Date :	2/16/2022

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. : DE-A1



THALWEG PROFILE




SECTION L-L

NOTES:

1. HEADER AND FOOTER ROCK SIZES TO BE AS PER STEP POOL STRUCTURE TABLE AND WITH ANGULAR SHAPE.
2. SELECT HEADER ROCKS AT INVERT (X) TO BE LARGEST OF THE HEADER ROCKS.
3. FIELD ADJUST ROCK PLACEMENT TO ENSURE STABLE FLOW PATH AND TRANSITION INTO ADJACENT BANKS..


STANDARD APRON (STD) MIX		
% MIX	SHA CLASS 0	60%
% MIX	SHA CLASS 1	40%

FURNISHED STREAMBED MATERIAL (SBM) MIX		
% MIX	SHA BANK RUN GRAVEL-BASE	30%
% MIX	1"-2" RIVER GRAVEL	40%
% MIX	3"-7" RIVER STONE	30%



PLAN VIEW - STEP POOL

1. BEGIN AT THE BOTTOM OF THE SLOPE, WORKING FROM DOWNSTREAM UP, AND ANCHOR FIBER MATTING IN A 12" DEEP INITIAL ANCHOR TRENCH. BACKFILL TRENCH AND TAMP EARTH FIRM.
2. OVERLAP EDGES OF ADJACENT PARALLEL ROLLS 12" AND ANCHOR AT 12" CENTERS WITH THE UPPER ROLL OVERLAPPING THE TOP OF THE LOWER ROLL.
3. WHEN FIBER MAT MUST BE SPLICED, PLACE END OVER END (SHINGLE STYLE IN DIRECTION OF FLOW) WITH 12" OVERLAP AND ANCHOR USING WOODEN STAKES AT 24" INTERVALS. ADDITIONAL FASTENING MAY BE REQUIRED WHERE MATTING IS CUT TO INSTALL PLANTINGS.
4. LAY FIBER MAT LOOSELY AND ANCHOR SUFFICIENTLY TO MAINTAIN DIRECT CONTACT WITH THE SOIL - DO NOT STRETCH.
5. FOR SLOPES 2:1 AND STEEPER, PLACE WOODEN STAKES IN ALTERNATING ROWS AT THREE (3') FOOT INTERVALS ACROSS THE MATTING AND FOR SLOPES FLATTER THAN 2:1, PLACE WOODEN STAKES IN ALTERNATING ROWS AT FOUR (4') FOOT INTERVALS ACROSS THE MATTING.
6. WOOD STAKES SHALL BE ANGLED SUCH THAT EXPOSED PORTION (2"x4") FACES UPSTREAM.
7. ANCHOR, FILL, AND COMPACT END OF FIBER MATTING IN 6"x6" TERMINAL ANCHOR TRENCH ANCHORING DIMENSIONS TO BE REDUCED IN AREAS OF NATURAL RESOURCES TO BE PROTECTED.



TYPE D SOIL STABILIZATION MATTING (BIO-D 70, OR EQUAL)

NOT TO SCALE

STEP POOL DETAIL

NOT TO SCALE

2.1

STR. #	STA.	OFFSET	X (TOP ELEV.)	Lp (STEP SPACING)	"B" BANKFULL WIDTH (FT)	"C" TOE WIDTH (FT)	LEFT BANK TIE IN "Y"		RIGHT BANK TIE IN "Y"		TOP ROCK DIMENSIONS			FOOTER ROCK DIMENSIONS		
							OFFSET	ELEV.	OFFSET	ELEV.	LENGTH (L)	HEIGHT (H)	WIDTH (W)	LENGTH (L)	HEIGHT (H)	WIDTH (W)
							SP-01	11+42.70	0.0	65.03	19.27	13.50	6.0	-6.75	66.00	6.75
SP-02	11+61.97	0.0	64.03	19.05	13.50	6.0	-6.75	65.00	6.75	65.00	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-03	12+61.64	0.0	61.03	19.09	13.50	6.0	-6.75	61.80	6.75	62.00	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-04	12+80.73	0.0	60.03	19.23	13.50	6.0	-6.75	61.00	6.75	61.00	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-05	13+87.08	0.0	56.75	19.15	20.35	6.0	-13.60	57.75	6.75	57.75	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-06	14+06.23	0.0	55.75	19.13	13.50	6.0	-6.75	56.75	6.75	56.75	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-07	14+25.36	0.0	54.76	19.16	13.50	6.0	-6.75	56.00	6.75	56.00	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-08	14+44.52	0.0	53.76	22.02	13.50	6.0	-6.75	55.00	6.75	55.00	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-09	14+66.54	0.0	53.00	19.12	13.50	6.0	-6.75	54.15	6.75	54.15	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-10	14+85.66	0.0	52.00	19.21	13.50	6.0	-6.75	53.15	6.75	53.15	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-11	15+04.87	0.0	51.00	19.16	13.50	6.0	-6.75	52.15	6.75	52.15	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-12	17+26.01	0.0	45.00	21.19	13.50	6.0	-6.75	45.85	6.75	46.10	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-13	17+47.20	0.0	44.00	28.41	13.50	6.0	-6.75	44.95	6.75	45.20	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"
SP-14	18+89.46	0.0	40.00	14.97	16.90	6.0	-8.15	41.50	8.75	41.5	18"-24"	12"-18"	18"-24"	30"-36"	12"-18"	24"-30"

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
DETAILS - STREAM			
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	----
Reviewed By :	GWF	Sheet	45 Of 78
		Date :	2/16/2022

DE-A2




ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE: 1"=10'



NOTES:

- SILL SHALL BE CONSTRUCTED BY EXCAVATING A TRENCH SLIGHTLY LARGER THAN THE SILL DIMENSIONS.
- TOP ROCKS SHALL BE SUPPORTED BY A FOOTER ROCK AND SHINGLED UPSTREAM AND INTO STREAM BANK. ALL ROCKS SHALL BE INTERLOCKED MINIMIZING OR ELIMINATING GAPS WITH NO VOIDS/GAPS LARGER THAN 4 INCHES.
- PLACE GEOTEXTILE (NON-WOVEN) ON UPSTREAM SIDE OF SILL. FABRIC SHALL COVER THE UPSTREAM FACE OF THE ENTIRE SILL.
- DISTURBED STREAMBED UPSTREAM OF SILL SHALL BE BACKFILLED WITH 10" MIN. OF STANDARD APRON (STD) MIX OR RIFFLE GRADE CONTROL (RGC) MIX TO MEET EXISTING GRADE.
- STREAM BANK AROUND STRUCTURE SHALL BE BACKFILLED AND HAND COMPACTED.
- SEE STRUCTURE TABLE, PROFILE, AND GRADING SHEET FOR ALL DIMENSIONS AND ELEVATIONS.
- SILL ROCKS SHALL BE FLUSH WITH FINISHED GRADE AND CUTOFF ROCKS SHALL EXTEND A MINIMUM OF 4 FEET INTO STREAMBANK UNLESS SILL IS REPLACED WITH IMBRICATED ROCK WALL.
- PROVIDE DROP ROCKS DOWNSTREAM OF SILL PER DETAIL.

ROCK SILL DETAIL 6.1
NO SCALE





ROCK SILL STRUCTURE SCHEDULE																	
STR. #	STA.	OFFSET	INVERT ELEV. "X"	SILL LENGTH "A"	TIE IN WIDTH "B"	TOE WIDTH "C"	TIE-IN ELEV. (LEFT) "Y"	TIE-IN ELEV. (RIGHT) "Y"	BANKFULL ELEV.	APEX APRON TYPE	DROP ROCK TOP ELEV.	HEADER ROCK DIMENSIONS			FOOTER ROCK DIMENSIONS		
												LENGTH (L)	HEIGHT (H)	WIDTH (W)	LENGTH (L)	HEIGHT (H)	WIDTH (W)
RS-01	19+04.43	0	38.75	0.75	18.50	6.0	40.67	41.66	0.99	STD	37.3	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	DETAILS - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____
Reviewed By : _____	GWF	Sheet <u>46</u> Of <u>78</u>
		Date : <u>2/16/2022</u>

DE-A3

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: SCALE: 1"=10'



NOTES:

1. COMPACT SALVAGED STREAMBED MATERIAL BACKFILL TO MATCH PRE-CONSTRUCTION GRADE UNLESS OTHERWISE SPECIFIED.
2. RIFFLE GRADE CONTROL STRUCTURE FEATURES SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN IN THIS DETAIL UNLESS OTHERWISE NOTED ON THE STRUCTURE TABLE, CROSS SECTION, AND PROFILES PLAN SHEETS.
3. CROSS-SECTIONAL DIMENSIONS AND LONGITUDINAL SPACING OF FEATURES VARY. SEE STRUCTURE TABLES, CROSS SECTIONS, AND PROFILES FOR DIMENSIONS OF EACH INDIVIDUAL STRUCTURE.
4. RIFFLE GRADE CONTROL (RGC) MIX MUST BE PLACED IN A MANNER TO PROMOTE INTERLOCKING. DUMPING OF RIPRAP SHALL NOT BE PERMITTED.
5. RIFFLE GRADE CONTROL (RGC) MIX SHALL BE PLACED IN TWO SEPARATE LIFTS. VOIDS BETWEEN SMALLER AND LARGER STONES SHALL BE MINIMIZED.
6. AFTER PLACEMENT OF FIRST LIFT, BACKWASH WITH SALVAGED STREAMBED MATERIAL AND WATER.
7. THE SECOND LIFT SHALL BE BACKWASHED AND CHOKED WITH SALVAGED STREAMBED MATERIAL IF AVAILABLE AND SUPPLEMENTED WITH FURNISHED STREAMBED MATERIAL (SBM) MIX WHEN SALVAGED MATERIAL IS NOT AVAILABLE.
8. THALWEG MAY BE MODIFIED IN FIELD PER DIRECTION OF THE ENGINEER.



RIFFLE GRADE CONTROL (RGC) MIX	
MIX	SHA CLASS 0 30%
MIX	SHA CLASS 1 60%
%	SALVAGED STREAMBED MATERIAL 10%

FURNISHED STREAMBED MATERIAL (SBM) MIX	
MIX	SHA BANK RUN GRAVEL-BASE 30%
MIX	1\"/>

RIFFLE GRADE CONTROL (RGC) WITH WOOD DETAIL 4.1
NOT TO SCALE

- INSTALLATION NOTES**
1. TREE LIMBS SHALL RANGE FROM 4\"/>

SMALL TREE LIMB PLACEMENT DETAIL 4.2
NOT TO SCALE



STR. #	UPSTREAM			DOWNSTREAM			WIDTH (FT)	LENGTH (FT)	AREA (FT ²)	SLOPE (FT/FT)
	STA.	OFFSET	ELEV.	STA.	OFFSET	ELEV.				
RCC-01	2+83.33	0.00	84	3+06.62	0.00	83.5	10.0	23.29	232.90	0.021
RCC-02	4+00.72	0.00	82.5	4+24.97	0.00	82	10.0	24.25	242.50	0.021
RCC-03	5+23.64	0.00	80.01	5+58.83	0.00	79.05	10.0	35.19	351.90	0.027
RCC-04	6+18.91	0.00	78.4	6+42.43	0.00	77.71	10.0	23.52	235.20	0.029
RCC-05	13+37.48	0.00	58.03	13+49.52	0.00	57.75	10.0	12.04	120.40	0.023
RCC-06	19+05.43	0.00	38.75	19+15.66	0.00	38.37	10.0	10.23	102.30	0.037

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	DETAILS - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____
Reviewed By : _____	GWF	Sheet <u>47</u> Of <u>78</u>
		Date : <u>2/16/2022</u>


ADC MAP : TAX MAP : HCC BILLING ID No. : HCC DWG ID No. : SCALE: 1"=10'

DE-A4

STANDARD APRON (STD) MIX OR RIFFLE GRADE CONTROL (RGC) MIX PLACED UPSTREAM OF APEX STONES. MIX TYPE IS INDICATED UNDER APEX APRON TYPE IN J-HOOK STRUCTURE TABLE.

NOTE: CHINK SMALLER STONES INTO GAPS TO ENSURE TIGHT FIT

CHOKE STANDARD APRON (STD) MIX OR RIFFLE GRADE CONTROL (RGC) MIX WITH SALVAGED STREAMBED MATERIAL, IF AVAILABLE. OTHERWISE USE FURNISHED STREAMBED MATERIAL (SBM) MIX.




PLAN VIEW
(NOT TO SCALE)

RIFFLE GRADE CONTROL (RGC) MIX		
% MIX	SHA CLASS 0	30%
	SHA CLASS 1	60%
	SALVAGED STREAMBED MATERIAL	10%


STANDARD APRON (STD) MIX		
% MIX	SHA CLASS 0	60%
	SHA CLASS 1	40%

FURNISHED STREAMBED MATERIAL (SBM) MIX		
% MIX	SHA BANK RUN GRAVEL-BASE	30%
	1"-2" RIVER GRAVEL	40%
	3"-7" RIVER STONE	30%



NOTE: J-HOOK STONE SHOWN IN THIS VIEW IS FOR PERSPECTIVE

CROSS SECTION C-C
(NOT TO SCALE)



SECTION D-D
PROFILE VIEW
(NOT TO SCALE)

J-HOOK DETAIL
NOT TO SCALE





J-HOOK STRUCTURE SCHEDULE																							
STR. #	STA.	OFFSET	A (FT)	B (FT)	C (FT)	F (SHORT ARM) (FT)	E (LONG ARM) (FT)	Ls (FT)	X (MSL)	V (Short Arm)			Y (Long Arm)			Z (MSL)	APEX APRON TYPE	HEADER ROCK DIMENSIONS			FOOTER ROCK DIMENSIONS		
										ELEV (MSL)	STA.	OFFSET (FT)	ELEV (MSL)	STA.	OFFSET (FT)			LENGTH (L)	HEIGHT (H)	WIDTH (W)	LENGTH (L)	HEIGHT (H)	WIDTH (W)
JH-01	6+43.43	0.0	6.0	12.0	8.0	2.0	4.0	10.04	77.71	78.15	6+51.81	7.3	78.17	6+50.30	-9.53	76.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-02	6+92.49	0.0	6.0	12.0	8.0	2.0	4.0	10.04	76.53	77.00	6+99.55	-6.15	77.00	7+01.30	13.85	75.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-03	7+33.23	0.0	6.0	12.0	8.0	2.0	4.0	9.91	75.53	76.04	7+39.70	5.81	76.00	7+43.15	-8.06	74.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-04	7+73.18	0.0	6.0	12.0	8.0	2.0	4.0	10.05	74.53	75.20	7+77.25	-8.01	75.13	7+81.60	6.75	73.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-05	8+13.60	0.0	6.0	12.0	8.0	2.0	4.0	9.87	73.53	74.00	8+20.60	-5.70	74.50	8+21.01	8.31	72.52	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-06	10+15.04	0.0	6.0	12.0	8.0	2.0	4.0	10.03	68.53	69.00	10+23.14	5.97	69.00	10+23.81	-8.20	67.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-07	10+55.65	0.0	6.0	12.0	8.0	2.0	4.0	9.86	67.53	68.00	10+61.85	-5.65	68.00	10+65.40	10.02	66.53	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-08	11+23.44	0.0	6.0	12.0	8.0	2.0	4.0	5.86	66.03	66.75	11+26.60	-6.50	66.45	11+34.70	9.43	65.03	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-09	11+81.02	0.0	6.0	12.0	8.0	2.0	4.0	10.02	63.03	64.00	11+84.75	7.34	63.42	11+92.30	-10.10	62.04	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-10	12+21.55	0.0	6.0	12.0	8.0	2.0	4.0	9.89	62.04	62.72	12+25.50	-8.30	63.00	12+33.45	9.20	61.03	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-11	12+99.96	0.0	6.0	12.0	8.0	2.0	4.0	9.86	59.04	59.70	13+05.75	-7.09	60.15	13+09.80	8.34	58.03	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-12	13+50.53	0.0	6.0	12.0	8.0	2.0	4.0	16.5	57.75	58.50	13+56.35	6.57	58.20	13+60.75	-8.80	56.75	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-13	15+24.03	0.0	6.0	12.0	8.0	2.0	4.0	9.84	50.01	50.85	15+28.50	6.50	51.32	15+35.00	-8.50	48.99	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-14	15+60.46	0.0	6.0	12.0	8.0	2.0	4.0	9.86	48.99	49.80	15+66.00	6.42	50.35	15+73.22	-11.40	47.99	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"
JH-15	16+51.36	0.0	6.0	12.0	8.0	2.0	4.0	7.58	47.00	47.75	16+55.09	-6.94	48.06	16+56.50	9.11	46.00	STD	18"-24"	12"-18"	18"-24"	24"-36"	18"-24"	24"-30"

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	DETAILS - STREAM	
	Drawn By : <u> LBT </u> Designed By : <u> MCB </u> Reviewed By : <u> GWF </u>	Contract No : <u> DP1602779 </u> Scale : <u> ---- </u> Sheet <u> 48 </u> Of <u> 78 </u> Date : <u> 2/16/2022 </u>

DE-A5

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: SCALE: 1"=10'



IMBRICATED RIPRAP WALL DETAIL 6.2
NOT TO SCALE

STR. #	IMBRICATED RIPRAP WALL STRUCTURE SCHEDULE																		WALL LENGTH	WALL SLOPE	HEADER ROCK DIMENSIONS			FOOTER ROCK DIMENSIONS		
	UPSTREAM						DOWNSTREAM						BANKFULL DEPTH (FT)	BANKFULL DEPTH (FT)	LENGTH (L)	HEIGHT (H)	WIDTH (W)	LENGTH (L)			HEIGHT (H)	WIDTH (W)				
	STA.	OFFSET	INVERT ELEV.	STA.	OFFSET	TOP ELEV.	STA.	OFFSET	INVERT ELEV.	STA.	OFFSET	TOP ELEV.											FOOTER BOTTOM ELEV.	FOOTER BOTTOM ELEV.	LENGTH (L)	HEIGHT (H)
IRR-01	18+54.08	-7.21	40.50	18+54.08	-9.70	44.00	38.50	0.99	18+87.47	-7.93	38.75	18+87.47	-10.55	45.42	36.8	0.99	78.0	1:6	30"-36"	18"-24"	24"-30"	36"-48"	18"-24"	24"-30"		
IRR-02	18+54.41	7.70	40.50	18+54.41	10.03	45.73	38.50	0.99	19+03.18	10.07	38.65	19+03.18	12.65	47.87	36.7	0.99	74.0	1:6	30"-36"	18"-24"	24"-30"	36"-48"	18"-24"	24"-30"		

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	DETAILS - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____
Reviewed By : _____	GWF	Sheet <u>49</u> Of <u>78</u>
		Date : <u>2/16/2022</u>


DE-A6

ADC MAP :

TAX MAP :

HCG BILLING ID No.:


HCG DWG ID No.:



SUBMERGED GRAVEL WETLAND SECTION (UNDERDRAIN TO WEIR WALL)

NOT TO SCALE

* NOTE:
AT ELEV. 81.5 MARK THE C.O. PVC SCH 40 PIPE WITH PAINT TO INDICATE FORBAY REQUIRED CLEANING.



SUBMERGED GRAVEL WETLAND TYPICAL SECTION (A-A)

NOT TO SCALE


IN-LINE CLEANOUT DETAIL AT SOUTH FORBAY

NOT TO SCALE

STRUCTURAL NOTES


- DESIGN CODES**
ALL CONSTRUCTION SHALL CONFORM WITH THE 2012 INTERNATIONAL BUILDING CODE AND ALL SUBSEQUENT SUPPLEMENTS, IN ADDITION TO ACI 318-#5 AND ACI 350-06.
- CAST IN PLACE CONCRETE**
 - ALL CONCRETE CONSTRUCTION SHALL CONFORM TO THE CODE REQUIREMENTS FOR ENVIRONMENTAL ENGINEERING CONCRETE STRUCTURES (ACI 350-06 AND ACI 318-#5).
 - ALL CONCRETE, UNLESS OTHERWISE NOTED, SHALL BE STONE AGGREGATE CONCRETE HAVING A MINIMUM 28 DAY CONCRETE COMPRESSIVE STRENGTH OF 4,000 PSI (SHA MIX NO. 6). ALL CONCRETE EXPOSED TO WEATHER SHALL BE AIR ENTRAINED FOR SEVERE EXPOSURE.
 - ALL REINFORCING STEEL BARS SHALL BE NEW BILLET STEEL CONFORMING TO ASTM A 615 GRADE 60. UNLESS OTHERWISE NOTED, THE MINIMUM TYPICAL LAP SPICES ARE AS SHOWN BELOW:

#4	2'-0"
#5	2'-6"
#6	3'-0"
#7	3'-6"
#8	3'-11"
 - MINIMUM COVER FOR ALL REINFORCING STEEL SHALL BE AS FOLLOWS UNLESS OTHERWISE NOTED:
CONCRETE CAST AGAINST SOIL 3"
ELSEWHERE 2"
- FOUNDATIONS**
 - ALL FOUNDATIONS HAVE BEEN DESIGNED FOR AN ASSUMED NET ALLOWABLE SOIL BEARING PRESSURE OF 2,000 PSF. THE ALLOWABLE SOIL BEARING PRESSURE SHALL BE FIELD VERIFIED BY A REGISTERED GEOTECHNICAL ENGINEER AND APPROVED PRIOR TO PLACING FOUNDATIONS. SHOULD THE ACTUAL SOIL BEARING PRESSURE BE LESS THAN 2,000 PSF THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER.
 - SPILLWAY MUST BE CONSTRUCTED ON SUBGRADE APPROVED BY GEOTECHNICAL ENGINEER. A GRAVEL SUBGRADE IS NOT ALLOWABLE, USE MUDMAT IF NECESSARY.
- SPILLWAY DESIGN**
 - SPILLWAY HAS BEEN DESIGNED WITH BACKFILL MATERIAL HAVING THE FOLLOWING CHARACTERISTICS: EARTH PRESSURE CALCULATED BASED ON EQUIVALENT FLUID PRESSURE OF 60 H SOIL WEIGHT = 120 PCF.
 - SPILLWAY HAS BEEN DESIGNED FOR THE MINIMUM FACTOR OF SAFETY OF 1.2 FOR BUOYANCY AT THE PERMANENT CONDITION.
- MISCELLANEOUS**
 - ALL CONNECTIONS SHALL BE WATER TIGHT. PROVIDE PVC TYPE WATERSTOP IN THE CONSTRUCTION JOINT BETWEEN THE SPILLWAY BASE AND WALLS.
 - THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS SHOWN ON THE CONTRACT DRAWINGS BEFORE PROCEEDING WITH CONSTRUCTION. ALL DISCREPANCIES AND OMISSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
 - CONTRACTOR SHALL NOT SUBMIT REPRODUCTIONS OF THE STRUCTURAL CONTRACT DOCUMENTS AS SHOP DRAWINGS. CONTRACTOR SHALL SUBMIT REINFORCEMENT STEEL DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO PROCURING OR FABRICATING STEEL.




WEIR WALL DETAIL

NOT TO SCALE




CONCRETE WEIR WALL SECTION

NOT TO SCALE



TERMINAL CLEANOUT DETAIL

NOT TO SCALE



OBSERVATION WELL DETAIL WITHIN (SGW)

NOT TO SCALE

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		DETAILS - SWM	
Drawn By :	JS / MTB	Contract No :	DP1602779
Designed By :	JS / MTB	Scale :	AS SHOWN
Reviewed By :	MAE	Sheet	50 Of 78
		Date :	2/16/2022


ADC MAP :

TAX MAP :

HCG BILLING ID No.:


HCG DWG ID No.:

DE-B1




EXISTING SUBMERGED GRAVEL WETLAND BASELINE PROFILE

SCALE: HORZ 1" = 30'
VERT. 1" = 3'



EXISTING SUBMERGED GRAVEL WETLAND EMBANKMENT CENTERLINE PROFILE


SCALE: HORZ 1" = 30'
VERT. 1" = 3'



CORE TRENCH TYPICAL SECTION

NOT TO SCALE

DRAINAGE AREA CONTRIBUTING	STRUCTURE CLASSIFICATION	Q10 AND Q100 MANAGEMENT	STORAGE VOLUME AT TOP OF DAM	STORAGE VOLUME AT OUTFALL WEIR	EFFECTIVE HEIGHT OF EMBANKMENT	TOP WIDTH OF EMBANKMENT	Q IN AND OUT FOR 10 YR. STORM EVENT	Q IN AND OUT FOR 100 YR. STORM EVENT	FREEBOARD PROVIDED
5.99 ac.	CLASS "a" 12,904 cu.ft.	N/A & N/A	40,280 cu.ft.	12,904 cu.ft.	6.58'	7'-0" (min.)	(IN) 35.98 cfs (OUT) 28.19 cfs	(IN) 66.39 cfs (OUT) 60.36 cfs	1.26'



EXISTING EMERGENCY SPILLWAY CENTERLINE PROFILE

SCALE: HORZ 1" = 30'
VERT. 1" = 3'

EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
DETAILS - SWM			
Drawn By : JS / MTB	Contract No : DP1602779		
Designed By : JS / MTB	Scale : AS SHOWN		
Reviewed By : MAE	Sheet 51 Of 78		
	Date : 2/16/2022		


ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

DE-B2



INFILTRATION TRENCH PROFILE
SCALE: HORZ 1" = 30'
VERT. 1" = 3'

NYLOPLAST 12" DRAIN BASIN: 2812AG __ X

STRUCTURES: IN-1, IN-2, IN-3, IN-4, IN-5

(1, 2) INTEGRATED DUCTILE IRON FRAME & GRATE TO MATCH BASIN O.D.

(3) VARIABLE INVERT HEIGHTS AVAILABLE (ACCORDING TO PLAN/STAKE OFF)

(4) VARIOUS TYPES OF INLET & OUTLET ADAPTERS AVAILABLE: 4" - 12" FOR CORRUGATED HDPE (ADS N-12HANCOR DUAL WALL, ADSHANCOR SINGLE WALL), N-12 HP PVC SEWER (EX: SDR 35), PVC DWV (EX: SCH 40), PVC C900/C805, CORRUGATED & RIBBED PVC

TRAFFIC LOADS: CONCRETE SLAB DIMENSIONS ARE FOR GUIDELINE PURPOSES ONLY. ACTUAL CONCRETE SLAB MUST BE DESIGNED TAKING INTO CONSIDERATION LOCAL SOIL CONDITIONS, TRAFFIC LOADING, & OTHER APPLICABLE DESIGN FACTORS. SEE DRAWING NO. 7001-110-111 FOR NON TRAFFIC INSTALLATION.

GRATE OPTIONS	LOAD RATING	PART #	DRAWING #
PEDESTRIAN	MEETS H-10	1296CGP	7001-110-202
STANDARD	MEETS H-20	1296CGS	7001-110-203
SOLID COVER	MEETS H-30	1296CGT	7001-110-204
PEDESTRIAN BRONZE	N/A	1296CGP8	7001-110-205
DOME	N/A	1296CGD	7001-110-206
DROP IN GRATE	LIGHT DUTY	1201GR	7001-110-201

1 - GRATES/SOLID COVER SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-90-05 WITH THE EXCEPTION OF THE BRONZE GRATE.

2 - FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-90-05

3 - DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS. RISERS ARE NEEDED FOR BASINS OVER 8' DUE TO SHIPPING RESTRICTIONS. SEE DRAWING NO. 7001-110-065

4 - DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D2122 FOR CORRUGATED HDPE (ADS N-12HANCOR DUAL WALL, N-12 HP, & PVC SERIES)

5 - ADAPTERS CAN BE MOUNTED ON ANY ANGLE 0° TO 360°. TO DETERMINE MINIMUM ANGLE BETWEEN ADAPTERS SEE DRAWING NO. 7001-110-012

THIS PRINT DISCLOSES SUBJECT MATTER IN WHICH NYLOPLAST HAS PROPRIETARY RIGHTS. THE RECEIPT OR POSSESSION OF THIS PRINT DOES NOT CONFER, TRANSFER, OR LICENSE THE USE OF THE DESIGN OR TECHNICAL INFORMATION SHOWN HEREIN. REPRODUCTION OF THIS PRINT OR ANY INFORMATION CONTAINED HEREIN, OR MANUFACTURE OF ANY ARTICLE HEREFROM, FOR THE DISCLOSURE TO OTHERS IS FORBIDDEN, EXCEPT BY SPECIFIC WRITTEN PERMISSION FROM NYLOPLAST.

3130 VERONA AVE
BUFFORD, GA 30518
P/N (770) 933-2443
FAX (770) 933-2480
www.nyloplast-us.com

Nyloplast

DRAWN BY: EBC DATE: 03-29-06
REVISOR: NMM PROJECT NO: NAME
DATE: 03-11-16
DWG SIZE: A SCALE: 1:20 SHEET: 1 OF 1 DWG NO.: 7001-110-189 REV: E

WHEN ARE INLINE DRAINS USED?

2708AG __ X
2710AG __ X
2712AG __ X
2715AG __ X
2718AG __ X
2724AG __ X
2730AG __ X

TYPICAL INSTALLATIONS

1: TO ENTER AN EXISTING LINE USING A TEE & RISER

2: AT THE BEGINNING OF A DRAIN LINE USING AN ELBOW & RISER

3: VARIABLE ELEVATION

4: FOR SHALLOW APPLICATIONS

5: TO CHANGE DIRECTION

WHEN ARE DRAIN BASINS USED?

1: TO CHANGE ELEVATION

2: TO CHANGE PIPE DIAMETER

3: TO CHANGE PIPE TYPE

4: FOR SHALLOW APPLICATIONS

5: TO CHANGE DIRECTION

1 - STRUCTURES & ADAPTERS AVAILABLE IN SIZES 8" - 30"

2 - ADAPTERS CAN BE MOUNTED ON ANY ANGLE 0° TO 360°. TO DETERMINE MINIMUM ANGLE BETWEEN ADAPTERS SEE DRAWING NO. 7001-110-012

3 - DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS. RISERS ARE NEEDED FOR BASINS OVER 8' DUE TO SHIPPING RESTRICTIONS. SEE DRAWING NO. 7001-110-065

THIS PRINT DISCLOSES SUBJECT MATTER IN WHICH NYLOPLAST HAS PROPRIETARY RIGHTS. THE RECEIPT OR POSSESSION OF THIS PRINT DOES NOT CONFER, TRANSFER, OR LICENSE THE USE OF THE DESIGN OR TECHNICAL INFORMATION SHOWN HEREIN. REPRODUCTION OF THIS PRINT OR ANY INFORMATION CONTAINED HEREIN, OR MANUFACTURE OF ANY ARTICLE HEREFROM, FOR THE DISCLOSURE TO OTHERS IS FORBIDDEN, EXCEPT BY SPECIFIC WRITTEN PERMISSION FROM NYLOPLAST.

3130 VERONA AVE
BUFFORD, GA 30518
P/N (770) 933-2443
FAX (770) 933-2480
www.nyloplast-us.com

Nyloplast

DRAWN BY: AWA MATERIAL: DATE: 8-16-00
REVISOR: EBC PROJECT NO: NAME
DATE: 1-8-10
DWG SIZE: A SCALE: 1:40 SHEET: 1 OF 1 DWG NO.: 7001-110-042 REV: D

DRAIN BASIN DETAILS

NOT TO SCALE

1

NOTE:
USE PVC SCH. 40 FOR ALL PIPES IN AND OUT OF NYLOPLAST OR (APPROVE EQUAL) DRAIN BASIN.

EG-SWMENG-000747-2016

Revisions

HARFORD COUNTY, MARYLAND

DETAILS - SWM

Drawn By: JS / MTB Contract No: DP1602779

Designed By: JS / MTB Scale: AS SHOWN

Reviewed By: MAE Sheet 53 Of 78

Date: 2/16/2022

3130 VERONA AVE
BUFFORD, GA 30518
P/N (770) 933-2443
FAX (770) 933-2480
www.nyloplast-us.com

Nyloplast

DRAWN BY: AWA MATERIAL: DATE: 8-16-00
REVISOR: EBC PROJECT NO: NAME
DATE: 1-8-10
DWG SIZE: A SCALE: 1:40 SHEET: 1 OF 1 DWG NO.: 7001-110-042 REV: D

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: DE-B4

MD POND 378 CONSTRUCTION SPECIFICATIONS

THESE SPECIFICATIONS ARE APPROPRIATE TO ALL PONDS WITHIN THE SCOPE OF THE STANDARD FOR PRACTICE MD-378. ALL REFERENCES TO ASTM AND AASHTO SPECIFICATIONS APPLY TO THE MOST RECENT VERSION.

SITE PREPARATION

AREAS DESIGNATED FOR BORROW AREAS, EMBANKMENT, AND STRUCTURAL WORKS SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL, ALL TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED. CHANNEL BANKS AND SHARP BREAKS SHALL BE SLOPED TO NO STEEPER THAN 1:1. ALL TREES SHALL BE CLEARED AND GRUBBED WITHIN 15 FEET OF THE TOE OF THE EMBANKMENT.

AREAS TO BE COVERED BY THE RESERVOIR SHALL BE CLEARED OF ALL TREES, BRUSH, LOGS, FENCES, RUBBISH AND OTHER OBJECTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED ON THE PLANS. TREES, BRUSH, AND STUMPS SHALL BE CUT APPROXIMATELY LEVEL WITH THE GROUND SURFACE. FOR DRY STORMWATER MANAGEMENT PONDS, A MINIMUM OF A 25-FOOT RADIUS AROUND THE INLET STRUCTURE SHALL BE CLEARED.

ALL CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF OUTSIDE AND BELOW THE LIMITS OF THE DAM AND RESERVOIR AS DIRECTED BY THE OWNER OR HIS REPRESENTATIVE. WHEN SPECIFIED, A SUFFICIENT QUANTITY OF TOPSOIL SHALL BE STOCKPILED IN A SUITABLE LOCATION FOR USE ON THE EMBANKMENT AND OTHER DESIGNATED AREAS.

EARTH FILL

MATERIAL—THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREAS. IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBISH, STONES GREATER THAN 6", FROZEN OR OTHER OBJECTIONABLE MATERIALS. FILL MATERIAL FOR THE CENTER OF THE EMBANKMENT, AND CUT OFF TRENCH SHALL CONFORM TO UNIFIED SOIL CLASSIFICATION GC, SC, CH, OR CL AND MUST HAVE AT LEAST 30% PASSING THE #200 SIEVE. CONSIDERATION MAY BE GIVEN TO THE USE OF OTHER MATERIALS IN THE EMBANKMENT IF DESIGNED BY A GEOTECHNICAL ENGINEER. SUCH SPECIAL DESIGNS MUST HAVE CONSTRUCTION SUPERVISED BY A GEOTECHNICAL ENGINEER.

MATERIALS USED IN THE OUTER SHELL OF THE EMBANKMENT MUST HAVE THE CAPABILITY TO SUPPORT VEGETATION OF THE QUALITY REQUIRED TO PREVENT EROSION OF THE EMBANKMENT.

PLACEMENT—AREAS ON WHICH FILL IS TO BE PLACED SHALL BE SCARIFIED PRIOR TO PLACEMENT OF FILL. FILL MATERIALS SHALL BE PLACED IN MAXIMUM 8-INCH-THICK (BEFORE COMPACTION) LAYERS WHICH ARE TO BE CONTINUOUS OVER THE ENTIRE LENGTH OF THE FILL. THE MOST PERMEABLE BORROW MATERIAL SHALL BE PLACED IN THE DOWN STREAM PORTIONS OF THE EMBANKMENT. THE PRINCIPAL SPILLWAY MUST BE INSTALLED CONCURRENTLY WITH FILL PLACEMENT AND NOT EXCAVATED INTO THE EMBANKMENT.

COMPACTION—THE MOVEMENT OF THE HAULING AND SPREADING EQUIPMENT OVER THE FILL SHALL BE CONTROLLED SO THAT THE ENTIRE SURFACE OF EACH LIFT SHALL BE TRAVERSED BY NOT LESS THAN ONE TREAD TRACK OF HEAVY EQUIPMENT OR COMPACTION SHALL BE ACHIEVED BY A MINIMUM OF FOUR COMPLETE PASSES OF A SHEEPSFOOT, RUBBER Tired OR VIBRATORY ROLLER. FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SUCH THAT THE REQUIRED DEGREE OF COMPACTION SHALL BE OBTAINED WITH THE EQUIPMENT USED. THE FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SO THAT IF FORMED INTO A BALL IT WILL NOT CRUMBLE, YET NOT BE SO WET THAT WATER CAN BE SQUEEZED OUT.

WHEN REQUIRED BY THE REVIEWING AGENCY THE MINIMUM REQUIRED DENSITY SHALL NOT BE LESS THAN 95% OF MAXIMUM DRY DENSITY WITH A MOISTURE CONTENT WITHIN 0.02% OF THE OPTIMUM. EACH LAYER OF FILL SHALL BE COMPACTED AS NECESSARY TO OBTAIN THAT DENSITY, AND IS TO BE CERTIFIED BY THE ENGINEER AT THE TIME OF CONSTRUCTION. ALL COMPACTION IS TO BE DETERMINED BY AASHTO METHOD T-99 (STANDARD PROCTOR).

CUT OFF TRENCH—THE CUTOFF TRENCH SHALL BE EXCAVATED INTO IMPERVIOUS MATERIAL ALONG OR PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE BOTTOM WIDTH OF THE TRENCH SHALL BE GOVERNED BY THE EQUIPMENT USED FOR EXCAVATION, WITH THE MINIMUM WIDTH BEING FOUR FEET. THE DEPTH SHALL BE AT LEAST FOUR FEET BELOW EXISTING GRADE OR AS SHOWN ON THE PLANS. THE SIDE SLOPES OF THE TRENCH SHALL BE 1 TO 1 OR FLATTER. THE BACKFILL SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT, ROLLERS, OR HAND TAMPERS TO ASSURE MAXIMUM DENSITY AND MINIMUM PERMEABILITY.

EMBANKMENT CORE—THE CORE SHALL BE PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE TOP WIDTH OF THE CORE SHALL BE A MINIMUM OF FOUR FEET. THE HEIGHT SHALL EXTEND UP TO AT LEAST THE 10 YEAR WATER ELEVATION OR AS SHOWN ON THE PLANS. THE SIDE SLOPES SHALL BE 1 TO 1 OR FLATTER. THE CORE SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT, ROLLERS, OR HAND TAMPERS TO ASSURE MAXIMUM DENSITY AND MINIMUM PERMEABILITY. IN ADDITION, THE CORE SHALL BE PLACED CONCURRENTLY WITH THE OUTER SHELL OF THE EMBANKMENT.

STRUCTURE BACKFILL

BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL NEEDS TO FILL COMPLETELY ALL SPACES UNDER AND ADJACENT TO THE PIPE. AT NO TIME DURING THE BACKFILLING OPERATION SHALL DRIVEN EQUIPMENT BE ALLOWED TO OPERATE CLOSER THAN FOUR FEET, MEASURED HORIZONTALLY, TO ANY PART OF A STRUCTURE. UNDER NO CIRCUMSTANCES SHALL EQUIPMENT BE DRIVEN OVER ANY PART OF A CONCRETE STRUCTURE OR PIPE, UNLESS THERE IS A COMPACTED FILL OF 24" OR GREATER OVER THE STRUCTURE OR PIPE.

STRUCTURE BACKFILL MAY BE FLOWABLE FILL MEETING THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 313 AS MODIFIED. THE MIXTURE SHALL HAVE A 100-200 PSI; 28 DAY UN CONFINED COMPRESSIVE STRENGTH. THE FLOWABLE FILL SHALL HAVE A MINIMUM PH OF 4.0 AND A MINIMUM RESISTIVITY OF 2,000 OHM-CM. MATERIAL SHALL BE PLACED SUCH THAT A MINIMUM OF 6" (MEASURED PERPENDICULAR TO THE OUTSIDE OF THE PIPE) OF FLOWABLE FILL SHALL BE UNDER (BED DING), OVER AND, ON THE SIDES OF THE PIPE. IT ONLY NEEDS TO EXTEND UP TO THE SPRING LINE FOR RIGID CONDUITS. AVERAGE SLUMP OF THE FILL SHALL BE 7" TO ASSURE FLOWABILITY OF THE MATERIAL. ADEQUATE MEASURES SHALL BE TAKEN (SAND BAGS, ETC.) TO PREVENT FLOATING THE PIPE. WHEN USING FLOWABLE FILL, ALL METAL PIPE

SHALL BE BITUMINOUS COATED. ANY ADJOINING SOIL FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL SHALL COMPLETELY FILL ALL VOIDS ADJACENT TO THE FLOWABLE FILL ZONE. AT NO TIME DURING THE BACKFILLING OPERATION SHALL DRIVEN EQUIPMENT BE ALLOWED TO OPERATE CLOSER THAN FOUR FEET, MEASURED HORIZONTALLY, TO ANY PART OF A STRUCTURE. UNDER NO CIRCUMSTANCES SHALL EQUIPMENT BE DRIVEN OVER ANY PART OF A STRUCTURE OR PIPE UNLESS THERE IS A COMPACTED FILL OF 24" OR GREATER OVER THE STRUCTURE OR PIPE. BACKFILL MATERIAL OUTSIDE THE STRUCTURAL BACKFILL (FLOWABLE FILL) ZONE SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE CORE OF THE EMBANKMENT OR OTHER EMBANKMENT MATERIALS.

PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION.

CORRUGATED METAL PIPE — ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED METAL PIPE:

1. MATERIALS—(POLYMER COATED STEEL PIPE) — STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (10 MIL) ON BOTH SIDES OF THE PIPE. THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATIONS M-245 & M-246 WITH WATERTIGHT COUPLING BANDS OR FLANGES.

MATERIALS—(ALUMINUM COATED STEEL PIPE) — THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-274 WITH WATERTIGHT COUPLING BANDS OR FLANGES. ALUMINUM COATED STEEL PIPE, WHEN USED WITH FLOWABLE FILL OR WHEN SOIL AND/OR WATER CONDITIONS WARRANT THE NEED FOR INCREASED DURABILITY, SHALL BE FULLY BITUMINOUS COATED PER REQUIREMENTS OF AASHTO SPECIFICATION M-190 TYPE A. ALUMINUM SURFACES THAT ARE TO BE IN CONTACT WITH CONCRETE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER OR TWO COATS OF ASPHALT.

MATERIALS—(ALUMINUM PIPE) — THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-196 OR M-211 WITH WATERTIGHT COUPLING BANDS OR FLANGES. ALUMINUM PIPE, WHEN USED WITH FLOWABLE FILL OR WHEN SOIL AND/OR WATER CONDITIONS WARRANT FOR INCREASED DURABILITY, SHALL BE FULLY BITUMINOUS COATED PER REQUIREMENTS OF AASHTO SPECIFICATION M-190 TYPE A. ALUMINUM SURFACES THAT ARE TO BE IN CONTACT WITH CONCRETE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER OR TWO COATS OF ASPHALT. HOT DIP GALVANIZED BOLTS MAY BE USED FOR CONNECTIONS. THE PH OF THE SURROUNDING SOILS SHALL BE BETWEEN 4 AND 9.

2. COUPLING BANDS, ANTI-SEEP COLLARS, END SECTIONS, ETC., MUST BE COMPOSED OF THE SAME MATERIAL AND COATINGS AS THE PIPE. METALS MUST BE INSULATED FROM DISSIMILAR MATERIALS WITH USE OF RUBBER OR PLASTIC INSULATING MATERIALS AT LEAST 24 MILS IN THICKNESS.

3. CONNECTIONS—ALL CONNECTIONS WITH PIPES MUST BE COMPLETELY WATERTIGHT. THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHALL BE WELDED ALL AROUND WHEN THE PIPE AND RISER ARE METAL. ANTI-SEEP COLLARS SHALL BE CONNECTED TO THE PIPE IN SUCH A MANNER AS TO BE COMPLETELY WATERTIGHT. DIMPLE BANDS ARE NOT CONSIDERED TO BE WATERTIGHT.

ALL CONNECTIONS SHALL USE A RUBBER OR NEOPRENE GASKET WHEN JOINING PIPE SECTIONS. THE END OF EACH PIPE SHALL BE RE-ROLLED AN ADEQUATE NUMBER OF CORRUGATIONS TO ACCOMMODATE THE BANDWIDTH. THE FOLLOWING TYPE CONNECTIONS ARE ACCEPTABLE FOR PIPES LESS THAN 24 INCHES IN DIAMETER: FLANGES ON BOTH ENDS OF THE PIPE WITH A CIRCULAR 3/8 INCH CLOSED CELL NEOPRENE GASKET, PRE-PUNCHED TO THE FLANGE BOLT CIRCLE, SANDWICHED BETWEEN ADJACENT FLANGES; A 12-INCH WIDE STANDARD LAP TYPE BAND WITH 12-INCH WIDE BY 3/8-INCH THICK CLOSED CELL CIRCULAR NEOPRENE GASKET; AND A 12-INCH WIDE HUGGER TYPE BAND WITH O RING GASKETS HAVING A MINIMUM DIAMETER OF 1/2 INCH GREATER THAN THE CORRUGATION DEPTH. PIPES 24 INCHES IN DIAMETER AND LARGER SHALL BE CONNECTED BY A 24-INCH-LONG ANNULAR CORRUGATED BAND USING A MINIMUM OF 4 (FOUR) RODS AND LUGS, 2 ON EACH CONNECTING PIPE END. A 24-INCH WIDE BY 3/8-INCH THICK CLOSED CELL CIRCULAR NEOPRENE GASKET SHALL BE INSTALLED WITH 12 INCHES ON THE END OF EACH PIPE. FLANGED JOINTS WITH 3/8 INCH CLOSED CELL GASKETS THE FULL WIDTH OF THE FLANGE IS ALSO ACCEPTABLE.

HELICALLY CORRUGATED PIPE SHALL HAVE EITHER CONTINUOUSLY WELDED SEAMS OR HAVE LOCK SEAMS WITH INTERNAL CAULKING OR A NEOPRENE BEAD.

4. BEDDING—THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED, ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.
5. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL".
6. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

REINFORCED CONCRETE PIPE — ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR REINFORCED CONCRETE PIPE:

1. MATERIALS—REINFORCED CONCRETE PIPE SHALL HAVE BELL AND SPIGOT JOINTS WITH RUBBER GASKETS AND SHALL EQUAL OR EXCEED ASTM C-361.

2. BEDDING—REINFORCED CONCRETE PIPE CONDUITS SHALL BE LAID IN A CONCRETE BEDDING CRADLE FOR THEIR ENTIRE LENGTH. THIS BED DING CRADLE SHALL CONSIST OF HIGH SLUMP CONCRETE PLACED UNDER THE PIPE AND UP THE SIDES OF THE PIPE AT LEAST 50% OF ITS OUT SIDE DIAMETER WITH A MINIMUM THICKNESS OF 6 INCHES. WHERE A CONCRETE CRADLE IS NOT NEEDED FOR STRUCTURAL REASONS, FLOWABLE FILL MAY BE USED AS DESCRIBED IN THE "STRUCTURE BACKFILL" SECTION OF THIS STANDARD. GRAVEL BEDDING IS NOT PERMITTED.

3. LAYING PIPE — BELL AND SPIGOT PIPE SHALL BE PLACED WITH THE BELL END UPSTREAM. JOINTS SHALL BE MADE IN ACCORDANCE WITH RECOMMENDATIONS OF THE MANUFACTURER OF THE MATERIAL. AFTER THE JOINTS ARE SEALED FOR THE ENTIRE LINE, THE BEDDING SHALL BE PLACED

SO THAT ALL SPACES UNDER THE PIPE ARE FILLED. CARE SHALL BE EXERCISED TO PREVENT ANY DEVIATION FROM THE ORIGINAL LINE AND GRADE OF THE PIPE. THE FIRST JOINT MUST BE LOCATED WITHIN 4 FEET FROM THE RISER.

4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL".

5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

PLASTIC PIPE—THE FOLLOWING CRITERIA SHALL APPLY FOR PLASTIC PIPE:

1. MATERIALS—PVC PIPE SHALL BE PVC-1120 OR PVC-1220 CONFORMING TO ASTM D-1785 OR ASTM D-2241. CORRUGATED HIGH DENSITY POLYETHYLENE (HDPE) PIPE, COUPLINGS AND FITTINGS SHALL CONFORM TO THE FOLLOWING: 4" - 10" INCH PIPE SHALL MEET THE REQUIREMENTS OF AASHTO M252 TYPE S, AND 12" THROUGH 24" INCH SHALL MEET THE REQUIREMENTS OF AASHTO M294 TYPE S.

2. JOINTS AND CONNECTIONS TO ANTI-SEEP COLLARS SHALL BE COMPLETELY WATERTIGHT.

3. BEDDING — THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED, ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.

4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL".

5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

DRAINAGE DIAPHRAGMS — WHEN A DRAINAGE DIAPHRAGM IS USED, A REGISTERED PROFESSIONAL ENGINEER SHALL SUPERVISE THE DESIGN AND CONSTRUCTION INSPECTION.

CONCRETE

CONCRETE SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 414, MIX NO. 3.

ROCK RIPRAP

ROCK RIPRAP SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 311.

GEOTEXTILE SHALL BE PLACED UNDER ALL RIPRAP AND SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 921.09, CLASS C.

CARE OF WATER DURING CONSTRUCTION

ALL WORK ON PERMANENT STRUCTURES SHALL BE CARRIED OUT IN AREAS FREE FROM WATER. THE CONTRACTOR SHALL CONSTRUCT AND MAINTAIN ALL TEMPORARY DIKES, LEVEES, COFFERDAMS, DRAINAGE CHANNELS, AND STREAM DIVERSIONS NECESSARY TO PROTECT THE AREAS TO BE OCCUPIED BY THE PERMANENT WORKS. THE CONTRACTOR SHALL ALSO FURNISH, INSTALL, OPERATE, AND MAINTAIN ALL NECESSARY PUMPING AND OTHER EQUIPMENT REQUIRED FOR REMOVAL OF WATER FROM VARIOUS PARTS OF THE WORK AND FOR MAINTAINING THE EXCAVATIONS, FOUNDATION, AND OTHER PARTS OF THE WORK FREE FROM WATER AS REQUIRED OR DIRECTED BY THE ENGINEER FOR CONSTRUCTING EACH PART OF THE WORK. AFTER HAVING SERVED THEIR PURPOSE, ALL TEMPORARY PROTECTIVE WORKS SHALL BE REMOVED OR LEVELED AND GRADED TO THE EXTENT REQUIRED TO PREVENT OBSTRUCTION IN ANY DEGREE WHATSOEVER OF THE FLOW OF WATER TO THE SPILLWAY OR OUTLET WORKS AND SO AS NOT TO INTERFERE IN ANY WAY WITH THE OPERATION OR MAINTENANCE OF THE STRUCTURE. STREAM DIVERSIONS SHALL BE MAINTAINED UNTIL THE FULL FLOW CAN BE PASSED THROUGH THE PERMANENT WORKS. THE REMOVAL OF WATER FROM THE REQUIRED EXCAVATION AND THE FOUNDATION SHALL BE ACCOMPLISHED IN A MANNER AND TO THE EXTENT THAT SHALL MAINTAIN STABILITY OF THE EXCAVATED SLOPES AND BOTTOM REQUIRED EXCAVATIONS AND SHALL ALLOW SATISFACTORY PERFORMANCE OF ALL CONSTRUCTION OPERATIONS. DURING THE PLACING AND COMPACTING OF MATERIAL IN REQUIRED EXCAVATIONS, THE WATER LEVEL AT THE LOCATIONS BEING REFILLED SHALL BE MAINTAINED BELOW THE BOTTOM OF THE EXCAVATION AT SUCH LOCATIONS WHICH MAY REQUIRE DRAINING THE WATER SUMPS FROM WHICH THE WATER SHALL BE PUMPED.

STABILIZATION

ALL BORROW AREAS SHALL BE GRADED TO PROVIDE PROPER DRAINAGE AND LEFT IN A SIGHTLY CONDITION. ALL EXPOSED SURFACES OF THE EMBANKMENT, SPILLWAY, SPOIL AND BORROW AREAS, AND BERMS SHALL BE STABILIZED BY SEEDING, LIMING, FERTILIZING AND MULCHING IN ACCORDANCE WITH THE NATURAL RESOURCES CONSERVATION SERVICE STANDARDS AND SPECIFICATIONS FOR CRITICAL AREA PLANTING (MD-342) OR AS SHOWN ON THE ACCOMPANYING DRAWINGS.



EROSION AND SEDIMENT CONTROL

CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION SHALL BE CONTROLLED AND WATER AND AIR POLLUTION MINIMIZED. STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT SHALL BE FOLLOWED. CONSTRUCTION PLANS SHALL DETAIL EROSION AND SEDIMENT CONTROL MEASURES.

COMPACTED CLAY LINER

PLACE 12" THICK CLAY BLANKET ON UPSTREAM SLOPE OF EMBANKMENT. INSTALL IN 8-INCH LIFTS AND COMPACT WITH TWO COMPLETE PASSES OF A SHEEPSFOOT ROLLER. COMPACT FINISH SURFACE WITH TWO PASSES OVER THE ENTIRE SURFACE WITH HEAVY EQUIPMENT. PLACE CLAY WITHIN 2% OF OPTIMUM MOISTURE CONTENT AND COMPACT TO MINIMUM DENSITY OF 90% OF STANDARD PROCTOR. KEY CLAY LINER INTO EXISTING SLOPE. ALL COMPACTION TO BE IN ACCORDANCE WITH ASTM D698.

PLACE 6" OF LOW PLASTICITY SOIL (ONSITE GRAVEL) OVER THE COMPACTED CLAY LINER.



STORMWATER MANAGEMENT AS-BUILT CERTIFICATION REQUIREMENTS:

1. THE CONSTRUCTION OF ALL STORMWATER MANAGEMENT FACILITIES SHALL CONFORM TO THE APPROVED CONTRACT DOCUMENTS AND MDE STORMWATER DESIGN MANUAL VOLUMES 1&1.
2. THE CONTRACTOR IS RESPONSIBLE FOR FULLY UNDERSTANDING THE DESIGN AND FUNCTION OF THE PROPOSED FACILITIES AND FOR CONSTRUCTING FACILITIES IN FULL COMPLIANCE WITH DESIGN STANDARDS.
3. THE CONTRACTOR SHALL ENSURE THAT ALL OF THE REQUIRED PLAN CHECKLISTS ARE SIGNED BY THE APPROPRIATE INDIVIDUALS AT THE REQUIRED STAGES OF CONSTRUCTION.
4. THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 7-DAYS ADVANCED NOTICE OF CONSTRUCTION OF THE STORMWATER MANAGEMENT FACILITY(S) TO THE OWNER AND CERTIFYING ENGINEER.
5. THE CONTRACTOR SHALL VERIFY ALL CRITICAL INVERTS AND ELEVATIONS THROUGHOUT CONSTRUCTION TO VERIFY CONFORMANCE WITH THE DESIGN AND STANDARDS. THIS INFORMATION SHALL BE PROVIDED TO THE OWNER AND THE CERTIFYING ENGINEER IN THE FORM OF RED-LINED CONTRACT DRAWINGS AT THE END OF THE PROJECT.
6. THE CONTRACTOR OBTAIN THE SERVICES OF A MARYLAND LICENSED SURVEYOR TO CONDUCT AN AS-BUILT SURVEY OF THE STORMWATER MANAGEMENT FACILITY(S) PRIOR TO FINAL PLANTING LANDSCAPING.
7. ANY ADJUSTMENTS TO THE CONSTRUCTION OF THE FACILITIES SHALL BE REVIEWED AND APPROVED BY THE CERTIFYING ENGINEER AND OWNER. APPROVAL OF THE MODIFICATIONS IS REQUIRED PRIOR TO PROCEEDING WITH CONSTRUCTION.
8. THE CONTRACTOR SHALL MAKE ANY CORRECTIONS AND ADJUSTMENTS REQUIRED TO FULLY PROVIDE REQUIRED DESIGN VOLUMES, FUNCTION, AND STRUCTURAL INTEGRITY OF FACILITIES AT NO ADDITIONAL COST TO THE OWNER.
9. THE CONTRACTOR SHALL ALSO VERIFY THAT ALL SITE IMPROVEMENTS, FLOW PATHS, AND DRAINAGE AREAS TO EACH FACILITY ARE IN CONFORMANCE WITH THE APPROVED DESIGN PLANS.
10. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT PLANS AND APPROPRIATE SUPPORT DOCUMENTATION TO THE OWNER AND CERTIFYING ENGINEER.
11. THE CONTRACTOR SHALL MAKE ANY AND ALL REPAIRS AND/OR MODIFICATIONS REQUIRED TO OBTAIN AS-BUILT APPROVAL BY HARFORD COUNTY AT NO ADDITIONAL COSTS TO THE OWNER.
12. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR MAINTENANCE OF ALL STORMWATER-RELATED FACILITIES UNTIL FINAL ACCEPTANCE OF THE FACILITIES BY OWNER, AND SHALL PERFORM FULL CLEANOUT AND/OR DREDGING OF FACILITIES PRIOR TO TURN OVER TO THE OWNER.

EG-SWMENG-000747-2016


Revisions		HARFORD COUNTY, MARYLAND	
DETAILS - SWM			
Drawn By :	JS / MTB	Contract No :	DP1602779
Designed By :	JS / MTB	Scale :	AS SHOWN
Reviewed By :	MAE	Sheet	54 Of 78
		Date :	2/16/2022

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No. DE-B5



BOARD OF EDUCATION OF HARFORD COUNTY
 4299 CHURCH CREEK ROAD
 BELCAMP MD 21017
 TAX MAP 0062 LOT 1 PARCEL 0813
 LIBER 01858
 FOLIO 0954
 PLAT 77772

DEWATERING NOTES:

1. DEWATERING DEVICES SHOWN ON THE PLANS ARE SUGGESTED MEASURES. THE CONTRACTOR MAY USE ANY MDE APPROVED DEWATERING DEVICE AS NECESSARY WHICH SHALL INCLUDE: FILTER BAG, REMOVABLE PUMPING STATION, PORTABLE SEDIMENT TANK, SLUMP PIT. THE CONTRACTOR SHALL FIELD LOCATE ALL DEWATERING MEASURES WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
2. MOBILE DEWATERING DEVICES SHALL BE LOCATED WITHIN THE LOD.
3. ALL DEWATERING DEVICES SHALL HAVE A STABLE OUTFALL.
4. ANY PUMPING OF WORK AREA DRAINAGE (SPRINGS, SEEPS, ETC.) SHALL BE PUMPED TO A FILTER BAG OR OTHER APPROVED METHOD.

MAINTENANCE OF STREAM FLOW GENERAL NOTES:

1. THE CONTRACTOR SHALL REFER TO SHEET 64 OF 78 FOR THE EROSION AND SEDIMENT CONTROL SEQUENCE OF CONSTRUCTION.
2. AT THE BEGINNING OF EACH WORKDAY, THE PUMP-AROUND PRACTICE SHALL BE OPERATIONAL PRIOR TO THE COMMENCEMENT OF GRADING OPERATIONS. THE PUMP-AROUND PRACTICE SHOWN ON THIS PLAN ILLUSTRATES ONE POTENTIAL PUMP-AROUND CONFIGURATION. THE PUMP-AROUND PRACTICE SHALL BE FIELD LOCATED BY THE CONTRACTOR. THE CONTRACTOR MAY MODIFY THE PUMP-AROUND PRACTICE LOCATION AND LENGTH WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
3. THE CONTRACTOR SHALL ONLY PERFORM STREAM WORK THAT CAN BE COMPLETED IN ONE WORKING DAY. ALL INSTREAM WORK SHALL BE STABILIZED BY THE END OF EACH WORK DAY BEFORE THE PUMP-AROUND PRACTICE IS SHUT DOWN. THE SANDBAGS ARE TO BE REMOVED FROM THE STREAM CHANNEL AT THE END OF EACH WORKING DAY TO ALLOW WATER TO FLOW THROUGH THE WORK AREA.
4. THE CONTRACTOR SHALL ENSURE THAT ALL SEDIMENT CONTROLS REMAIN FUNCTIONAL AT THE END OF EACH WORKDAY TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE LIMITS OF DISTURBANCE.

5. INSTREAM WORKSHALL NOT COMMENCE UNTIL ALL NECESSARY RESOURCES ARE ONSITE.
6. THE CONTRACTOR SHALL TAKE EFFORTS TO AVOID IMPACTING TREES LOCATED WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
7. NO FUEL SHALL BE STORED WITHIN THE 100-YR FLOODPLAIN.
8. WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, SILT FENCE MAY BE SUBSTITUTED FOR SUPER SILT FENCE AROUND STOCKPILE AREAS.

SITE ANALYSIS:

TOTAL SITE AREA: 5.69 AC
 TOTAL DISTURBED AREA: 5.69 AC
 AREA TO BE PAVED: 0 AC
 AREA TO BE STABILIZED: 5.69 AC
 CUT: 3603.68 CU FT.
 FILL: 5914.54 CU FT.
 TOPSOIL: 2310.86 CU FT.

NPDES ID PT. N:1525248.0831 E:660164.9582

LEGEND


- SOIL BOUNDARY
- D SOIL GROUP LABEL

Revisions

Revisions

**HARFORD COUNTY, MARYLAND
 EROSION AND SEDIMENT
 CONTROL PLAN - STREAM**

Drawn By : LBT Contract No : DP1602779
 Designed By : MCB Scale : 1"=20'
 Reviewed By : GWF Sheet 55 Of 78
 Date : 2/17/2022



MATCHLINE SEE SHEET 59

MATCHLINE SEE SHEET 56

MATCHLINE SEE SHEET 56

MATCHLINE SEE SHEET 60


ADC MAP :

TAX MAP :

HCC BILLING ID No.:

HCC DWG ID No.:

EP-A1



DEWATERING NOTES:

- DEWATERING DEVICES SHOWN ON THE PLANS ARE SUGGESTED MEASURES. THE CONTRACTOR MAY USE ANY MDE APPROVED DEWATERING DEVICE AS NECESSARY WHICH SHALL INCLUDE:
 FILTER BAG
 REMOVABLE PUMPING STATION
 PORTABLE SEDIMENT TANK
 SUMP PIT
 THE CONTRACTOR SHALL FIELD LOCATE ALL DEWATERING MEASURES WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- MOBILE DEWATERING DEVICES SHALL BE LOCATED WITHIN THE LOD.
- ALL DEWATERING DEVICES SHALL HAVE A STABLE OUTFALL.
- ANY PUMPING OF WORK AREA DRAINAGE (SPRINGS, SEEPS, ETC.) SHALL BE PUMPED TO A FILTER BAG OR OTHER APPROVED METHOD.

MAINTENANCE OF STREAM FLOW GENERAL NOTES:


- THE CONTRACTOR SHALL REFER TO SHEET 64 OF 78 FOR THE EROSION AND SEDIMENT CONTROL SEQUENCE OF CONSTRUCTION.
- AT THE BEGINNING OF EACH WORKDAY, THE PUMP-AROUND PRACTICE SHALL BE OPERATIONAL PRIOR TO THE COMMENCEMENT OF GRADING OPERATIONS. THE PUMP-AROUND PRACTICE SHOWN ON THIS PLAN ILLUSTRATES ONE POTENTIAL PUMP-AROUND CONFIGURATION. THE PUMP-AROUND PRACTICE SHALL BE FIELD LOCATED BY THE CONTRACTOR. THE CONTRACTOR MAY MODIFY THE PUMP-AROUND PRACTICE LOCATION AND LENGTH WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- THE CONTRACTOR SHALL ONLY PERFORM STREAM WORK THAT CAN BE COMPLETED IN ONE WORKING DAY. ALL INSTREAM WORK SHALL BE STABILIZED BY THE END OF EACH WORK DAY BEFORE THE PUMP-AROUND PRACTICE IS SHUT DOWN. THE SANDBAGS ARE TO BE REMOVED FROM THE STREAM CHANNEL AT THE END OF EACH WORKING DAY TO ALLOW WATER TO FLOW THROUGH THE WORK AREA.
- THE CONTRACTOR SHALL ENSURE THAT ALL SEDIMENT CONTROLS REMAIN FUNCTIONAL AT THE END OF EACH WORKDAY TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE LIMITS OF DISTURBANCE.

- INSTREAM WORKSHALL NOT COMMENCE UNTIL ALL NECESSARY RESOURCES ARE ONSITE.
- THE CONTRACTOR SHALL TAKE EFFORTS TO AVOID IMPACTING TREES LOCATED WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
- NO FUEL SHALL BE STORED WITHIN THE 100-YR FLOODPLAIN.
- WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, SILT FENCE MAY BE SUBSTITUTED FOR SUPER SILT FENCE AROUND STOCKPILE AREAS.

LEGEND

--- SOIL BOUNDARY

D SOIL GROUP LABEL



Revisions

EG-SWMENG-000747-2016 S/C PLAN # 59832 GRADING PERMIT # 9386-2017

HARFORD COUNTY, MARYLAND
EROSION AND SEDIMENT CONTROL PLAN - STREAM

Drawn By : LBT	Contract No : DP1602779
Designed By : MCB	Scale : 1"=20'
Reviewed By : GWF	Sheet 56 Of 78
Date : 2/17/2022	EP-A2

MATCHLINE SEE SHEET 55

MATCHLINE SEE SHEET 57

MATCHLINE SEE SHEET 55

MATCHLINE SEE SHEET 60

MATCHLINE SEE SHEET 60


ADC MAP :

TAX MAP :

HCC BILLING ID No.:

HCC DWG ID No.:

SCALE 1"=20'



MATCHLINE SEE SHEET 56

MATCHLINE SEE SHEET 58


DEWATERING NOTES:

- DEWATERING DEVICES SHOWN ON THE PLANS ARE SUGGESTED MEASURES. THE CONTRACTOR MAY USE ANY MDE APPROVED DEWATERING DEVICE AS NECESSARY WHICH SHALL INCLUDE:
 FILTER BAG
 REMOVABLE PUMPING STATION
 PORTABLE SEDIMENT TANK
 SUMP PIT
 THE CONTRACTOR SHALL FIELD LOCATE ALL DEWATERING MEASURES WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- MOBILE DEWATERING DEVICES SHALL BE LOCATED WITHIN THE LOD.
- ALL DEWATERING DEVICES SHALL HAVE A STABLE OUTFALL.
- ANY PUMPING OF WORK AREA DRAINAGE (SPRINGS, SEEPS, ETC.) SHALL BE PUMPED TO A FILTER BAG OR OTHER APPROVED METHOD.

MAINTENANCE OF STREAM FLOW GENERAL NOTES:

- THE CONTRACTOR SHALL REFER TO SHEET 64 OF 78 FOR THE EROSION AND SEDIMENT CONTROL SEQUENCE OF CONSTRUCTION.
- AT THE BEGINNING OF EACH WORKDAY, THE PUMP-AROUND PRACTICE SHALL BE OPERATIONAL PRIOR TO THE COMMENCEMENT OF GRADING OPERATIONS. THE PUMP-AROUND PRACTICE SHOWN ON THIS PLAN ILLUSTRATES ONE POTENTIAL PUMP-AROUND CONFIGURATION. THE PUMP-AROUND PRACTICE SHALL BE FIELD LOCATED BY THE CONTRACTOR. THE CONTRACTOR MAY MODIFY THE PUMP-AROUND PRACTICE LOCATION AND LENGTH WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- THE CONTRACTOR SHALL ONLY PERFORM STREAM WORK THAT CAN BE COMPLETED IN ONE WORKING DAY. ALL INSTREAM WORK SHALL BE STABILIZED BY THE END OF EACH WORK DAY BEFORE THE PUMP-AROUND PRACTICE IS SHUT DOWN. THE SANDBAGS ARE TO BE REMOVED FROM THE STREAM CHANNEL AT THE END OF EACH WORKING DAY TO ALLOW WATER TO FLOW THROUGH THE WORK AREA.
- THE CONTRACTOR SHALL ENSURE THAT ALL SEDIMENT CONTROLS REMAIN FUNCTIONAL AT THE END OF EACH WORKDAY TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE LIMITS OF DISTURBANCE.
- INSTREAM WORK SHALL NOT COMMENCE UNTIL ALL NECESSARY RESOURCES ARE ONSITE.
- THE CONTRACTOR SHALL TAKE EFFORTS TO AVOID IMPACTING TREES LOCATED WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
- NO FUEL SHALL BE STORED WITHIN THE 100-YR FLOODPLAIN.
- WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, SILT FENCE MAY BE SUBSTITUTED FOR SUPER SILT FENCE AROUND STOCKPILE AREAS.

LEGEND	
	SOIL BOUNDARY
	SOIL GROUP LABEL



EG-SWMENG-000747-2016

S/C PLAN # 59832
 GRADING PERMIT # 9386-2017

**HARFORD COUNTY, MARYLAND
 EROSION AND SEDIMENT
 CONTROL PLAN - STREAM**

Revisions	Drawn By : <u> </u> LBT	Contract No : <u> </u> DP1602779
	Designed By : <u> </u> MCB	Scale : <u> </u> 1"=20'
	Reviewed By : <u> </u> GWF	Sheet <u>57</u> Of <u>78</u>
		Date : <u>2/17/2022</u>

EP-A3

ADC MAP :


TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE 1"=20'



MATCHLINE SEE SHEET 57



- DEWATERING NOTES:**
- DEWATERING DEVICES SHOWN ON THE PLANS ARE SUGGESTED MEASURES. THE CONTRACTOR MAY USE ANY MDE APPROVED DEWATERING DEVICE AS NECESSARY WHICH SHALL INCLUDE:
 FILTER BAG
 REMOVABLE PUMPING STATION
 PORTABLE SEDIMENT TANK
 SUMP PIT
 THE CONTRACTOR SHALL FIELD LOCATE ALL DEWATERING MEASURES WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
 - MOBILE DEWATERING DEVICES SHALL BE LOCATED WITHIN THE LOD.
 - ALL DEWATERING DEVICES SHALL HAVE A STABLE OUTFALL.
 - ANY PUMPING OF WORK AREA DRAINAGE (SPRINGS, SEEPS, ETC.) SHALL BE PUMPED TO A FILTER BAG OR OTHER APPROVED METHOD.

- MAINTENANCE OF STREAM FLOW GENERAL NOTES:**
- THE CONTRACTOR SHALL REFER TO SHEET 64 OF 78 FOR THE EROSION AND SEDIMENT CONTROL SEQUENCE OF CONSTRUCTION.
 - AT THE BEGINNING OF EACH WORKDAY, THE PUMP-AROUND PRACTICE SHALL BE OPERATIONAL PRIOR TO THE COMMENCEMENT OF GRADING OPERATIONS. THE PUMP-AROUND PRACTICE SHOWN ON THIS PLAN ILLUSTRATES ONE POTENTIAL PUMP-AROUND CONFIGURATION. THE PUMP-AROUND PRACTICE SHALL BE FIELD LOCATED BY THE CONTRACTOR. THE CONTRACTOR MAY MODIFY THE PUMP-AROUND PRACTICE LOCATION AND LENGTH WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
 - THE CONTRACTOR SHALL ONLY PERFORM STREAM WORK THAT CAN BE COMPLETED IN ONE WORKING DAY. ALL INSTREAM WORK SHALL BE STABILIZED BY THE END OF EACH WORK DAY BEFORE THE PUMP-AROUND PRACTICE IS SHUT DOWN. THE SANDBAGS ARE TO BE REMOVED FROM THE STREAM CHANNEL AT THE END OF EACH WORKING DAY TO ALLOW WATER TO FLOW THROUGH THE WORK AREA.

- THE CONTRACTOR SHALL ENSURE THAT ALL SEDIMENT CONTROLS REMAIN FUNCTIONAL AT THE END OF EACH WORKDAY TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE LIMITS OF DISTURBANCE.
- INSTREAM WORKSHALL NOT COMMENCE UNTIL ALL NECESSARY RESOURCES ARE ONSITE.
- THE CONTRACTOR SHALL TAKE EFFORTS TO AVOID IMPACTING TREES LOCATED WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
- NO FUEL SHALL BE STORED WITHIN THE 100-YR FLOODPLAIN.
- WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, SILT FENCE MAY BE SUBSTITUTED FOR SUPER SILT FENCE AROUND STOCKPILE AREAS.



Revisions	

EG-SWMENG-000747-2016 S/C PLAN # 59832 GRADING PERMIT # 9386-2017

HARFORD COUNTY, MARYLAND

EROSION AND SEDIMENT CONTROL PLAN - STREAM

Drawn By : LBT Contract No : DP1602779


Designed By : MCB Scale : 1"=20'

Reviewed By : GWF Sheet 58 Of 78

Date : 2/17/2022

EP-A4

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. :





DEWATERING NOTES:

- DEWATERING DEVICES SHOWN ON THE PLANS ARE SUGGESTED MEASURES. THE CONTRACTOR MAY USE ANY MDE APPROVED DEWATERING DEVICE AS NECESSARY WHICH SHALL INCLUDE:
 FILTER BAG
 REMOVABLE PUMPING STATION
 PORTABLE SEDIMENT TANK
 SUMP PIT
 THE CONTRACTOR SHALL FIELD LOCATE ALL DEWATERING MEASURES WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- MOBILE DEWATERING DEVICES SHALL BE LOCATED WITHIN THE LOD.
- ALL DEWATERING DEVICES SHALL HAVE A STABLE OUTFALL.
- ANY PUMPING OF WORK AREA DRAINAGE (SPRINGS, SEEPS, ETC.) SHALL BE PUMPED TO A FILTER BAG OR OTHER APPROVED METHOD.

MAINTENANCE OF STREAM FLOW GENERAL NOTES:

- THE CONTRACTOR SHALL REFER TO SHEET 64 OF 78 FOR THE EROSION AND SEDIMENT CONTROL SEQUENCE OF CONSTRUCTION.
- AT THE BEGINNING OF EACH WORKDAY, THE PUMP-AROUND PRACTICE SHALL BE OPERATIONAL PRIOR TO THE COMMENCEMENT OF GRADING OPERATIONS. THE PUMP-AROUND PRACTICE SHOWN ON THIS PLAN ILLUSTRATES ONE POTENTIAL PUMP-AROUND CONFIGURATION. THE PUMP-AROUND PRACTICE SHALL BE FIELD LOCATED BY THE CONTRACTOR. THE CONTRACTOR MAY MODIFY THE PUMP-AROUND PRACTICE LOCATION AND LENGTH WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- THE CONTRACTOR SHALL ONLY PERFORM STREAM WORK THAT CAN BE COMPLETED IN ONE WORKING DAY. ALL INSTREAM WORK SHALL BE STABILIZED BY THE END OF EACH WORKDAY BEFORE THE PUMP-AROUND PRACTICE IS SHUT DOWN. THE SANDBAGS ARE TO BE REMOVED FROM THE STREAM CHANNEL AT THE END OF EACH WORKING DAY TO ALLOW WATER TO FLOW THROUGH THE WORK AREA.
- THE CONTRACTOR SHALL ENSURE THAT ALL SEDIMENT CONTROLS REMAIN FUNCTIONAL AT THE END OF EACH WORKDAY TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE LIMITS OF DISTURBANCE.
- INSTREAM WORK SHALL NOT COMMENCE UNTIL ALL NECESSARY RESOURCES ARE ONSITE.
- THE CONTRACTOR SHALL TAKE EFFORTS TO AVOID IMPACTING TREES LOCATED WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
- NO FUEL SHALL BE STORED WITHIN THE 100-YR FLOODPLAIN.
- WITH APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, SILT FENCE MAY BE SUBSTITUTED FOR SUPER SILT FENCE AROUND STOCKPILE AREAS.




Revisions	

EG-SWMENG-000747-2016 S/C PLAN # 59832 GRADING PERMIT # 9386-2017


HARFORD COUNTY, MARYLAND
EROSION AND SEDIMENT CONTROL PLAN - STREAM

Drawn By : LBT	Contract No : DP1602779
Designed By : MCB	Scale : 1"=20'
Reviewed By : GWF	Sheet 59 Of 78
Date : 2/16/2022	EP-A5

ADC MAP : TAX MAP : HCG BILLING ID No. : HCG DWG ID No. : SCALE: 1"=20'



SEDIMENT CONTROL - FINAL PHASE



SEDIMENT CONTROL - INITIAL PHASE

SEQUENCE OF CONSTRUCTION – GRAVEL WETLAND

- GENERAL NOTES:
- A. THE CONTRACTOR SHALL NOTIFY THE HARFORD COUNTY INSPECTOR AT LEAST SEVEN (7) DAYS PRIOR TO THE INSTALLATION OF WORK.
 - B. THE LIMITS OF DISTURBANCE MUST BE FIELD MARKED PRIOR TO INSTALLATION OF SEDIMENT CONTROL MEASURES, CONSTRUCTION, OR OTHER LAND DISTURBING ACTIVITIES.
 - C. SEE SHEET ER-A3 FOR ADDITIONAL GENERAL NOTES AND SEQUENCE OF CONSTRUCTION FOR THE STREAM RESTORATION PORTION OF THE PROJECT.
 - D. THE CONTRACTOR SHALL NOTIFY THE CERTIFYING ENGINEER 1-WEEK IN ADVANCE OF CONSTRUCTION TO COORDINATE NECESSARY SWM AS-BUILT CERTIFICATION SITE VISITS.

GRAVEL WETLAND – INITIAL PHASE

1. INSTALL SSF ALONG THE EASTERN SIDE OF THE GRAVEL WETLAND AS SHOWN ON THIS SHEET.
2. ONCE SUPER SILT FENCE IS INSTALLED, INSTALL CLEAR WATER TEMPORARY DIVERSION PIPES AND SANDBAGS, SUMP PIT AND SUMP PIT PIPE, AND FILTER BAG AS INDICATED.
3. ONCE INSTALLATION OF ALL EROSION CONTROL MEASURES IS COMPLETED, BEGIN WITH GRADING FOR REMOVAL OF 12" CMP AND ASSOCIATED RIP-RAP.
4. WITH THE APPROVAL FROM THE SEDIMENT CONTROL INSPECTION, DEMOLISH EXISTING OUTFALL PIPE AND RIPRAP.
5. ONCE ITEMS ARE DEMOLISHED, CONTINUE WITH GRADING FOR GRAVEL WETLAND FACILITY AND WEIR WALL CONSTRUCTION.
6. CONSTRUCT CLAY CUT-OFF TRENCH, CLAY CORE TRENCH, WEIR WALL, OUTFALL PIPE, AND EMBANKMENT FROM STATION 0+00 TO STATION 1+70.
7. ONCE ITEM 6 CONSTRUCTION IS COMPLETE, CONTRACTOR CAN PROCEED TO THE FINAL PHASE.

GRAVEL WETLAND – FINAL PHASE


8. ADJUST LOCATION OF SANDBAGS TO ALLOW FOR FINAL PHASE OF CONSTRUCTION. INSTALL / ADJUST SUMP PIT, SUMP PIT PIPES LOCATION AND FILTER BAG LOCATION AND LOCATION OF CLEAR WATER DIVERSION PIPES AS SHOWN ON FINAL PHASE PLAN. ENSURE POSITIVE DRAINAGE IN CLEAR WATER DIVERSION PIPES. INSTALL PUMP AS NECESSARY TO ENSURE CLEAR WATER DIVERSION PIPE FUNCTIONING.
9. REMOVE PORTION OF SUPER SILT FENCE DOWNSTREAM OF NEW OUTFALL. NEW OUTFALL STRUCTURE SHALL BE UTILIZED DURING FINAL PHASE TO CONVEY CLEAR WATER FROM THE SITE.
10. CONTRACTOR CAN BEGIN CONSTRUCTION OF THE REMAINING GRAVEL WETLAND. THE CONTRACTOR SHALL PROTECT INSTALLED MATERIALS FROM GETTING CONTAMINATED WITH SEDIMENT. INSTALL TEMPORARY FILTER CLOTH MATERIAL OVER THE NEWLY INSTALLED WORK AT THE END OF EACH WORK DAY.
11. ONCE THE GRAVEL WETLAND IS CONSTRUCTED, THE CONTRACTOR SHALL PREPARE AN AS-BUILT SURVEY OF THE COMPLETED CONSTRUCTION AND PROVIDE TO THE OWNER AND CERTIFYING ENGINEER FOR REVIEW. THE CONTRACTOR SHALL MAKE ALL NECESSARY ADJUSTMENTS TO THE CONSTRUCTION TO ENSURE IT COMPLIES WITH THE APPROVED PLANS. THE CONTRACTOR SHALL RESURVEY ANY UPDATED ITEMS.
12. WITH THE APPROVAL FROM THE OWNER, CERTIFYING ENGINEER AND SEDIMENT CONTROL INSPECTOR, CONTRACTOR CAN PROCEED WITH THE FINAL LANDSCAPE INSTALLATION, CHAIN LINK FENCE INSTALLATION AND SITE RESTORATION.
13. ONCE ALL CONSTRUCTION IS COMPLETE, STABILIZE ALL DISTURBED AREAS.
14. CONTRACTOR SHALL OBTAIN APPROVAL FROM INSPECTOR PRIOR TO THE REMOVAL OF ANY SEDIMENT CONTROL DEVICES AND DIVERSION PIPES.
15. WITH THE APPROVAL OF SEDIMENT CONTROL INSPECTOR, REMOVE ALL SEDIMENT CONTROL DEVICES AND PERMANENTLY STABILIZE ALL DISTURBED AREAS.

LEGEND

--- SOIL BOUNDARY

D SOIL GROUP LABEL

NOTE TO THE CONTRACTOR: "EROSION AND SEDIMENT CONTROL SHALL BE STRICTLY ENFORCED"
THIS PLAN IS FOR EROSION & SEDIMENT CONTROL PURPOSES ONLY.



STANDARD STABILIZATION NOTE

FOLLOWING INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION MUST BE COMPLETED WITHIN:

- a. THREE (3) CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES, AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1); AND
- b. SEVEN (7) CALENDAR DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE NOT UNDER ACTIVE GRADING.

EG-SWMENG-000747-2016 S/C PLAN # 59832
GRADING PERMIT # 9386-2017

Revisions		HARFORD COUNTY, MARYLAND EROSION AND SEDIMENT CONTROL PLAN - SWM	
Drawn By :	JS / MTB		
Designed By :	JS / MTB	Scale :	1"=30'
Reviewed By :	MAE	Sheet	60 Of 78
		Date :	2/16/2022


ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

EP-B1



LEGEND	
---	SOIL BOUNDARY
D	SOIL GROUP LABEL

STANDARD STABILIZATION NOTE

FOLLOWING INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION MUST BE COMPLETED WITHIN:

- THREE (3) CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES, AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1); AND
- SEVEN (7) CALENDAR DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE NOT UNDER ACTIVE GRADING

EROSION CONTROL NOTES:


- CONTRACTOR SHALL CLEAR ALL STREETS FREE OF SEDIMENT AT THE END OF EACH WORK DAY. ALL EFFORTS ARE TO BE MADE TO PREVENT SEDIMENT FROM GETTING ON THE STREETS. ALL SEDIMENT SPILLED, DROPPED OR TRACKED ONTO THE ROAD MUST BE REMOVED IMMEDIATELY BY VACUUMING, SCRAPING OR SWEEPING. WHEN WASHING WATER IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE THAT DRAINS TO AN APPROVED SEDIMENT CONTROL DEVICE.
- ALL AREAS SHALL BE STABILIZED AT THE END OF EACH WORK DAY WITH SOIL STABILIZATION MATTING UNLESS THE RUNOFF DRAINS TO AN APPROVED EROSION CONTROL DEVICE.

SEQUENCE OF CONSTRUCTION -LID/BMP'S

- GENERAL NOTES:
- THE CONTRACTOR SHALL NOTIFY THE HARFORD COUNTY INSPECTOR AT LEAST SEVEN (7) DAYS PRIOR TO THE INSTALLATION OF WORK.
 - THE LIMITS OF DISTURBANCE MUST BE FIELD MARKED PRIOR TO INSTALLATION OF SEDIMENT CONTROL MEASURES, CONSTRUCTION, OR OTHER LAND DISTURBING ACTIVITIES.
 - SEE SHEET ER-A3 FOR ADDITIONAL GENERAL NOTES AND SEQUENCE OF CONSTRUCTION FOR THE STREAM RESTORATION PORTION OF THE PROJECT.
 - THE CONTRACTOR SHALL NOTIFY THE CERTIFYING ENGINEER 1-WEEK IN ADVANCE OF CONSTRUCTION TO COORDINATE NECESSARY SWM AS-BUILT CERTIFICATION SITE VISITS.

LID BMP'S

- INSTALL MOT MEASURES AND COORDINATE LOADING DOCK CLOSURE WITH COUNTY.
- DEMOLISH ITEMS INDICATED AND CONSTRUCT INFILTRATION TRENCH, ASSOCIATED STORM DRAINAGE DRAIN BASIN, PIPING AND FINE GRADE THE AREAS INDICATED.
- STABILIZE ALL DISTURBED AREAS AT THE END OF EACH WORK DAY.
- THE CONTRACTOR SHALL PREPARE AN AS-BUILT SURVEY OF THE COMPLETED CONSTRUCTION AND PROVIDE TO THE OWNER AND CERTIFYING ENGINEER FOR REVIEW. THE CONTRACTOR SHALL MAKE ALL NECESSARY ADJUSTMENTS TO THE CONSTRUCTION TO ENSURE IT COMPLIES WITH THE APPROVED PLANS. THE CONTRACTOR SHALL RESURVEY ANY UPDATED ITEMS.
- WITH THE APPROVAL FROM THE OWNER, CERTIFYING ENGINEER AND SEDIMENT CONTROL INSPECTOR, CONTRACTOR CAN PROCEED WITH THE FINAL LANDSCAPE INSTALLATION AND SITE RESTORATION.



NOTE TO THE CONTRACTOR: "EROSION AND SEDIMENT CONTROL SHALL BE STRICTLY ENFORCED" THIS PLAN IS FOR EROSION & SEDIMENT CONTROL PURPOSES ONLY.

EG-SWMENG-000747-2016 S/C PLAN # 59832 GRADING PERMIT # 9386-2017

Revisions	HARFORD COUNTY, MARYLAND EROSION AND SEDIMENT CONTROL PLAN - SWM	
Drawn By : JS / MTB	Contract No : DP1602779	
Designed By : JS / MTB	Scale : 1"=30'	
Reviewed By : MAE	Sheet 61 Of 78	
	Date : 2/16/2022	EP-B2









ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE 1"=30'



EG-SWMENG-000747-2016 S/C PLAN # 59832
GRADING PERMIT # 9386-2017

Revisions	HARFORD COUNTY, MARYLAND SEDIMENT CONTROL NOTES AND DETAILS - STREAM	
	Drawn By : <u> </u> LBT	Contract No : <u> </u> DP1602779
	Designed By : <u> </u> MCB	Scale : <u> </u> NOT TO SCALE
	Reviewed By : <u> </u> GWF	Sheet <u>62</u> Of <u>78</u>
		Date : <u>2/16/2022</u>



ER-A1

ADC MAP : TAX MAP :


HCC BILLING ID No.:

HCC DWG ID No.:

MARYLAND'S GUIDELINES TO WATERWAY CONSTRUCTION
DETAIL 1.5: SANDBAG/STONE DIVERSION





TEMPORARY INSTREAM CONSTRUCTION MEASURES
 REVISED NOVEMBER 2000
 MARYLAND DEPARTMENT OF THE ENVIRONMENT WATER MANAGEMENT ADMINISTRATION




- NOTES:
- ACCESS ROUTES TO BE FIELD LOCATED WITH HARFORD COUNTY INSPECTORS AT PRE-CONSTRUCTION MEETING.
 - CONTRACTOR SHALL SEQUENCE CONSTRUCTION SUCH THAT NO EQUIPMENT WILL IMPACT AREAS TO BE PROTECTED PRIOR TO MULCH PLACEMENT.
 - CONTRACTOR SHALL MAINTAIN MULCH MAT THROUGHOUT CONSTRUCTION PERIOD.

MULCH MAT DETAIL
 NOT TO SCALE
DETAIL 3.5



PUMPED WATER FILTER BAG DETAIL
 NOT TO SCALE




DETAIL H-4-5 ORANGE CONSTRUCTION FENCING

48" Safety Fence, 72" T-Posts


LEGEND

SAF12	48" ORANGE FENCE, 12 FEET O.C.
SAF11	48" ORANGE FENCE, 11 FEET O.C.
SAF10	48" ORANGE FENCE, 10 FEET O.C.
SAF9	48" ORANGE FENCE, 9 FEET O.C.
SAF8	48" ORANGE FENCE, 8 FEET O.C.
SAF7	48" ORANGE FENCE, 7 FEET O.C.
SAF6	48" ORANGE FENCE, 6 FEET O.C.



- NOTES:
- ALL SENSITIVE AREAS SHALL BE PROTECTED AS PER PLAN.
 - ALL TREES IN THE CONSTRUCTION AREA NOT SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE PRESERVED AND PROTECTED WITH HIGH VISIBILITY FENCE AS PER PLAN.
 - WHEN PRACTICABLE, INSTALL HIGH VISIBILITY 3 FEET OUTSIDE OF THE DRIP LINE OF THE TREE.
 - SAFETY FENCE SHOULD BE FASTENED SECURELY TO THE T-POSTS.
 - THE FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION; ANY CHANGE OF THE PROTECTIVE FENCING MUST BE APPROVED.

www.erosionrunner.com



- NOTES:
- PRACTICE MAY BE COMBINED WITH SEDIMENT CONTROL FENCING.
 - LOCATION AND LIMITS OF FENCING SHALL BE COORDINATED IN FIELD WITH ARBORIST.
 - BOUNDARIES OF PROTECTION AREA SHOULD BE STAKED PRIOR TO INSTALLING PROTECTIVE DEVICE.
 - ROOT DAMAGE SHOULD BE AVOIDED.
 - PROTECTIVE SIGNAGE IS REQUIRED.
 - FENCING SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.

TREE PROTECTION FENCE
 The Maryland-National Capital Park and Planning Commission
 Montgomery County Department of Parks
 Detail No. JUNE 2007

EG-SWMENG-000747-2016 S/C PLAN # 59832
 GRADING PERMIT # 9386-2017

Revisions	HARFORD COUNTY, MARYLAND	
	SEDIMENT CONTROL NOTES	
	AND DETAILS - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ NOT TO SCALE
Reviewed By : _____	GWF	Sheet <u>63</u> Of <u>78</u>
		Date : <u>2/16/2022</u>

ADC MAP : TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

ER-A2

HARFORD COUNTY STANDARD EROSION & SEDIMENT CONTROL NOTES

1. A GRADING UNIT OF 20 ACRES IS THE MAXIMUM CONTIGUOUS AREA ALLOWED TO BE GRADED AT A GIVEN TIME.
2. A PROJECT IS TO BE SEQUENCED SO THAT GRADING ACTIVITIES BEGIN ON ONE GRADING UNIT AT A TIME. WORK MAY PROCEED TO A SUBSEQUENT GRADING UNIT WHEN AT LEAST 50 PERCENT OF THE DISTURBED AREA IN THE PROCEEDING GRADING UNIT HAS BEEN STABILIZED AND APPROVED BY DPW. NO MORE THAN THIRTY ACRES CUMULATIVELY MAY BE DISTURBED AT ANY GIVEN TIME.
3. THE CONTRACTOR/OWNER IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS. FURTHER, NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE UNTIL ALL REQUIRED PERMITS HAVE BEEN OBTAINED.
4. THE LIMITS OF DISTURBANCE SHALL BE CLEARLY DELINEATED IN THE FIELD PRIOR TO GRADING OF THE SITE TO ENSURE COMPLIANCE WITH APPROVED PLANS. ALL FOREST RETENTION AREAS WILL BE DELINEATED WITH BLAZE ORANGE FENCE AS WELL AS ANY SWM INFILTRATION PRACTICE PRIOR TO ANY CLEARING. WORK BEYOND THE LIMITS OF DISTURBANCE AND IN ANY AREA INSIDE THE FOREST RETENTION AND SWM INFILTRATION AREA IS CONSIDERED TO BE A VIOLATION OF THIS PLAN.
5. ALL SEDIMENT CONTROL PRACTICES MUST BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITY. UPON COMPLETION OF THE INSTALLATION OF PERIMETER SEDIMENT CONTROL PRACTICES THE SITE MUST BE INSPECTED BY THE DEPARTMENT OF PUBLIC WORKS (DPW). NO ADDITIONAL CONSTRUCTION ACTIVITY WILL BE AUTHORIZED WITHOUT THE APPROVAL FROM DPW.
6. ALL POINTS OF INGRESS AND EGRESS SHALL BE PROTECTED TO PREVENT TRACKING OF MUD INTO PUBLIC WAYS. DURING CONSTRUCTION, EVERY MEANS WILL BE TAKEN TO CONTROL SOIL EROSION AND SILTATION. IF NECESSARY A WASH RACK MAY NEED TO BE ESTABLISHED.
7. EARTH DIKES, SEDIMENT TRAPS, ETC. WILL BE LOCATED AS SHOWN ON THESE DRAWINGS. FIELD CHANGES AND MINOR ADJUSTMENTS ARE PERMISSIBLE AS LONG AS THE INSTALLATION FUNCTIONS AND CONFORMS TO SPECIFICATIONS. THE SITE INSPECTOR PRIOR TO INSTALLATION MUST APPROVE ALL SUCH CHANGES. MAJOR CHANGES TO THE APPROVED PLAN WILL REQUIRE RE-APPROVAL BY THE HARFORD SOIL CONSERVATION DISTRICT.
8. FOLLOWING INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN:
 - a) THREE CALENDAR DAYS ON SLOPES GREATER THAN 3:1, ALL WATERWAYS AND TO THE SURFACE OF ALL PERIMETER CONTROLS.
 - b) SEVEN CALENDAR DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS OF THE PROJECT SITE.
9. DUST CONTROL MUST BE MANAGED AS PART OF ALL SEDIMENT CONTROL PLANS. FAILURE TO DO SO IS A VIOLATION OF THIS PLAN.
10. SEDIMENT BASINS MUST BE BUILT TO DESIGN SPECIFICATIONS SHOWN ON THE PLAN. IF THE BASIN IS TO BE USED AS A FUTURE SWM FACILITY, THE BASIN WILL BE BUILT IN ACCORDANCE WITH THE LATEST MD-378 STANDARDS AND SPECIFICATIONS. SPECIFIED MATERIALS MUST BE USED. NO CHANGES OR MODIFICATIONS WILL BE MADE WITHOUT WRITTEN AUTHORIZATION OF THE HARFORD SOIL CONSERVATION DISTRICT.
11. TEMPORARY FENCING SHALL BE PLACED AROUND ALL SEDIMENT BASINS, TRAPS, AND PONDS DURING CONSTRUCTION AND SITE GRADING.
12. AT THE END OF EACH WORKING DAY ALL SEDIMENT CONTROL PRACTICES WILL BE INSPECTED AND LEFT OPERATIONAL. A WEEKLY LOG WILL BE KEPT IN ACCORDANCE WITH NOI/NPDES REGULATIONS. A COPY OF THE APPROVED SEDIMENT CONTROL PLANS SHALL BE AVAILABLE AT THE SITE AT ALL TIMES.
13. ENSURE POSITIVE DRAINAGE TO ALL ROAD INLETS DURING ALL PHASES OF ROAD CONSTRUCTION TO ENSURE POSITIVE FLOW TO TRAPS AND OR BASINS.
14. CUT AND/OR FILL SHALL BE DONE IN CONFORMANCE WITH 2011 EROSION AND SEDIMENT CONTROL STANDARDS AND SPECIFICATIONS FOR LAND GRADING.
15. SURFACE FLOWS OVER CUT AND FILL SLOPES SHALL BE CONTROLLED BY EITHER REDIRECTING FLOWS FROM TRAVERSING THE SLOPES OR BY INSTALLING MECHANICAL DEVICES TO SAFELY CONVEY WATER DOWN SLOPES WITHOUT CAUSING EROSION.
16. OFF-SITE WASTE OR BORROW AREAS SHALL HAVE AN APPROVED EROSION AND SEDIMENT CONTROL PLAN PRIOR TO THE IMPORT OR EXPORT OF MATERIAL TO/FROM THE PROJECT SITE.
17. ALL MATERIAL ORIGINATING FROM THE DEVELOPMENT OF THE PROPERTY AND DEPOSITED ON THE PUBLIC RIGHT-OF-WAY SHALL BE IMMEDIATELY REMOVED.
18. STORM DRAIN INLETS AND OUTLETS SHALL BE PROTECTED PER 2011 EROSION AND SEDIMENT CONTROL STANDARDS AND SPECIFICATIONS.
19. TOPSOIL, LIMING, FERTILIZING, SEEDING, MULCHING, SOD, ETC. ARE ALL ESSENTIAL PARTS OF THE SEDIMENT CONTROL PLAN AND MUST BE COMPLETED ALONG WITH ALL OTHER PRACTICES.
20. TRAPS TO BE REMOVED SHALL BE DEWATERED AS PER THE 2011 EROSION AND SEDIMENT CONTROL STANDARDS AND SPECIFICATIONS.
21. PRIOR TO REMOVAL OF TRAPS OR CONVERSION OF SEDIMENT BASINS TO SWM FACILITIES, THE STORM DRAINS WILL BE FLUSHED.
22. SEDIMENT CONTROL PRACTICES WILL BE MAINTAINED UNTIL ALL DISTURBED AREAS FOR WHICH THE PRACTICES WERE INSTALLED HAVE BEEN STABILIZED. SEDIMENT CONTROL PRACTICES MAY BE REMOVED ONLY WITH THE AUTHORIZATION OF THE DPW INSPECTOR. ALL DISTURBED AREAS RESULTING FROM THE REMOVAL OF SEDIMENT CONTROL DEVICES SHALL BE STABILIZED IMMEDIATELY. REMOVAL PRIOR TO INSPECTOR'S APPROVAL CONSTITUTES A VIOLATION.

SEQUENCE OF CONSTRUCTION

REFER TO 2011 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR STANDARD NOTES, DETAILS, AND FOR THE INITIAL SEQUENCE OF CONSTRUCTION NOT SPECIFICALLY IDENTIFIED IN THE SEQUENCE OF CONSTRUCTION BELOW.

CHURCH CREEK STREAM RESTORATION:

PRIOR TO CLEARING TREES, INSTALLING SEDIMENT CONTROL MEASURES, OR GRADING, A PRE-CONSTRUCTION MEETING MUST BE CONDUCTED ON-SITE WITH THE HARFORD COUNTY DEPARTMENT OF PUBLIC WORKS, SEDIMENT CONTROL INSPECTOR (48 HOURS NOTICE) THE OWNERS REPRESENTATIVE, AND THE SITE ENGINEER.

1. THE LIMITS OF DISTURBANCE MUST BE FIELD MARKED PRIOR TO CLEARING OF TREES, INSTALLATION OF SEDIMENT CONTROL MEASURES, CONSTRUCTION, OR OTHER LAND DISTURBING ACTIVITIES.
2. WITH APPROVAL OF DEPARTMENT OF PUBLIC WORKS AND MD STATE HIGHWAY ADMINISTRATION, INSTALL THE STABILIZED CONSTRUCTION ENTRANCES OFF OF RIVERSIDE PARKWAY AND CHURCH CREEK ROAD AS SHOWN ON THE EROSION AND SEDIMENT CONTROL PLANS AND MAINTENANCE OF TRAFFIC PLANS. CONTRACTOR SHALL USE FLAGGERS AS NECESSARY FOR WALKING AND BIKE PATH TRAFFIC.
3. INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES (SSF, SF, SCE, TEMP. PIPES, TEMP. RIPRAP, SANDBAGS, PUMPS AND FILTER BAGS) AS SHOWN ON THE ESC PLANS AND SPECIFIED IN GENERAL NOTES.
4. ONCE THE SEDIMENT CONTROL DEVICES ARE INSTALLED, THE CONTRACTOR MUST OBTAIN WRITTEN APPROVAL FROM SEDIMENT CONTROL INSPECTOR BEFORE PROCEEDING WITH ANY GRADING OR CONSTRUCTION.
5. GRADE FOR AND INSTALL TEMPORARY ACCESS ROADS AND STAGING AREAS.
6. THE STREAM RESTORATION, GRAVEL WETLAND AND STORMWATER MANAGEMENT FACILITIES CAN BE CONSTRUCTED INDEPENDENTLY AND IN ANY ORDER PREFERRED BY THE CONTRACTOR FOLLOWING THE EROSION AND SEDIMENT CONTROL AND MAINTENANCE OF TRAFFIC PLANS.

GRAVEL WETLAND:

7. ACCESS IS FROM RIVERSIDE PARKWAY AND IS SHARED WITH THE UPSTREAM RESTORATION ACCESS.
8. SEE SHEET EP-B1 FOR DETAILED SEQUENCE OF CONSTRUCTION FOR THE LID/ BMP'S.

SWM/ESD SITES:

9. ACCESS TO THESE SITES ARE FROM CHURCH CREEK ROAD AND THE SCHOOL LOADING DOCK AREA. THE OVERALL DISTURBANCE IN THESE AREAS IS LESS THAN 5000 SF AND A STABILIZED CONSTRUCTION ENTRANCE IS NOT NECESSARY FOR WORK IN THIS AREA. THE CONTRACTOR IS RESPONSIBLE TO KEEP ALL SEDIMENT AND SEDIMENT LADEN RUNOFF FROM REACHING THE ROADWAY OR STORM DRAIN SYSTEM. SEE SHEET EP-B1 FOR DETAILED SEQUENCE OF CONSTRUCTION FOR THE LID/ BMP'S.

STREAM RESTORATION:

10. THERE ARE 2 PROPOSED CONSTRUCTION ENTRANCES FOR THE STREAM PORTION OF CONSTRUCTION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO IMPLEMENT THE APPROPRIATE PUMP AROUND AND SEDIMENT CONTROL PRACTICES. THE CONTRACTOR SHALL SEQUENCE THE WORK TO BALANCE THE CUT/FILL AND MINIMIZE THE AMOUNT OF SOIL MATERIAL THAT HAS TO BE REMOVED AND BROUGHT ONTO THE SITE.
11. THE UPSTREAM REACH ACCESS IS OFF OF RIVERSIDE PARKWAY AND IS SHARED WITH THE LID/ BMP'S ACCESS. INSTALL SANDBAG DIKES, PUMPS, OUTFALL DIVERSION PIPES AND DEWATERING DEVICES FROM STATION 1+50 TO 6+64 INCLUDING ALL TRIBUTARIES UPSTREAM OF STA. 6+64 WITHIN THE DRY WORKING ZONE.
12. BEGIN STREAM REPAIRS AS SHOWN ON STREAM RESTORATION PLANS, PROFILES, AND DETAILS. UTILIZE DEWATERING PUMP TO DEWATER EXCAVATED AREAS.
13. AFTER COMPLETION OF ALL PROPOSED IMPROVEMENTS, PERMANENTLY STABILIZE ALL DISTURBED AREAS.
14. INSTALL PROPOSED TREES, SHRUBS AND OTHER PLANTINGS AS PER THE PLANTING PLANS AND DETAILS.
15. CONTRACTOR SHALL OBTAIN WRITTEN APPROVAL FROM SEDIMENT CONTROL INSPECTOR PRIOR TO THE REMOVAL OF SEDIMENT CONTROL DEVICES INCLUDING STREAM DIVERSION PUMPS AND STRUCTURES.
16. WITH THE APPROVAL OF SEDIMENT CONTROL INSPECTOR, REMOVE ALL REMAINING SEDIMENT CONTROL DEVICES. REMOVE STREAM DIVERSION PUMPS AND STRUCTURES AND PERMANENTLY STABILIZE ALL DISTURBED AREAS.
17. THE DOWNSTREAM ACCESS IS OFF OF CHURCH CREEK ROAD. INSTALL SANDBAG DIKES, PUMPS, OUTFALL DIVERSION PIPES AND DEWATERING DEVICES FROM STATION 6+64 TO 19+16 INCLUDING ALL TRIBUTARIES UPSTREAM OF STA. 19+16 WITHIN THE DRY WORKING ZONE.
18. REPEAT STEPS 12-16 FOR THIS PORTION OF THE STREAM WORK. BE ADVISED THAT FROM STATION 5+00 THROUGH 8+50 ACCESS TO THE STREAM WILL BE ACHIEVED BY IN-STREAM ROUTING.
19. REMOVE TEMPORARY ACCESS ROAD AND ALL ASSOCIATED STRUCTURES. COMPLETE GRADING AFTER REMOVAL.
20. PERMANENTLY STABILIZE DISTURBED AREAS AFTER ACCESS ROAD REMOVAL.

ENGINEER'S CERTIFICATION	
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.	
DESIGN ENGINEER SIGNATURE <i>Gregory Fox</i>	EXPIRATION DATE 02-01-19 02-16-22
GREGORY FOX PRINTED NAME	31177 GWF REGISTRATION NUMBER
OWNER'S CERTIFICATION	
I HEREBY CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATION OF ATTENDANCE AT A MARYLAND DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HARFORD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS OR AS DEEMED NECESSARY.	
OWNER/DEVELOPER SIGNATURE <i>Joseph J. Siemak</i>	DATE 2-12-18
JOSEPH J. SIEMAK - DIRECTOR DPW PRINTED NAME AND TITLE	

EROSION AND SEDIMENT CONTROL PLAN# 59832	
RECOMMENDED FOR APPROVAL: <i>John D. Amick</i> 3-2-18 HARFORD COUNTY, DPW	
TECHNICAL CONCURRENCE: <i>John D. Amick</i> 3-14-18 HARFORD SOIL CONSERVATION DISTRICT	
APPROVED: <i>W.C. P. Jr.</i> 3/15/18 HARFORD SOIL CONSERVATION DISTRICT	

UPDATE

EROSION AND SEDIMENT CONTROL PLAN# 59832	
RECOMMENDED FOR APPROVAL: HARFORD COUNTY, DPW	
TECHNICAL CONCURRENCE: HARFORD SOIL CONSERVATION DISTRICT	
APPROVED: HARFORD SOIL CONSERVATION DISTRICT	

EG-SWMENG-000747-2016 S/C PLAN # 59832 ¹⁸⁰²⁷³ GRADING PERMIT # 9386-2017

Revisions	HARFORD COUNTY, MARYLAND SEDIMENT CONTROL NOTES AND DETAILS - STREAM	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ NOT TO SCALE
Reviewed By : _____	GWF	Sheet <u>84</u> Of <u>78</u>
		Date : <u>2/16/2022</u>

ADC MAP : TAX MAP : HCC BILLING ID No.: HCC DWG ID No.: SCALE: 1"=40'

PLANTING ZONES




ZONE 1: LIVESTAKE PLANTING AND STREAMSIDE SEEDING AREA



ZONE 4: RIPARIAN TREE, SHRUB AND SEED PLANTING




ZONE 5: TURF SOD



BOARD OF EDUCATION OF HARFORD COUNTY
 4299 CHURCH CREEK ROAD
 BELCAMP MD 21017
 TAX MAP 0062 LOT 1 PARCEL 0813
 LIBER 01858
 FOLIO 0954
 PLAT 77/72

MATCHLINE SEE SHEET 69

EG-SWMENG-000747-2016



Revisions		HARFORD COUNTY, MARYLAND	
		LANDSCAPE PLAN - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	65 Of 78
		Date :	2/17/2022


LS-A1

ADC MAP :


TAX MAP :

HCC BILLING ID No.:


HCC DWG ID No.:



PLANTING ZONES

-  ZONE 1: LIVESTAKE PLANTING AND STREAMSIDE SEEDING AREA
-  ZONE 2: STREAMSIDE TREE, SHRUB & SEED PLANTING AREA
-  ZONE 3: WETLAND TREE, SHRUB AND SEEDING AREA
-  ZONE 4: RIPARIAN TREE, SHRUB AND SEED PLANTING

EG-SWMENG-000747-2016



Revisions		HARFORD COUNTY, MARYLAND	
		LANDSCAPE PLAN - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	66 Of 78
		Date :	2/17/2022

LS-A2

MATCHLINE SEE SHEET 65

MATCHLINE SEE SHEET 65

MATCHLINE SEE SHEET 70

MATCHLINE SEE SHEET 70

MATCHLINE SEE SHEET 67

ADC MAP :

TAX MAP :

HCC BILLING ID No.:

HCC DWG ID No.:


MATCHLINE SEE SHEET 66

MATCHLINE SEE SHEET 68



PLANTING ZONES

-  ZONE 1: LIVESTAKE PLANTING AND STREAMSIDE SEEDING AREA
-  ZONE 2: STREAMSIDE TREE, SHRUB & SEED PLANTING AREA
-  ZONE 3: WETLAND TREE, SHRUB AND SEEDING AREA
-  ZONE 4: RIPARIAN TREE, SHRUB AND SEED PLANTING



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		LANDSCAPE PLAN - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	67 Of 78
		Date :	2/17/2022

LS-A3

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

GROUND COVERS



ZONE 1: LIVESTAKE PLANTING AND STREAMSIDE SEEDING AREA



ZONE 3: WETLAND TREE, SHRUB AND SEEDING AREA



ZONE 4: RIPARIAN TREE, SHRUB AND SEED PLANTING




ZONE 5: TURF SOD

MATCHLINE SEE SHEET 67



EG-SWMENG-000747-2016



Revisions		HARFORD COUNTY, MARYLAND	
		LANDSCAPE PLAN - STREAM	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	1"=20'
Reviewed By :	GWF	Sheet	68 Of 78
		Date :	2/17/2022

LS-A4

ADC MAP :

TAX MAP :

HCC BILLING ID No.:


HCC DWG ID No.:



MATCHLINE SEE SHEET 65

PLANTING ZONES

 ZONE 5: TURF SOD



EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	LANDSCAPE PLAN - STREAM	
Drawn By :	LBT	Contract No : DP1602779
Designed By :	MCB	Scale : 1"=20'
Reviewed By :	GWF	Sheet 69 Of 78
		Date : 2/16/2022

LS-A5

ADC MAP :

TAX MAP :

HCG BILLING ID No.:


HCG DWG ID No.:

SCALE 1"=20'


CHAPPEL GATE CT & PLACE
BEL CAMP MD 21017
LIBER 01858
FOLIO 0954
PLAT 7772
TAX MAP 0062 LOT 1 PARCEL 0813
LIBER 01858
FOLIO 0954
PLAT 7772

BOARD OF EDUCATION OF HARFORD COUNTY
4299 CHURCH CREEK ROAD
BEL CAMP MD 21017
TAX MAP 0062 LOT 1 PARCEL 0813
LIBER 01858
FOLIO 0954
PLAT 7772

INFILTRATION TRENCH



SUBMERGED GRAVEL WETLAND



UNM - ERNMX-172 / UPLAND NATIVE SEED MIX*

71.9%	Schizachyrium scoparium	Little Bluestem
15.0%	Elymus virginicus	Virginia Wildrye
3.0%	Asclepias tuberosa	Butterfly Milkweed
3.0%	Rudbeckia hirta	Blackeyed Susan
2.0%	Chamaecrista fasciculata	Partridge Pea
1.0%	Aster laevis	Smooth Blue Aster
1.0%	Lespedeza virginica	Slender Lespedeza
0.5%	Aster novae-angliae	New England Aster
0.5%	Monarda fistulosa	Wild Bergamot
0.4%	Senna hebecarpa	Wild Senna
0.3%	Chamaecrista nictitans	Sensitive Pea
0.3%	Senna marilandica	Maryland Senna
0.3%	Solidago juncea	Early Goldenrod
0.3%	Solidago nemoralis	Gray Goldenrod
0.3%	Vernonia noveboracensis	New York Ironweed
0.2%	Baptisia tinctoria	Yellow False Indigo
100%	TOTAL	

* SEEDING RATE: 20 LBS/ACRE

WNM - WETLAND NATIVE PLANT MIX

13%	Acorus americanus	Sweet Flag
13%	Alisma subcordatum	Water Plantain
13%	Hibiscus moscheutos	Marsh Hibiscus
13%	Iris versicolor	Blue Flag Iris
13%	Peltandra virginica	Arrow Arum
13%	Pontederia cordata	Pickersweed
11%	Saururus cernuus	Lizard's Tail
11%	Scirpus fluviatilis	River Bulrush
100%	TOTAL	

RNM - RIPARIAN NATIVE PLANT MIX

20%	Andropogon gerardii	Big Bluestem
14%	Asclepias incarnata	Swamp Milkweed
14%	Eupatorium dubium	Joe-pye Weed
20%	Juncus effusus	Soft Rush
12%	Liatris spicata	Blazingstar
20%	Sorghastrum nutans	Indiangrass
100%	TOTAL	

PLANT EACH SPECIES IN RANDOM GROUPS OF 13 TO 25 PLANTS.
PLANTS SHALL BE INSTALLED INTO UNDATED CONDITIONS.

TURFGRASS ESTABLISHMENT SEED MIX*

33%	Poa pretensis	Kentucky Bluegrass
34%	Schedanoris pheonix	Tall Fescue
33%	Lolium perenne	Perennial Rye Grass
100%	TOTAL	

*SEEDING RATE: 25 LBS/ACRE

GENERAL PLANTING NOTES:


- THIS PLAN IS FOR PLANTING PURPOSES ONLY, AND ANY OTHER INFORMATION SHOWN IS **FOR REFERENCE ONLY**. SEE SITE PLAN FOR INFORMATION ABOUT ALL LAYOUT, GRADING AND OTHER SITE IMPROVEMENTS.
- CALL MISS UTILITY AT 811 OR 1-800-257-7777 TO MARK UTILITIES AT LEAST 48 HOURS BEFORE DIGGING.
- All materials and planting procedures except as otherwise noted shall conform to the latest edition of "LANDSCAPE SPECIFICATION GUIDELINES" by the Landscape Contractors Association MD-DC-VA.
- Plants shall conform to the current edition of the American Standard for Nursery Stock, (ANSI z60.1)
- Plant names shall be those given in the latest edition of Standard Plant Names, American Committee on Horticultural Nomenclature.
- Topsoil shall meet specifications as per the 2011 MD Standards and Specifications for Soil Erosion and Sediment Control.
- The Contractor shall submit representative soil samples from both in-situ soils and soils brought in from off-site to a state licensed testing laboratory. The Contractor shall incorporate or apply soil amendments and fertilization based upon results of the soil tests and recommendations by the test lab.
- The Contractor shall apply grass according to the 2011 MD Standard and Specifications for Soil Erosion and Sediment Control. Do not use Kentucky 31 tall fescue.
- The Contractor shall stake out all planting beds and tree locations for approval by the Landscape Architect or Owner and representative before digging. It is the Contractor's responsibility to locate and coordinate plantings with all existing utilities. If discrepancies occur because of utility locations or other existing conditions the Contractor shall notify the Landscape Architect and Owner's representative immediately to coordinate any necessary adjustments.
- All plant material shall be labeled by the nursery and delivered with labels in place for inspection. Substitutions in plant species or size will not be permitted except with the approval of the Landscape Architect and Owner. Do not prune until plant material has been planted but as soon thereafter as is advisable under standard horticultural practices. For tree pruning and care methods please refer to ANSI A-300, latest edition.
- It is of utmost importance that all plant material be set slightly higher in relation to grade than it was grown in the nursery and with good earth to root contact. Any materials or work may be rejected by the Landscape Architect if it does not meet this or any other requirement of the specifications. Rejected materials shall be removed from the site by the Contractor at Contractor's expense.
- The Contractor shall mulch and water all plants well on the day they are planted. Individual planting shall be mulched. Acceptable mulch shall be hardwood only. Mulch must be well aged, uniform in color, and free of foreign material including plant material. Well aged mulch is defined as mulch that has been stockpiled or stored for at least twelve (12) months. The Contractor shall apply the mulch uniformly to a 2 to 3 inch depth. Bark shall be kept 3 to 4 inches away from all trunks and woody stems.
- In case of discrepancies between quantities on the plant list and the plan, the plan shall govern.
- Seed or sod bare areas as directed by Owner for all disturbed areas to be stabilized that are not landscaped or covered.
- Wetland plants must be wet cultured for a minimum of 3 months and supplied by a recognized wetland nursery which will provide certification of the culture process. Upland plants can be supplied from standard upland grown nursery operations. See the following list for suggested wetland plant sources:

Signature Horticultural Services 19960 Core Mill Road Freeland, MD 21053 TEL: 410-329-6466 FAX: 410-329-2156	Environmental Concern P.O. Box P 201 Boundary Lane St. Michaels, MD 21663 TEL: 410-745-9620	Octoraro Native Plant Nursery 6126 Street Road Kirkwood, PA 17536 TEL: 717-529-3160 FAX: 717-529-4099	Wicklin's Water Gardens 1820 Cromwell Bridge Road Baltimore, MD 21234 TEL: 410-823-1335 FAX: 410-823-1427
--	---	---	---

EG-SWMENG-000747-2016

PLANT CENTER	SPACING "D"	ROW "A"	PLANTS PER 10 SQ. FT.
TRIANGULAR PLANT SPACING ALL EQUAL OR AS SHOWN ON PLANTING PLAN	8" O.C.	6.93"	26
	12" O.C.	10.4"	11.5
	18" O.C.	15.6"	5.12
	20" O.C.	17.3"	2.42
	24" O.C.	20.8"	2.9
	36" O.C.	30.0"	1.28

NOTE: QUANTITY OF PERENNIALS AND SPACING AS NOTED IN PLANT SCHEDULE




1 HERBACEOUS & GRASS PLANTING DETAIL

NOT TO SCALE 329301-05

PLANT SCHEDULE

GROUND COVERS	CODE	QTY	PLANT MATERIAL	CONT	SPACING
	UNM	14,556 SF	ERNMX-172 UPLAND NATIVE SEED MIX	SEED	
	RNM	2,103	RIPARIAN NATIVE PLANT MIX SEE PLANT LIST THIS SHEET	1 QT	24" o.c.
	WNM	803	WETLAND NATIVE PLANT MIX SEE PLANT LIST THIS SHEET	2.25"x5" PLUG	24" o.c.
	SOD	9,836 SF	TURFGRASS ESTABLISHMENT SEE PLANT LIST THIS SHEET	SEED	




Revisions	HARFORD COUNTY, MARYLAND	
	LANDSCAPE PLAN - SWM	
Drawn By : JS / MTB	Contract No : DP1602779	
Designed By : JS / MTB	Scale : 1"=20'	
Reviewed By : MAE	Sheet 70 Of 78	
	Date : 2/16/2022	LS-B1

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:




- NOTES:
1. RETENTION AREAS WILL BE SET AS PART OF THE REVIEW PROCESS AND PRECONSTRUCTION MEETING.
 2. BOUNDARIES OF RETENTION AREAS MUST BE STAKED AT THE PRECONSTRUCTION MEETING AND FLAGGED PRIOR TO TRENCHING.
 3. EXACT LOCATION OF TRENCH SHALL BE DETERMINED IN THE FIELD IN COORDINATION WITH THE FOREST CONSERVATION (FC) INSPECTOR.
 4. TRENCH SHOULD BE IMMEDIATELY BACKFILLED WITH EXCAVATED SOIL OR OTHER ORGANIC SOIL AS SPECIFIED PER PLAN OR BY THE FC INSPECTOR.
 5. ROOTS SHALL BE CLEANLY CUT USING VIBRATORY KNIFE OR OTHER ACCEPTABLE EQUIPMENT.
 6. ALL PRUNING MUST BE EXECUTED WITH LOD SHOWN ON PLANS OR AS AUTHORIZED IN WRITING BY THE FC INSPECTOR.

ROOT PRUNING DETAIL


NTS

TREE PROTECTION SIGNAGE



1. ATTACHMENT TO TREES IS PROHIBITED
2. SIGNS MUST BE PROPERLY MAINTAINED
3. AVOID INJURING ROOTS WHEN PLACING POSTS FOR SIGNS.
4. SIGNS MUST BE POSTED TO BE VISIBLE TO ALL CONSTRUCTION PERSONNEL FROM ALL DIRECTIONS


**STRESS REDUCTION MEASURE
ROOT PRUNING WITH FENCE**



- NOTES:
1. RETENTION AREAS WILL BE SET AS PART OF THE REVIEW PROCESS.
 2. BOUNDARIES OF RETENTION AREAS SHOULD BE STAKED AND FLAGGED PRIOR TO TRENCHING
 3. EXACT LOCATION OF TRENCH SHOULD BE IDENTIFIED.
 4. ROOTS SHOULD BE CLEANLY CUT USING VIBRATORY KNIFE OR OTHER ACCEPTABLE EQUIPMENT.
 5. TRENCH SHOULD BE IMMEDIATELY BACKFILLED WITH SOIL REMOVED OR OTHER HIGH ORGANIC SOIL.

NOT TO SCALE


**TREE PROTECTION FENCING
ORANGE CONSTRUCTION FENCE (OCF)**



- NOTES:
1. FOREST PROTECTION DEVICE ONLY.
 2. BOUNDARIES OF RETENTION AREA SHOULD BE STAKED AND FLAGGED PRIOR TO INSTALLATION OF DEVICE.
 3. AVOID ROOT DAMAGE WHEN PLACING POSTS.
 4. PROTECTIVE SIGNAGE IS REQUIRED.
 5. DEVICE MUST BE MAINTAINED THROUGHOUT DURATION OF CONSTRUCTION.
 6. TREE PROTECTION FENCING MAY BE COMBINED WITH SUPER SILT FENCE


NOT TO SCALE

CONTAINER GROWN TREE PLANTING DETAIL



NOT TO SCALE

CONTAINER GROWN SHRUB DETAIL



- NOTES:
1. REMOVE ALL NON-ORGANIC MATERIAL FROM THE SOIL PIT AND HAND TAMP LOOSE SOIL AT BOTTOM OF THE PIT
 2. PLANT EVERGREEN AND DECIDUOUS SHRUBS USING THE SAME METHOD

NOT TO SCALE

ZONES 1 & 2: STREAMSIDE/STREAMBANK SEED MIX		
ERNST MIX ERNMX-723 OR APPROVED EQUAL (15 lbs/acre)		
SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Carex vulpinoidea</i>	Fox Sedge	20%
<i>Elymus virginicus</i>	Virginia Wildrye	12%
<i>Carex squarrosa</i>	Squarrose Sedge	8%
<i>Carex lurida</i>	Lurid (Shallow) Sedge	8%
<i>Carex scoparia</i>	Blunt Broom Sedge	8%
<i>Panicum rigidulum (P. stipitatum)</i>	Redtop Panicgrass	5%
<i>Carex lupulina</i>	Hop Sedge	4%
<i>Juncus effusus</i>	Soft Rush	4%
<i>Helenium autumnale</i>	Common Sneezeweed	4%
<i>Eupatorium maculatum</i>	Spotted Joe Pye Weed	3%
<i>Bidens cernua</i>	Nodding Bur Marigold	3%
<i>Scirpus cyperinus</i>	Woolgrass	2%
<i>Carex baileyi</i>	Bailey's Sedge	2%
<i>Euthamia graminifolia (Solidago g.)</i>	Grassleaf Goldenrod	2%
<i>Eupatorium perfoliatum</i>	Boneset	2%
<i>Verbena hastata</i>	Blue Vervain	2%
<i>Panicum anceps</i>	Beaked Panicgrass	2%
<i>Aster prenanthoides (Symphyotrichum p.)</i>	Zigzag Aster	1%
<i>Onoclea sensibilis</i>	Sensitive Fern	1%
<i>Glyceria canadensis</i>	Rattlesnake Grass	1%
<i>Ludwigia alternifolia</i>	Seedbox	1%
<i>Vernonia noveboracensis</i>	New York Ironweed	1%
<i>Carex crinita</i>	Fringed (Nodding) Sedge	1%
<i>Asclepias incarnata</i>	Swamp Milkweed	1%
<i>Aster puniceus (Symphyotrichum puniceum)</i>	Purplestem Aster	1%
<i>Mimulus ringens</i>	Square Stemmed Monkeyflower	1%
	TOTAL (lbs)	2.31

ZONE 3: WETLAND SEED MIX		
ERNST MIX ERNMX-724 OR APPROVED EQUAL (15 lbs/acre)		
SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Carex vulpinoidea</i>	Fox Sedge	20%
<i>Sparganium eurycarpum</i>	Giant Bur Reed	18%
<i>Carex lurida</i>	Lurid (Shallow) Sedge	8%
<i>Carex scoparia</i>	Blunt Broom Sedge	7%
<i>Panicum rigidulum (P. stipitatum)</i>	Redtop Panicgrass	5%
<i>Carex squarrosa</i>	Squarrose Sedge	5%
<i>Juncus effusus</i>	Soft Rush	4%
<i>Helenium autumnale</i>	Common Sneezeweed	4%
<i>Carex lupulina</i>	Hop Sedge	4%
<i>Eupatorium perfoliatum</i>	Boneset	3%
<i>Eupatorium maculatum (Eupatoriadelphus maculatus)</i>	Spotted Joe Pye Weed	3%
<i>Bidens cernua</i>	Nodding Bur Marigold	3%
<i>Carex comosa</i>	Cosmos (Bristly) Sedge	2%
<i>Mimulus ringens</i>	Square Stemmed Monkeyflower	2%
<i>Carex baileyi</i>	Bailey's Sedge	2%
<i>Scirpus cyperinus</i>	Woolgrass	2%
<i>Verbena hastata</i>	Blue Vervain	2%
<i>Glyceria canadensis</i>	Rattlesnake Grass	1%
<i>Ludwigia alternifolia</i>	Seedbox	1%
<i>Vernonia noveboracensis</i>	New York Ironweed	1%
<i>Asclepias incarnata</i>	Swamp Milkweed	1%
<i>Aster puniceus (Symphyotrichum puniceum)</i>	Purplestem Aster	1%
<i>Carex crinita</i>	Fringed (Nodding) Sedge	1%
	TOTAL (lbs)	3.03

ZONE 4: RIPARIAN BUFFER SEED MIX		
ERNST MIX ERNMX-722 OR APPROVED EQUAL (15 lbs/acre)		
SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Elymus riparius</i>	Riverbank Wildrye	20%
<i>Panicum clandestinum (Dichanthelium c.)</i>	Deertongue	15%
<i>Schizachyrium scoparium</i>	Little Bluestem	12%
<i>Elymus virginicus</i>	Virginia Wildrye	10%
<i>Andropogon gerardii</i>	Big Bluestem	10%
<i>Sorghastrum nutans</i>	Indiangrass	10%
<i>Senna marilandica (Cassia m.)</i>	Maryland Senna	5%
<i>Chasmanthium latifolium (Uniola latifolia)</i>	River Oats	5%
<i>Senna hebecarpa (Cassia h.)</i>	Wild Senna	5%
<i>Panicum rigidulum (P. stipitatum)</i>	Redtop Panicgrass	4%
<i>Agrostis perennans</i>	Autumn Bentgrass	2%
<i>Panicum anceps</i>	Beaked Panicgrass	2%
	TOTAL (lbs)	43.70

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	LANDSCAPE NOTES AND DETAILS	
Drawn By : _____	LBT	Contract No : _____ DP1602779
Designed By : _____	MCB	Scale : _____ NOT TO SCALE
Reviewed By : _____	GWF	Sheet <u>71</u> Of <u>78</u>
		Date : <u>2/17/2022</u>

LD-A1

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE 1"=10'


ZONE 1: LIVE STAKE PLANTING SCHEDULE				
(SPACED 3 FT ON CENTER)				
SCIENTIFIC NAME	COMMON NAME	SIZE	RATIO	APPROX #
<i>Cornus sericea cardinalis</i>	Red Osier Dogwood	2'-3'	25%	419
<i>Cornus amomum</i>	Silky Dogwood	2'-3'	50%	839
<i>Salix sericea</i>	Silky Willow	2'-3'	25%	419
			TOTAL	1677

ZONE 2: STREAMSIDE TREES & SHRUBS				
SHRUBS (SPACED 15 FT ON CENTER)				
SCIENTIFIC NAME	COMMON NAME	MINIMUM SIZE/CONTAINER	PERCENT OF TOTAL	QUANTITY
<i>Lindera benzoin</i>	Spicebush	18"-24" / #2	25%	10
<i>Viburnum dentatum</i>	Arrow-Wood Viburnum	18"-24" / #2	20%	8
<i>Cornus Amomum</i>	Silky Dogwood	18"-24" / #2	20%	8
<i>Amelanchier arborea</i>	Serviceberry	18"-24" / #2	10%	4
<i>Clethra alnifolia</i>	Sweet Pepperbush	18"-24" / #2	25%	10
			TOTAL	40
TREES (SPACED 20 FT ON CENTER)				
<i>Betula nigra</i>	River Birch	1" CAL. / #5	50%	5
<i>Platanus occidentalis</i>	American Sycamore	1" CAL. / #5	50%	5
			TOTAL	10

ZONE 3: WETLAND TREES & SHRUBS SCHEDULE				
SHRUBS (SPACED 15 FT ON CENTER)				
SCIENTIFIC NAME	COMMON NAME	MINIMUM SIZE/CONTAINER	PERCENT OF TOTAL	QUANTITY
<i>Cornus amomum</i>	Silky Dogwood	18"-24" / #2	25%	12
<i>Sambucus canadensis</i>	Elderberry	18"-24" / #2	25%	12
<i>Viburnum dentatum</i>	Arrowwood Viburnum	18"-24" / #2	25%	12
<i>Clethra alnifolia</i>	Sweet Pepperbrush	18"-24" / #2	25%	12
			TOTAL	48
TREES (SPACED 20 FT ON CENTER)				
<i>Nyssa sylvatica</i>	Black Gum	1" CAL. / #5	20%	4
<i>Quercus Phellos</i>	Willow Oak	1" CAL. / #5	20%	4
<i>Quercus Bicolor</i>	Swamp White Oak	1" CAL. / #5	20%	4
<i>Liquidambar styraciflua</i>	Sweet Gum	1" CAL. / #5	20%	4
<i>Platanus occidentalis</i>	Sycamore	1" CAL. / #5	20%	4
			TOTAL	20

ZONE 4: RIPARIAN TREES & SHRUBS				
SHRUBS (SPACED 15 FT ON CENTER)				
SCIENTIFIC NAME	COMMON NAME	MINIMUM SIZE/CONTAINER	PERCENT OF TOTAL	QUANTITY
<i>Lindera benzoin</i>	Spicebush	18"-24" / #2	20%	144
<i>Ilex Opaca</i>	American Holly	18"-24" / #2	25%	180
<i>Viburnum prunifolium</i>	Blackhaw Viburnum	18"-24" / #2	20%	144
<i>Amelanchier arborea</i>	Serviceberry	18"-24" / #2	15%	108
<i>Hamamelis virginiana</i>	Witch Hazel	18"-24" / #2	20%	144
			TOTAL	720
TREES (SPACED 20 FT ON CENTER)				
<i>Fagus grandifolia</i>	American Beech	1" CAL. / #5	20%	81
<i>Liriodendron tulipifera</i>	Tulip Poplar	1" CAL. / #5	20%	81
<i>Nyssa sylvatica</i>	Black Gum	1" CAL. / #5	20%	81
<i>Quercus Phellos</i>	Willow Oak	1" CAL. / #5	20%	81
<i>Quercus rubra</i>	Red Oak	1" CAL. / #5	20%	81
			TOTAL	405

ZONE 5: TURF SOD	
AREA	UNITS
25,786	Square Feet



CHURCH CREEK SWM AND STREAM RESTORATION EXISTING TREE INVENTORY AND REMOVAL TABLE						
TREE NUMBER	DBH (IN.)	SPECIES	CONDITION	NOTES	TREE TO BE REMOVED	TREE TO BE RE-USED ONSITE
01	34.0	Tuliptree	Fair	Vines into the canopy		
02	25.5	Tuliptree	Fair	Vines		
03	20.7	Tuliptree	Good			
04	25.1	Tuliptree	Fair	Vines		
05	27.7	Tuliptree	Good			
06	25.5	Sweetgum	Good			
07	36.5	White Oak	Fair	Vines		
08	30.8	Tuliptree	Fair	Vines/Dead Branches		
09	28.8	N. Red Oak	Good			
10	27.8	Tuliptree	Good		Yes	Yes
11	35.5	N. Red Oak	Good			
12	25.4	Chestnut Oak	Fair	Vines		
13	0.0	DEAD	Dead			
14	29.3	N. Red Oak	Good			
15	29.6	N. Red Oak	Good			
16	25.2	Red Maple	Good			
17	0.0	DEAD	Dead			
18	0.0	DEAD	Dead			
19	22.5	Sycamore	Fair	Vines/Treehouse		
20	0.0	Sycamore	Dead			
21	40.0	Tuliptree	Poor	Many Vines/Rotting Heartwood		
22	36.9	Red Oak	Good	On TOB	Yes	Yes
23	37.7	Red Oak	Fair	Vines/Dead Branches	Yes	Yes
24	27.1	Red Oak	Poor/Dead	Very Poor/Vines/Many Dead Branches	Yes	Yes
25	41.9	Red Oak	Good			
26	35.6	American Sycamore	Good			
27	24.0	White Oak	Good		Yes	Yes
28	23.0	White Oak	Good			
29	29.3	White Oak	Good			
30	32.0	White Oak	Good			
31	25.1	White Oak	Fair	Vines/Dead Branches		
32	30.7	White Oak	Good			
33	31.7	White Oak	Fair			
34	0.0	NA	Dead	Has fallen in the stream		
35	0.0	Red Oak	Dead			
36	18.8	Red Maple	Good			
37	28.5	Tuliptree	Good			
38	25.4	White Oak	Good	Some vines		
39	27.5	Tuliptree	Good			
40	22.2	Tuliptree	Good			
41	23.3	White Oak	Good			
42	24.6	Tuliptree	Good			
43	35.4	Red Maple	Good			
44	35.0	Tuliptree	Good			
45	24.2	Sweetgum	Good			
46	33.1	Tuliptree	Good			
47	49.3	Red Maple	Good			
48	30.2	American Beech	Good			
49	23.5	American Beech	Good			
50	24.9	N. Red Oak	Good			
51	26.2	N. Red Oak	Good			
52	36.8	Tuliptree	Good			
53	27.4	American Beech	Good			
54	0.0	DEAD (White Oak)	Dead	Dead		
55	29.8	American Beech	Good			
56	30.2	American Beech	Good			
57	0.0	DEAD (Tuliptree)	Dead	Vines		
58	30.4	American Beech	Good			
59	29.4	N. Red Oak	Good			
60	22.5	N. Red Oak	Good			
61	22.5	White Oak	Good		Yes	Yes
62	25.9	White Oak	Good			
63	31.9	Tuliptree	Good			
64	23.9	N. Red Oak	Good		Yes	Yes

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	LANDSCAPE NOTES AND DETAILS	
	Drawn By : _____ LBT Designed By : _____ MCB Reviewed By : _____ GWF	Contract No : _____ DP1602779 Scale : _____ NOT TO SCALE Sheet <u>72</u> Of <u>78</u> Date : <u>2/17/2022</u>

LD-A2

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.: SCALE: 1"=100'

GENERAL REQUIREMENTS:

1. THE CONTRACTOR SHALL REFER TO THE MAINTENANCE OF TRAFFIC PLAN (MT) DRAWINGS TO SELECT THE APPROPRIATE WORK ZONE TEMPORARY TRAFFIC CONTROLS FOR EACH PHASE OF CONSTRUCTION. WORK ZONE SITUATIONS WHICH ARE NOT ADDRESSED IN THE MT SHALL CONFORM TO THE GUIDELINES SET FORTH IN PART 6 OF THE MARYLAND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES OF STREETS AND HIGHWAY (MDMUTCD) AND CATEGORY 1 OF THE MDSHA BOOK OF STANDARDS.
2. THE CONTRACTOR MUST HAVE A "CERTIFIED" TRAFFIC CONTROL MANAGER ON SITE DURING ALL PHASES OF CONSTRUCTION AT ALL TIMES.
3. EACH PHASE OF CONSTRUCTION, INCLUDING THE FOLLOW UP RESTORATION OPERATIONS SHALL BE PROVIDED WITH APPROPRIATE WORK ZONE TRAFFIC CONTROLS.
4. SIDEWALK CLOSURES SHALL BE LIMITED TO OCCUR ONLY DURING THE ACTUAL WORK ACTIVITY. DURING CLOSURE, APPROPRIATE PEDESTRIAN DETOURS SHALL BE POSTED. DURING ALL OTHER TIMES, PROVISIONS FOR SAFE PEDESTRIAN ACCESS THROUGH THE WORK AREA, VIA A TEMPORARY WALKWAY SHALL BE PROVIDED.
5. ANY WORK WITHIN THE TRAVELED PORTION OF ROADWAYS SHALL BE RESTRICTED TO THE HOURS OF 9:00 AM TO 3:00 PM, MONDAY THROUGH FRIDAY. WORK ON HOLIDAYS AND WEEKENDS SHALL NOT OCCUR UNLESS AN EXCEPTION IS GRANTED IN WRITING BY HARFORD COUNTY AND MDSHA INSPECTOR.
6. CONSTRUCTION ACTIVITY, LOADING OR UNLOADING OF EQUIPMENT SHALL NOT BLOCK ANY TRAFFIC LANE OTHER THAN THOSE DELINEATED WITHIN THE WORK ZONE.
7. EXCLUSIVE OF EMERGENCY WORK, THE CONTRACTOR SHALL CONTACT OCCUPANTS OF ALL ADJOINING PROPERTIES AND INFORM THEM OF THE SCOPE AND THE TIMING OF CONSTRUCTION. A MINIMUM OF 24 HOURS NOTIFICATION SHALL BE REQUIRED PRIOR TO THE COMMENCEMENT OF ANY ACTIVITY ON THE SITE.
8. ACCESS SHALL BE MAINTAINED TO ALL DRIVEWAYS UNLESS PERMISSION FOR CLOSURE IS GRANTED BY THE PROPERTY OWNER/MANAGER. HOWEVER, ACCESSIBILITY FOR EMERGENCY VEHICLES SHALL BE MAINTAINED AT ALL TIMES
9. PAVEMENT EXCAVATION SHALL BE LIMITED TO A MAXIMUM OF ONE TRAVEL LANE AT ANY TIME UNLESS OTHERWISE SPECIFIED ON THE TTCP.
10. IF ANY TEMPORARY TRAFFIC CONTROL SIGNS ARE TO BE PLACED ALONG A MSHA ROADWAY OR WITHIN THE LIMITS OF AN INCORPORATED AREA, THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE AGENCY OF SIGNAGE TO BE INSTALLED.
11. NO HAZARDOUS MATERIALS SHALL BE STORED WITHIN PUBLIC RIGHT-OF-WAY. NO MATERIALS OR EQUIPMENT SHALL BE STORED ON THE ROADWAY SURFACES OR SIDEWALK DURING NON-WORK HOURS.
12. ALL EXISTING TRAFFIC CONTROL DEVICES (I.E. SIGNS, MARKING, ETC.) THAT MUST BE REMOVED SHALL BE REPLACED IN THEIR PROPER LOCATION PRIOR TO THE COMPLETION OF THE PROJECT. COST FOR THE REPLACEMENT AND/OR REPAIR OF DEVICES DAMAGED AS A RESULT OF THE PROJECT SHALL BE ASSESSED TO THE CONTRACTOR.
13. FOR MERGING, SHIFTING, SHOULDER TAPER, THE MAXIMUM SPACING BETWEEN DEVICES EQUALS THE POSTED SPEED IN FEET.
14. ALL TEMPORARY TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE MOST RECENT EDITION OF THE MDMUTCD. ALL SIGNS, TRAFFIC DRUMS AND CONES SHALL BE FULLY REFLECTORIZED WITH HIGH INTENSITY, REFLECTIVE SHEETING AS PER THE MDMUTCD.
15. PROVISION SHALL BE MADE FOR SAFE MAINTENANCE OF PEDESTRIAN AND BICYCLE TRAFFIC, SUBJECT TO APPROVAL OF THE HARFORD COUNTY AND MDSHA INSPECTOR. AT LEAST ONE 10-FOOT TRAVEL LANE SHALL BE AVAILABLE FOR TRAFFIC AT ALL TIMES.
16. THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR ALL ACCIDENTS AND/OR DAMAGE TO PERSONS AND/OR PROPERTY DAMAGE RESULTING FROM HIS OPERATIONS.
17. ALL TEMPORARY TRAFFIC CONTROL (TTC) DEVICES SHALL BE REMOVED AS SOON AS PRACTICAL WHEN THEY ARE NO LONGER NEEDED. WHEN WORK IS SUSPENDED FOR SHORT PERIODS OF TIME, TTC DEVICES THAT ARE NO LONGER APPROPRIATE SHALL BE REMOVED OR COVERED.
18. AT THE COMPLETION OF WORK ACTIVITIES, CONDITIONS WITHIN THE PUBLIC SPACE SHALL BE FULLY RESTORED TO THOSE THAT EXISTED PRIOR TO THE WORK ACTIVITY.
19. THE HARFORD COUNTY AND MDSHA INSPECTOR HAS THE AUTHORITY TO MODIFY THE TTCP AS DEEMED NECESSARY. THE INSPECTOR HAS THE AUTHORITY TO ORDER THE CONTRACTOR TO STOP WORK AND VACATE THE PUBLIC RIGHT-OF-WAY IF THE TTCP IS NOT COMPLIED WITH.

TRAFFIC CONTROL SEQUENCE		
	DESCRIPTION	DURATION
1.	INSTALL AFTER 9:00 AM AND MAINTAIN MOT TEMPORARY TRAFFIC CONTROL DEVICES PER SHEET MT-A2 DURING WORKING HOURS AND MUST BE REMOVED BY 3:00 PM DAILY.	90 DAYS
2.	REMOVE ALL MOT TEMPORARY TRAFFIC CONTROL DEVICES. RESTORE DISTURBED AREA.	1 DAY
TOTAL ESTIMATED DURATION OF WORK		10-15 WKS

TRAFFIC CONTROL SEQUENCE		
	DESCRIPTION	DURATION
1.	INSTALL AFTER 9:00 AM AND MAINTAIN MOT TEMPORARY TRAFFIC CONTROL DEVICES PER SHEET MT-A3 DURING WORKING HOURS AND REMOVE BY 3:00 PM DAILY.	90 DAYS
2.	REMOVE ALL MOT TEMPORARY TRAFFIC CONTROL DEVICES. RESTORE DISTURBED AREA.	1 DAY
TOTAL ESTIMATED DURATION OF WORK		10-15 WKS

TRAFFIC CONTROL SEQUENCE		
	DESCRIPTION	DURATION
1.	INSTALL AFTER 9:00 AM AND MAINTAIN MOT TEMPORARY TRAFFIC CONTROL DEVICES PER SHEET MT-A4 AND MT- A5 DURING WORKING HOURS AND REMOVE BY 3:00 PM DAILY.	90 DAYS
2.	REMOVE ALL MOT TEMPORARY TRAFFIC CONTROL DEVICES. RESTORE DISTURBED AREA.	1 DAY
TOTAL ESTIMATED DURATION OF WORK		10-15 WKS

EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND		
	MAINTENANCE OF TRAFFIC		
	NOTES		
	Drawn By : _____ LBT Designed By : _____ MCB Reviewed By : _____ GWF	Contract No : _____ DP1602779 Scale : _____ Sheet <u>73</u> Of <u>78</u> Date : <u>2/16/2022</u>	MT-A1

ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE: 1"=100'




NOTE:
WORK LIMITED FROM 9:00 AM TO 3:00 PM.

MAINTENANCE OF TRAFFIC NOTE
UPON COMPLETION OF SCE ENTRANCE, CONTRACTOR SHALL INSTALL W11-10(1)-TRUCK CROSSING (SYMBOL) SIGNS (48"x48") IN BOTH DIRECTIONS OF CHURCH CREEK ROAD 100' PRIOR TO THE ENTRANCE

LEGEND:

-  TEMPORARY WORK ZONE
-  TEMPORARY SIGN
-  TEMPORARY BARREL
-  FLAGGER
-  TRAFFIC FLOW




EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		MAINTENANCE OF TRAFFIC	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	----
Reviewed By :	GWF	Sheet	74 Of 78
		Date :	2/16/2022

HCG BILLING ID No.:
HCG DWG ID No.:
TAX MAP :
ADC MAP :

MT-A2




INSTALL SIGNS ON THE SIDEWALK ALONG NORTHBOUND CHURCH CREEK ROAD AT CRANESBILL COURT.

CONTRACTOR SHALL MAINTAIN PEDESTRIAN ACCESS AT ALL TIMES

NOTE:
WORK LIMITED FROM 9:00 AM TO 3:00 PM.

- LEGEND:**
- TEMPORARY WORK ZONE
 - TEMPORARY SIGN
 - TEMPORARY BARREL
 - FLAGGER
 - TRAFFIC FLOW


NOTE:
SEE ACCESS PLAN SHEETS AP-01 AND AP-02 FOR CONTINUING LIMIT OF DISTURBANCE AND ACCESS ROAD.




EG-SWMENG-000747-2016

<p>Revisions</p>	<h2 style="margin: 0;">HARFORD COUNTY, MARYLAND</h2> <h3 style="margin: 0;">MAINTENANCE OF TRAFFIC</h3>	
<p>Drawn By : _____ LBT</p> <p>Designed By : _____ MCB</p> <p>Reviewed By : _____ GWF</p>	<p>Contract No : _____ DP1602779</p> <p>Scale : _____</p> <p>Sheet <u>75</u> Of <u>78</u></p> <p>Date : <u>2/16/2022</u></p>	<p>HCG BILLING ID No.: _____</p> <p>HCG DWG ID No.: _____</p> <p>ADC MAP : _____</p> <p>TAX MAP : _____</p> <p style="font-size: small;">SCALE: 1"=50'</p>

MT-A3



- LEGEND:**
- TEMPORARY WORK ZONE
 - TEMPORARY SIGN
 - TEMPORARY BARREL
 - TRAFFIC FLOW




EG-SWMENG-000747-2016

Revisions	HARFORD COUNTY, MARYLAND	
	MAINTENANCE OF TRAFFIC	
Drawn By : _____	LBT	Contract No : _____
Designed By : _____	MCB	Scale : _____
Reviewed By : _____	GWF	Sheet <u>76</u> Of <u>78</u>
		Date : <u>2/16/2022</u>


MT-A4

ADC MAP : TAX MAP : HCG BILLING ID No.: HCG DWG ID No.:



MAINTENANCE OF TRAFFIC NOTE
 TRUCKS WILL ONLY BE ALLOWED TO ENTER AND EXIT THE CONSTRUCTION ENTRANCE BETWEEN THE HOURS OF 9 AM TO 3 PM.

- LEGEND:**
- TEMPORARY SIGN
 - ← TRAFFIC FLOW



EG-SWMENG-000747-2016

Revisions		HARFORD COUNTY, MARYLAND	
		MAINTENANCE OF TRAFFIC	
Drawn By :	LBT	Contract No :	DP1602779
Designed By :	MCB	Scale :	----
Reviewed By :	GWF	Sheet	77 Of 78
		Date :	2/16/2022

MT-A5


ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE 1"=30'




DRAINAGE AREA TO
INFILTRATION TRENCH
DA=0.95Ac
IMP.=0.42Ac

DRAINAGE AREA TO POND
DA=5.99 Ac.
IMP.=3.82 Ac.

LEGEND:

- STORM DRAIN SOIL TYPE
- INLET DRAINAGE DIVIDE
- MANHOLE
- SOIL BOUNDARY

FACILITY TYPE	DRAINAGE AREA Ac.	IMPERVIOUS DRAINAGE AREA Ac.
POND	5.99	3.82
INFILTRATION TRENCH	0.95	0.42



EG-SWMENG-000747-2016

<p>Revisions</p>	<h2 style="margin: 0;">HARFORD COUNTY, MARYLAND</h2> <h3 style="margin: 0;">DRAINAGE AREA MAP</h3>
<p>Drawn By : <u>NS</u></p> <p>Designed By : <u>JS</u></p> <p>Reviewed By : <u>MAE</u></p>	<p>Contract No : <u>DP1602779</u></p> <p>Scale : <u>60'</u></p> <p>Sheet <u>78</u> Of <u>78</u></p> <p>Date : <u>02/14/2018</u></p>



ADC MAP :

TAX MAP :

HCG BILLING ID No.:

HCG DWG ID No.:

SCALE 1"=60'