


INDEX OF SHEETS

NO.	DESCRIPTION	SHEET NAME
1	TITLE SHEET	GN-01
2	GENERAL CONSTRUCTION NOTES	GN-02
3	SITE PLAN	SP-01
4	EXISTING CONDITIONS	EX-01
5	EXISTING CONDITIONS	EX-02
6	FOREST CONSERVATION PLAN	FC-01
7	FOREST CONSERVATION PLAN	FC-02
8	FOREST CONSERVATION TABLE	FC-03
9	PROPOSED CONDITIONS	SR-01
10	PROPOSED CONDITIONS	SR-02
11	PROFILE VIEW	PR-01
12	PROFILE VIEW	PR-02
13	PROFILE VIEW	PR-03
14	PROFILE VIEW	PR-04
15	PROFILE VIEW	PR-05
16	PROFILE VIEW	PR-06
17	PROFILE VIEW	PR-07
18	PROFILE VIEW	PR-08
19	GEOMETRIC LAYOUT	GS-01
20	LINE AND CURVE TABLES	GS-02
21	STRUCTURE TABLES	ST-01
22	STREAM CROSS SECTIONS	XS-01
23	STREAM CROSS SECTIONS	XS-02
24	STREAM CROSS SECTION	XS-03
25	SECTION VIEW	SE-01
26	SECTION VIEW	SE-02
27	SECTION VIEW	SE-03
28	SECTION VIEW	SE-04
29	SECTION VIEW	SE-05
30	SECTION VIEW	SE-06
31	SECTION VIEW	SE-07
32	SECTION VIEW	SE-08
33	SECTION VIEW	SE-09
34	SECTION VIEWS	SE-10
35	SECTION VIEWS	SE-11
36	SECTION VIEWS	SE-12
37	STREAM DETAILS	DE-01
38	STREAM DETAILS	DE-02
39	STREAM DETAILS	DE-03
40	STREAM DETAILS	DE-04
41	STREAM DETAILS	DE-05
42	STREAM DETAILS	DE-06
43	SEQUENCE OF CONSTRUCTION	SC-01
44	ESC PLAN	ES-01
45	ESC PLAN	ES-02
46	ESC DETAILS	ED-01
47	ESC DETAILS	ED-02
48	ESC DETAILS	ED-03
49	MAINTENANCE OF TRAFFIC	MT-01
50	LANDSCAPING PLAN	LP-01
51	LANDSCAPING PLAN	LP-02
52	LANDSCAPING DETAILS	LD-01
53	LANDSCAPING DETAILS	LD-02
54	DRAINAGE AREA	DA-01

EDGEWATER VILLAGE PARK STREAM RESTORATION

WATERSHED PROTECTION AND RESTORATION OFFICE
HARFORD COUNTY, MARYLAND
BID NO. : TBD



LOCATION MAP

PROJECT SUMMARY

TOTAL LENGTH OF STREAM RESTORED: 1,332 LINEAR FEET
STREAM USE CLASS: DESIGNATED USE CLASS I
STREAM CLOSURE PERIOD: MARCH 1 THROUGH JUNE 15
LOAD REDUCTIONS:

REACH	TSS REDUCTION	TN REDUCTION	TP REDUCTION	IMPERVIOUS ACRES CREDITS
MAINSTEM(REACH 1,2A,2B)	130.71 TONS/YR	160.64 LBS/YR	21.07 LBS/YR	14.59
RT-1	0.9 TONS/YR	6.4 LBS/YR	1.3 LBS/YR	0.4
LT-1	9.9 TONS/YR	12.6 LBS/YR	2.1 LBS/YR	1.4
LT-2	9.63 TONS/YR	12.13 LBS/YR	2.02 LBS/YR	1.3
REACH 3	2.8 TONS/YR	3.1 LBS/YR	0.6 LBS/YR	0.2

SCALE 1" = 400'
400' 0 400' 800'

TMOL NOTES:

1. SEDIMENT AND NUTRIENT LOAD REDUCTIONS WERE DETERMINED IN ACCORDANCE WITH THE MDE APPROVED EXPERT PANEL DOCUMENT RECOMMENDATIONS OF THE EXPERT PANEL TO DEFINE REMOVAL RATES FOR INDIVIDUAL STREAM RESTORATION PROJECTS (BERG ET AL., 2014) AND SUPPORTING DOCUMENTS.
2. SUPPORTED DOCUMENTS CONSULTED INCLUDE "CONSENSUS RECOMMENDATIONS FOR IMPROVING THE APPLICATION OF THE PREVENTED SEDIMENT PROTOCOL FOR STREAM RESTORATION PROJECTS BUILT FOR POLLUTANT REMOVAL CREDIT" DATED SEPTEMBER 2019, "CONSENSUS RECOMMENDATIONS TO IMPROVE PROTOCOLS 2 AND 3 FOR DEFINING STREAM RESTORATION POLLUTANT REMOVAL CREDITS" DATED OCTOBER 2020, AND "RECOMMENDATIONS FOR CREDITING OUTFALL AND GULLY STABILIZATION PROJECTS IN THE CHESAPEAKE BAY WATERSHED" DATED OCTOBER 2019.
3. TMOL CALCULATIONS SHOWN ABOVE ARE PRELIMINARY AND INCLUDED FOR REFERENCE ONLY. FINAL LOAD REDUCTIONS WILL BE UPDATED AND RECALCULATED AS DESIGN PROGRESSES.

Client: HARFORD COUNTY
DEPARTMENT OF PUBLIC WORKS
WATERSHED PROTECTION AND
RESTORATION OFFICE
212 S. BOND STREET
BEL AIR, MD 21014
410-638-3211

Prepared By :

AECOM
12420 MILESTONE CENTER DRIVE
SUITE 150
GERMANTOWN, MARYLAND 20876
301-820-3000

TIER II IMPACTS
PROJECT FOOTPRINT: 2.73 ACRES
DISTURBED AREA: 2.73 ACRES
IMPACT TO 100 FOOT STREAM BUFFER: 2.47 ACRES
NET FOREST LOSS: TBD

BILLING NO. XXXXXX
EG-SWMENG- XXXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

GENERAL NOTES

1. SPECIFICATIONS: ALL WORK IS TO BE PERFORMED IN ACCORDANCE WITH MARYLAND STATE HIGHWAY ADMINISTRATIONS STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS DATED JULY 2024 AND THE MOST RECENT REVISIONS THEREOF AND ADDITIONS THERETO.
2. UTILITIES: UTILITY LOCATIONS SHOWN ON THE PLANS ARE BASED ON LIMITED INFORMATION AVAILABLE. HOWEVER, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF THIS INFORMATION. THE COST OF REPAIR OR REPLACEMENT OF ANY SUCH FACILITIES DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE BORNE BY HIM. CONTACT "MISS UTILITY" PHONE 1-800-257-7777, 48 HOURS PRIOR TO THE START OF WORK. THERE SHOULD BE NO EXCAVATION UNTIL THE LOCATIONS OF UNDERGROUND UTILITIES HAVE BEEN DETERMINED.
3. STANDARD DETAILS: REFERENCE MADE TO STANDARDS ARE TAKEN FROM THE HARFORD COUNTY ROAD CODE "BOOK OF STANDARD DETAILS" AND FROM "THE MARYLAND STATE HIGHWAY ADMINISTRATION'S BOOK OF STANDARDS-HIGHWAY AND INCIDENTAL STRUCTURES". IT WILL BE THE CONTRACTOR'S RESPONSIBILITY THAT THE STANDARD DRAWINGS IN HIS POSSESSION ARE THE LATEST REVISED STANDARDS UP TO AND INCLUDING THE DATE OF THE ADVERTISEMENT OF THIS CONTRACT.
4. RIGHT-OF-WAY LINES: RIGHT-OF-WAY LINES SHOWN ON THESE PLANS DO NOT INCLUDE EASEMENTS. THEY ARE FOR ASSISTANCE IN INTERPRETING THE PLANS ONLY. THESE LINES DO NOT REPRESENT THE OFFICIAL PROPERTY ACQUISITION LINES. FOR OFFICIAL FEE RIGHT-OF-WAY AND EASEMENT INFORMATION, SEE THE APPROPRIATE RIGHT-OF-WAY PLATS.
5. SOIL CONSERVATION: THE CONTRACTOR SHALL NOT DISTURB THE EXISTING VEGETATION OUTSIDE THE LIMITS OF DISTURBANCE. IF NECESSARY, A TEMPORARY STOCKPILE SHALL BE PROVIDED WITHIN THE LIMITS OF DISTURBANCE. THE STOCKPILE SHALL BE LOCATED SUCH THAT ANY RUNOFF WILL DRAIN TO AN EXISTING SEDIMENT CONTROL DEVICE (I.E., SUPER SILT FENCE). THE STOCKPILE MAY NOT PROTRUDE UPON NOR ALTER DRAINAGE DIVIDES TO THE SEDIMENT CONTROL DEVICE AT ANY TIME. SOIL STABILIZATION WILL CONFORM TO 2011 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL. THE CONTRACTOR WILL OBTAIN APPROVAL OF THE HARFORD COUNTY SOIL CONSERVATION DISTRICT FOR HIS PLANS IN CONTROLLING SEDIMENT EROSION FOR THE BORROW AREA AND DISPOSING OF ANY WASTE EXCAVATION.
6. EXISTING MAILBOXES AND EXISTING SIGNS: ALL EXISTING MAILBOXES, SIGNS AND PAPER BOXES DISTURBED DURING CONSTRUCTION SHALL BE TEMPORARILY RESET IMMEDIATELY AND PERMANENTLY RESET AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE INCIDENTAL TO ALL OTHER ITEMS IN THE CONTRACT.
7. SURVEYS:
HORIZONTAL CONTROL - COORDINATES SHOWN ON THE PLANS ARE BASED ON THE MARYLAND STATE PLANE COORDINATE SYSTEM (NAD83) IN U.S. SURVEY FEET.
VERTICAL CONTROL - ELEVATIONS SHOWN ON THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88).
ONLY THOSE CONTROL POINTS SHOWN ON THESE PLANS ARE TO BE USED FOR THE CONSTRUCTION OF THIS PROJECT.

NOT FOR CONSTRUCTION: 90% DESIGN REVIEW

HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK STREAM RESTORATION	
TITLE SHEET	
Drawn By : CA	Scale : AS SHOWN
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. GN-01 of GN-02	Sheet No. 01 of 54

GENERAL CONSTRUCTION NOTES

PROJECT DESCRIPTION
THE HARFORD COUNTY DEPARTMENT OF PUBLIC WORKS, WATERSHED PROTECTION AND RESTORATION DIVISION OFFICE IS PURSUING THE EDGEWATER VILLAGE STREAM RESTORATION PROJECT. THE PROJECT INCLUDES 1,332 LINEAR FEET OF STREAM RESTORATION AND 245 LINEAR FEET OF SANITARY SEWER REPLACEMENT. THE GOAL OF THE PROJECT IS TO REPLACE AND STABILIZE THE EXISTING EXPOSED SANITARY SEWER LINE AND TO PROVIDE STREAM STABILIZATION AND CHANNEL RESTORATION DESIGNS THAT ARE LOW-MAINTENANCE AND COST-EFFECTIVE WHILE MINIMIZING ADVERSE ENVIRONMENTAL IMPACTS. ADDITIONALLY, THESE IMPROVEMENTS WILL SUPPORT THE COUNTY IN MEETING TOTAL MAXIMUM DAILY LOAD (TMDL) RESTORATION GOALS FOR THE CHESAPEAKE BAY WATERSHED.

EXISTING SITE CONDITIONS
THE SITE IS LOCATED IN A SUBURBAN AREA WITHIN THE UNINCORPORATED COMMUNITY OF EDGEWOOD, MARYLAND. THE AREA SURROUNDING THE PROJECT AREA INCLUDES RESIDENTIAL NEIGHBORHOODS, ATHLETIC FIELDS, OPEN SPACE, AND FORESTED BUFFERS. THE SITE IS LOCATED WITHIN THE LOWER WINTERS RUN (MDE 8 DIGIT WATERSHED NUMBER: 02130702) WATERSHED. AREAS LOCATED OUTSIDE THE LOD WILL NOT BE DISTURBED DURING CONSTRUCTION.

Critical Erosion Areas
EARLY ESTABLISHMENT AND PROPER MAINTENANCE OF PERIMETER CONTROLS WILL PROVIDE SEDIMENTATION CONTROL, STABILIZE AND MAINTAIN CUT AND FILL SLOPES THROUGHOUT PROJECT CONSTRUCTION TO CONTROL EROSION. AREAS THAT MAY HAVE HIGH EROSION POTENTIAL DURING CONSTRUCTION INCLUDE THE STREAMBANKS AND AREAS OF HIGHLY ERODIBLE SOIL. PORTIONS OF THE STREAMBANK WITH SLOPES EXCEEDING 5% LOCATED WITHIN AREAS OF HIGHLY ERODIBLE SOIL (K VALUE GREATER THAN 0.4) WILL BE CONSIDERED CRITICAL AREAS AND WILL BE TREATED WITH EROSION CONTROL MATTING TO ENSURE ADEQUATE STABILIZATION.

Adequate Channel Protection
WATERWAYS DOWNSTREAM OF THE PROJECT SITE WILL BE PROTECTED FROM SEDIMENT DEPOSITION AND INCREASES FROM VOLUME, VELOCITY AND PEAK-FLOW THROUGH USE OF SEDIMENT CONTROL MEASURES DURING CONSTRUCTION, INCLUDING SANDBAG DIKES, COFFERDAMS, PUMPS, AND FILTER BAGS.

Spatial Data
SOURCES FOR ELEVATION DATA INCLUDE THE FOLLOWING:

1) SURVEY PERFORMED BY AECOM IN MAY 2024.

2) GIS TOPOGRAPHY AVAILABLE FROM THE HARFORD COUNTY GIS DATA DOWNLOAD PORTAL.

Proposed Work

A. COMPLETE ALL PROPOSED WORK CAREFULLY TO MINIMIZE DISTURBANCE TO ADJACENT AREAS.

B. RESTORE ANY AREAS DISTURBED DURING CONSTRUCTION TO THEIR ORIGINAL OR PROPOSED CONDITION TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.

C. IF WORK IS NOT AS ANTICIPATED OR INVOLVES DESIGN MODIFICATION CONSIDERATIONS, NOTIFY ENGINEER PRIOR TO PROCEEDING.

General Construction Notes:

A. THE ENGINEER USED NORMAL STANDARD OF CARE IN LOCATING, IDENTIFYING AND SURVEYING EXISTING UTILITIES. NO SPECIALIZED SUBSURFACE UTILITY ENGINEERING WAS CONDUCTED. ALL EXISTING UTILITIES FOUND DURING SURVEY ARE SHOWN ON THE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES WITHIN THE CONSTRUCTION LIMITS AND VERIFYING THE LOCATION AND DEPTHS OF BURIED UTILITIES PRIOR TO CONSTRUCTION. IF A CONFLICT IS DISCOVERED BETWEEN THE PLANS AND THE EXISTING UTILITIES, THE CONTRACTOR IS TO NOTIFY THE ENGINEER TO ADDRESS THE CONFLICT PRIOR TO BEGINNING CONSTRUCTION.

B. CONTRACTOR SHALL PROVIDE TEMPORARY STABILIZATION OF ALL UTILITIES DURING CONSTRUCTION INCLUDING ABOVE GROUND UTILITIES SUCH AS POWER POLES.

C. VERIFY ALL FIELD CONDITIONS PRIOR TO CONSTRUCTION AND/OR DEMOLITION AND REPORT ANY DIFFERENCE IN SITE CONDITIONS FROM THE DRAWINGS TO THE ENGINEER IMMEDIATELY.

D. PROMPTLY INFORM THE ENGINEER OF ANY ERROR OR DISCREPANCY DISCOVERED IN THESE DRAWINGS OR SPECIFICATIONS OR CONFLICT BETWEEN THE DRAWINGS AND THE SPECIFICATIONS.

Demolition Notes:


A. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEARING AND DEMOLITION OF ANY ELEMENTS WHICH ARE IN CONFLICT WITH PROPOSED NEW CONSTRUCTION. THIS INCLUDES BUT IS NOT LIMITED TO FENCES, TREES, DRAINAGE STRUCTURES, POLES, PAVEMENTS, VEGETATION, SIGNS AND OTHER MISCELLANEOUS SITE ELEMENTS.

B. ALL DEMOLITION DEBRIS SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS AND SPECIFICATIONS, LATEST REVISION.

C. CONTRACTOR SHALL STRIP TOPSOIL AND STOCKPILE IT FOR LATER USE.



D. EXISTING UTILITIES SUCH AS WATER, SEWER, GAS, ELECTRICAL, FIBER, CABLE, ETC. MAY BE PRESENT IN THE AREA. THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES SHOULD BE VERIFIED PRIOR TO CONSTRUCTION. ANY AND ALL DAMAGES RESULTING FROM THE FAILURE TO DO SO SHALL BE REPAIRED AT NO EXPENSE TO THE OWNER. CONTACT ANY APPLICABLE LOCAL AND REGIONAL UTILITIES COMPANIES AT LEAST 48 HOURS PRIOR TO COMMENCING CONSTRUCTION.

LEGEND



BILLING NO. XXXXX	Revisions	
GP # XXXXX-XXXX	SIGN AND SEAL	
PROFESSIONAL CERTIFICATION		
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.		

HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK	
STREAM RESTORATION	
GENERAL CONSTRUCTION NOTES	
Drawn By : CA	Scale : NTS
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. GN-02 of GN-02	
Sheet No. 02 of 54	



BILLING NO. XXXXXX
EG-SWMENG- XXXXXX-XXXX #XXXX
<u>PROFESSIONAL CERTIFICATION</u>
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	

CHARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION SITE PLAN

Drawn By :	CA	Scale :	1" = 50'
Designed By :	CA	Date :	JUNE 2025
Reviewed By :	BWA		
Drawing No.	SP-01	Sheet No.	03 of

HARFORD COUNTY
ROUTE 40
EDGEWOOD, MD 21040
PARCEL ID: 0254

SSMH-04
TOP=98.29'
SW 8" INV IN ELEV=80.34'
NE 8" INV OUT
ELEV=80.30'
N:642167.5153
E:1505098.0555

REFER TO EDGEWATER VILLAGE SEWER REPLACEMENT PLANS FOR MANHOLE MODIFICATIONS

DEMOLISH AND REMOVE 20 LF OF STORM DRAIN
60' RCP INV EL=85.69'


TOP=86.59'
MANHOLE LID IS
WELDED SHUT

BROWN JAMES A JR
1701 HARBINGER TRAIL
EDGEWOOD, MD 21040
PARCEL ID: 0961

SSMH-05
TOP=91.69'
SW 8" INV IN ELEV=79.09'
NE 8" INV OUT ELEV=78.89'
SE 8" INV IN ELEV=79.89'
N:642202.6640
E:1505252.0035

SOILS TABLE

SOIL SYMBOL	SOIL NAME	PERCENT SLOPE	KF VALUE	HYDRIC (Y/N)	HIGHLY ERODIBLE SOILS	HSG
BeB	BELTSVILLE SILT LOAM	2%-5%	0.3700	N	NO	C
BeC	BELTSVILLE SILT LOAM	5%-10%	0.4300	N	YES	C
Sa	SAND AND GRAVEL PITS	N/A	N/A	N/A	N/A	N/A



S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL
BILLING NO. XXXXXX	
EG-SWMENG- XXXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	

HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK STREAM RESTORATION EXISTING CONDITIONS	
Drawn By : CA	Scale : 1" = 20'
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. EX-02	Sheet No. 05 of 54

FOREST CONSERVATION PLAN SITE DETAILS

NET TRACT AREA: 2.73 ACRES

TOTAL FOREST CONSERVATION REQUIRED: 2.12 ACRES

TOTAL FOREST CONSERVATION PROVIDED ON-SITE: 1.88 ACRES

TOTAL WETLAND IMPACTS: 906 SF TEMPORARY IMPACTS

TOTAL STREAM IMPACTS: 884 LF / 6,524 SF PERENNIAL STREAM TEMPORARY IMPACTS;

92 LF / 414 SF INTERMITTENT STREAM TEMPORARY IMPACTS

TOTAL SPECIMEN TREE IMPACTS: 0 TREES

FOREST PROTECTION NOTES:

- INDIVIDUAL TREES WITHIN THE LOD THAT ARE NOT MARKED AS REMOVAL SHALL BE PROTECTED WITH TREE PLANKING PLACED CONTINUOUSLY AROUND THOSE TREES.
- CONTRACTOR SHALL USE LOW PRESSURE EQUIPMENT OR HAND GRADING WHEN GRADING WITHIN CRITICAL ROOT ZONES OR ROOT PRUNING OF TREES THAT ARE NOT MARKED AS REMOVAL. ROOT PRUNING SHALL OCCUR AS SOWN ON PLANS AND IN THE CONSTRUCTION SPECIFICATIONS.
- FOREST RETENTION SIGNAGE SHALL BE STAKED ALONG THE EXISTING HIGH VISIBILITY FENCING OR SILT FENCE AS APPROPRIATE ALONG THE LOD. SIGNS SHALL BE SPACED APPROXIMATELY 100 FEET APART WHERE POSSIBLE, WITH A MAXIMUM OF 150 FEET APART. SEE ITEM 3040 IN THE CONSTRUCTION SPECIFICATIONS FOR TYPICAL FOREST RETENTION SIGNAGE DETAIL.
- CONTRACTOR SHALL REFER TO THE FOREST PROTECTION REPORT AND PROJECT SPECIFICATIONS REGARDING ADDITIONAL REQUIRED FOREST/TREE PROTECTION METHODS AND TO BE SUPERVISED BY A LICENSED TREE CARE PROFESSIONAL.

GENERAL NOTES:

- ALL FOREST RETENTION AND CLEARING ARE PRIORITY 1 DUE TO ON-SITE STREAM AND WETLANDS.
- PROJECT SEQUENCE OF CONSTRUCTION IS LOCATED ON SHEET SC-01.
- SITE VICINITY MAP IS LOCATED ON COVER SHEET.
- LANDSCAPE PLANS FOUND ON SHEETS LP-01 THROUGH LP-02. LANDSCAPE DETAILS FOUND ON SHEET LD-01.
- REFER TO REFORESTATION PLANTING REPORT FOR NARRATIVE SUPPLEMENT TO FCP AND LANDSCAPING SHEETS.
- LOD ZONED AS URBAN RESIDENTIAL DISTRICT (R4).

FOREST CONSERVATION ACT QUALIFIED PROFESSIONAL

Joanna Hiebler

JOANNA HIEBLER

6/20/2025

20 0 20 40
SCALE IN FEET 1" = 20'

BILLING NO. XXXXX

EG-SWMENG- XXXXX-XXXX #XXXX

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL

HARFORD COUNTY, MARYLAND

EDgewater VILLAGE PARK
STREAM RESTORATION

FOREST CONSERVATION PLAN

Drawn By : CA Scale : 1" = 20'


Designed By : CA Date : JUNE 2025

Reviewed By : BWA

Drawing No. FC-01 of FC-03 Sheet No. 06 of 54

HARFORD COUNTY
ROUTE 40
EDGEWOOD, MD 21040
PARCEL ID: 0254

MATCHLINE SEE SHEET FC-01



FOREST CONSERVATION ACT QUALIFIED PROFESSIONAL

Joanna Hiebler

JOANNA HIEBLER 6/20/2025

BROWN JAMES A JR
1701 HARBINGER TRAIL
EDGEWOOD, MD 21040
PARCEL ID: 0961

BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL

HARFORD COUNTY, MARYLAND
EDGEWATER VILLAGE PARK
STREAM RESTORATION
FOREST CONSERVATION PLAN


Drawn By : CA
Designed By : CA
Reviewed By : BWA

Scale : 1" = 20'
Date : JUNE 2025

Drawing No. FC-02 of FC-03
Sheet No. 07 of 54


Tree ID	Common Name	DBH (in)	Appraisal	CRZ (ft)	Suitable for Re-use (Y/N)	Specimen Tree	Within LOD (Y/N)	To be Removed
1	American sycamore	23	Good	23	N	N	N	N
2	Tulip poplar	15	Good	15	Y	N	Y	Y
3	Red maple	14	Good	14	Y	N	Y	Y
4	Red maple	12	Good	12	N	N	Y	Y
5	Tulip poplar	16	Good	16	Y	N	Y	Y
6	Red maple	16	Good	16	Y	N	Y	Y
7	Tulip poplar	12	Good	12	N	N	Y	Y
8	Pitch pine	15	Poor	15	N	N	N	N
9	Red maple	14	Good	14	N	N	N	N
10	Tulip poplar	17	Good	17	Y	N	Y	Y
11	Chestnut oak	24	Poor	24	N	N	Y	N
12	Tulip poplar	16.5	Good	16.5	N	N	N	N
13	Red maple	36	Poor	36	N	Y	N	N
14	Red maple	14	Fair	14	Y	N	N	N
15	Tulip poplar	12	Good	12	N	N	Y	N
16	Tulip poplar	13	Good	13	Y	N	Y	Y
17	Tulip poplar	12	Fair	12	Y	N	Y	Y
18	Red maple	13	Good	13	Y	N	Y	N
19	Silver maple	12	Good	12	N	N	Y	N
20	Red maple	15	Good	15	Y	N	Y	Y
21	Tulip poplar	19	Good	19	Y	N	Y	Y
22	Red maple	13	Good	13	Y	N	Y	N
23	Red maple	17	Good	17	Y	N	Y	N
24	Black gum	12	Good	12	N	N	Y	Y
25	Red maple	14	Good	14	Y	N	Y	Y
26	Red maple	18	Good	18	Y	N	Y	Y
27	Black locust	12	Fair	12	Y	N	Y	Y
28	Black locust	17	Fair	17	Y	N	Y	Y
29	Chestnut oak	18	Good	18	Y	N	Y	Y
30	Chestnut oak	24	Poor	24	N	N	Y	Y
31	Scarlet oak	24	Good	24	Y	N	Y	Y
32	Tulip poplar	13	Good	13	Y	N	Y	Y
33	Tulip poplar	15	Good	15	Y	N	Y	Y
34	American beech	14	Good	14	Y	N	Y	Y
35	Tulip poplar	17	Good	17	Y	N	Y	Y
36	Tulip poplar	22	Good	22	Y	N	Y	Y
37	Tulip poplar	15	Good	15	Y	N	Y	Y
38	Chestnut oak	14	Good	14	Y	N	Y	Y
39	Pitch pine	15	Good	15	Y	N	Y	Y
40	Chestnut oak	16	Good	16	Y	N	Y	Y
41	Chestnut oak	15	Good	15	Y	N	Y	Y
42	Scarlet oak	15	Good	15	N	N	Y	N
43	Chestnut oak	22	Good	22	N	N	Y	N
44	Swamp white oak	15	Good	15	N	N	Y	N
45	White oak	25	Good	25	N	N	Y	Y
46	Chestnut oak	20	Good	20	Y	N	Y	N
47	Tulip poplar	12	Good	12	N	N	Y	Y
48	Chestnut oak	16	Good	16	N	N	Y	N
49	Chestnut oak	24	Good	24	Y	N	Y	Y
50	Tulip poplar	14	Good	14	Y	N	Y	Y
51	Chestnut oak	13	Good	13	Y	N	Y	Y
52	Tulip poplar	12	Good	12	N	N	Y	Y
53	White oak	26	Good	26	N	N	Y	N
54	Red maple	16	Fair	16	Y	N	Y	Y
55	Tulip poplar	22	Good	22	Y	N	Y	Y
56	Black gum	28	Fair	28	Y	N	Y	N
57	Black gum	20	Fair	20	Y	N	Y	N
58	Black gum	18	Good	18	Y	N	Y	N
59	Chestnut oak	16	Good	16	Y	N	Y	Y
60	Chestnut oak	17	Good	17	Y	N	Y	Y
61	White oak	17	Poor	17	N	N	N	N
62	Red maple	15	Poor	15	N	N	N	N
63	Chinese elm	12	Good	12	Y	N	Y	N
64	Chinese elm	12	Poor	12	N	N	Y	N
65	Chinese elm	14	Poor	14	N	N	Y	N
66	Chinese elm	12	Poor	12	N	N	Y	N
67	Chestnut oak	22	Fair	22	Y	N	Y	Y
68	Black cherry	16	Fair	16	Y	N	Y	Y
69	Japanese elm	16	Fair	16	Y	N	Y	Y
70	Red maple	14	Fair	14	Y	N	Y	Y
71	Chestnut oak	13	Fair	13	Y	N	Y	Y
72	Chestnut oak	23	Fair	23	Y	N	Y	Y
73	Chestnut oak	12	Good	12	Y	N	Y	Y
74	Chestnut oak	17	Fair	17	Y	N	Y	Y
75	Chestnut oak	16	Good	16	Y	N	Y	N
76	Chestnut oak	18	Good	18	Y	N	N	N
77	White oak	17	Fair	17	Y	N	N	N
78	Red maple	12	Fair	12	Y	N	Y	Y
79	Loblolly pine	17	Fair	17	Y	N	Y	Y
80	Virginia Pine	12	Fair	12	Y	N	Y	N
81	Virginia Pine	13	Fair	13	Y	N	Y	N
82	Red maple	13	Poor	13	N	N	Y	N
83	Tulip poplar	14	Poor	14	N	N	Y	N
84	Black cherry	23	Poor	23	N	N	Y	N
85	Virginia pine	16	Good	16	Y	N	Y	N
86	Black cherry	13	Poor	13	N	N	Y	Y
87	Virginia pine	12	Fair	12	Y	N	N	N
88	Red maple	13	Fair	13	Y	N	Y	N
89	Red maple	16.5	Fair	16.5	Y	N	Y	Y
90	Loblolly pine	16	Fair	16	Y	N	N	N
91	Loblolly pine	12.5	Fair	12.5	Y	N	Y	N
92	Virginia pine	13.5	Fair	13.5	Y	N	Y	Y
93	Loblolly pine	13.5	Fair	13.5	Y	N	N	N
94	Loblolly pine	16	Fair	16	Y	N	Y	N
95	Loblolly pine	18	Fair	18	Y	N	N	N
96	American sycamore	16	Fair	16	Y	N	N	Y
97	American sycamore	18	Fair	18	Y	N	N	Y
98	Red maple	16	Fair	16	Y	N	Y	Y
99	Sweetgum	13.5	Fair	13.5	Y	N	Y	Y
100	Red maple	16	Fair	16	Y	N	Y	Y

Tree ID	Common Name	DBH (in)	Appraisal	CRZ (ft)	Suitable for Re-use (Y/N)	Specimen Tree	Within LOD (Y/N)	To be Removed
101	American sycamore	17.5	Fair	17.5	Y	N	Y	Y
102	Loblolly pine	16	Fair	16	Y	N	Y	Y
103	Virginia pine	17	Fair	17	Y	N	Y	Y
104	Loblolly pine	17	Fair	17	Y	N	Y	Y
105	Loblolly pine	14	Poor	14	N	N	Y	Y
106	Bradford pear	18	Fair	18	Y	N	Y	Y
107	Red maple	14	Good	14	Y	N	Y	N
108	Red maple	14	Fair	14	Y	N	Y	N
109	Red maple	12	Fair	12	Y	N	Y	N
110	Red maple	20	Fair	20	Y	N	Y	N
111	Red maple	26	Fair	26	Y	N	Y	N
112	Bradford pear	15	Poor	15	N	N	Y	N
113	White mulberry	14	Fair	14	Y	N	Y	N
114	Loblolly pine	13	Fair	13	Y	N	Y	N



PLUNGE POOL DIMENSIONS

PLUNGE POOL DIMENSIONS						
	DEPTH	LENGTH	MAX WIDTH	MDE TYPE	RIPRAP CLASS	RIP RAP THICKNESS
PLUNGE POOL 1	2'	24'	20'	1	II	2.66'
PLUNGE POOL 2	2.5'	22.5	32'	2	II	2.66'
PLUNGE POOL 3	2'	24'	20'	1	II	2.66'



BILLING NO. XXXXXX

EG-SWMENG- XXXXX-XXXX #XXXX


PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

HARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION PROPOSED CONDITIONS

Drawn By :	CA	Scale :	1" = 20'
Designed By :	CA	Date :	JUNE 2025
Reviewed By :	BWA		
Drawing No.	SR-01	of	SR-02




PLUNGE POOL DIMENSIONS						
	DEPTH	LENGTH	MAX WIDTH	MDE TYPE	RIPRAP CLASS	RIP RAP THICKNESS
PLUNGE POOL 4	2'	24'	20'	1	II	2.66'

BILLING NO. XXXXXX
EG-SWMENG- XXXXXX-XXXX #XXXX
<u>PROFESSIONAL CERTIFICATION</u>
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	

HARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK
STREAM RESTORATION
PROPOSED CONDITIONS



1 REACH 1 PROFILE STA 0+00-2+00

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1" = 1'

HORIZONTAL




SCALE IN FEET 1" = 10'

VERTICAL



SCALE IN FEET 1" = 1'

S/C PLAN # XXXXX		Revisions	HARFORD COUNTY, MARYLAND	
GP # XXXXX-XXXX		SIGN AND SEAL	EDGEWATER VILLAGE PARK	
BILLING NO. XXXXX			STREAM RESTORATION	
EG-SWMENG- XXXXX-XXXX #XXXX			PROFILE VIEW	
PROFESSIONAL CERTIFICATION			I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	
Drawn By : CA		Scale : AS SHOWN		
Designed By : CA		Date : JUNE 2025		
Reviewed By : BWA				
Drawing No. PR-01 of PR-08		Sheet No. 11 of 54		



1 REACH 1 & 2A PROFILE STA 2+00-5+00

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1" = 1'

HORIZONTAL




SCALE IN FEET 1" = 10'

VERTICAL



SCALE IN FEET 1" = 1'

S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND EDGEMARSH VILLAGE PARK STREAM RESTORATION PROFILE VIEW		
GP # XXXXX-XXXX				
SIGN AND SEAL				
BILLING NO. XXXXX EG-SWMENG- XXXXX-XXXX #XXXX PROFESSIONAL CERTIFICATION I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.		Drawn By : CA	Scale : AS SHOWN	
		Designed By : CA	Date : JUNE 2025	
		Reviewed By : BWA		
		Drawing No. PR-02 of PR-08	Sheet No. 12 of 54	



1 REACH 2A & 2B PROFILE STA 5+00-7+50

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1" = 1'

HORIZONTAL



SCALE IN FEET 1" = 10'

VERTICAL




SCALE IN FEET 1" = 1'

BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL

HARFORD COUNTY, MARYLAND
EDGEMARSH VILLAGE PARK
STREAM RESTORATION
PROFILE VIEW
Drawing No. PR-03 of PR-08 Sheet No. 13 of 54
Scale : AS SHOWN Date : JUNE 2025
HCG DWG ID No. : 14000000000000000000000000000000
BID No. :
14000000000000000000000000000000



1 REACH 2B PROFILE STA 7+50 - 9+20

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1'

HORIZONTAL


A horizontal scale with numerical markings at 0, 10, and 20. Below the scale, a black and white checkerboard pattern is positioned, with the first 10 units of the scale corresponding to the white squares of the pattern.

SCALE IN FEET 1" = 10'

A horizontal scale with numerical markers at 1, 0, 1, and 2. A black and white checkered bar is positioned such that its black segments are aligned with the markers at 1, 0, and 1, while its white segments are aligned with the markers at 2 and the end of the scale.

SCALE IN FEET 1" = 1'

S/C PLAN # XXXXX		Revisions	EDGEWATER VILLAGE PARK STREAM RESTORATION PROFILE VIEW		
GP # XXXXX-XXXX					
BILLING NO. XXXXXX			Drawn By :	CA	Scale : <u>AS SHOWN</u>
EG-SWMENG- XXXXX-XXXX #XXXX			Designed By :	CA	Date : <u>JUNE 2025</u>
<u>PROFESSIONAL CERTIFICATION</u>			Reviewed By :	BWA	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.			Drawing No.	PR-04 of PR-08	Sheet No.
SIGN AND SEAL					14 of 54



1 RT-1 PROFILE STA 500+00 TO 500+31

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1" = 1'

HORIZONTAL



SCALE IN FEET 1" = 10'

VERTICAL



SCALE IN FEET 1" = 1'

BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX

Revisions

GP # XXXXX-XXXX

SIGN AND SEAL

HARFORD COUNTY, MARYLAND


EDGEMARSH VILLAGE PARK
STREAM RESTORATION
PROFILE VIEW

Drawn By : CA Scale : AS SHOWN

Designed By : CA Date : JUNE 2025

Reviewed By : BWA

Drawing No. PR-05 of PR-08 Sheet No. 15 of 54



1 LT-1 PROFILE STA 100+00-101+00

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1" = 1'

HORIZONTAL



SCALE IN FEET 1" = 10'

VERTICAL





SCALE IN FEET 1" = 1'

HARFORD COUNTY, MARYLAND

EDGEMARSH VILLAGE PARK
STREAM RESTORATION
PROFILE VIEW

S/C PLAN # XXXXX	Revisions	SIGN AND SEAL
GP # XXXXX-XXXX		
BILLING NO. XXXXX		
EG-SWMENG- XXXXX-XXXX #XXXX		
PROFESSIONAL CERTIFICATION		
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.		
Drawn By : CA	Scale : AS SHOWN	
Designed By : CA	Date : JUNE 2025	
Reviewed By : BWA		
Drawing No. PR-06	of PR-08	Sheet No. 16 of 54





1 REACH 3 STA 400+00-402+14

SCALE: HORIZONTAL 1" = 10'; VERTICAL 1" = 1'

HORIZONTAL



SCALE IN FEET 1" = 10'

VERTICAL




SCALE IN FEET 1" = 1'

HARFORD COUNTY, MARYLAND

EDGEMARSH VILLAGE PARK
STREAM RESTORATION
PROFILE VIEW

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
BILLING NO. XXXXX	
EG-SWMENG- XXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	
Drawing No. PR-08 of PR-08	



Point	Northing	Easting	Elevation (Ft)	Description
AEC95	641846.3349	1504794.0337	104.03	TRAV AEC RC
AEC96	641780.5190	1504867.6594	102.78	TRAV AEC RC
AEC97	641902.8799	1504898.1706	103.97	TRAV AEC RC
AEC98	641984.1210	1504935.5933	103.63	TRAV AEC RC
AEC99	642113.6808	1505005.0040	98.84	TRAV AEC RC
AEC100	642167.8419	1505115.9660	96.43	TRAV AEC RC
AEC101	642173.3505	1505292.3155	93.54	TRAV AEC RC
AEC102	642429.6745	1505462.2930	89.05	TRAV AEC RC
AEC106	642501.7264	1505326.6980	80.38	TRAV AEC RC
AEC106A	642494.2963	1505387.6249	77.05	TRAV AEC RC
AEC107	642431.6481	1505292.6801	82.33	TRAV AEC RC
AEC108	642341.5568	1505255.9200	83.11	TRAV AEC RC
AEC109	642286.2888	1505198.1170	89.11	TRAV AEC RC
AEC109A	642326.1978	1505087.4054	94.18	TRAV NAIL

HARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION GEOMETRIC LAYOUT

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
	SIGN AND SEAL
BY ME, LAW OF XXXX.	

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS
THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XX

SCALE IN FEET 1" = 40'

BID No.:

HCC DWG ID No. :
SCALE : 1 inch

Line Table: Reach 1, 2A & 2B				
Line #	Length	Direction	Start Point	End Point
L1	20.86	N36° 24' 59.47"E	(1504869.31,641629.39)	(1504881.69,641646.18)
L2	35.68	N16° 37' 57.35"W	(1504883.79,641658.21)	(1504873.58,641692.39)
L3	30.53	N41° 19' 12.71"W	(1504869.44,641700.33)	(1504849.28,641723.26)
L4	38.58	N2° 07' 09.23"E	(1504844.24,641737.40)	(1504845.67,641775.96)
L5	22.83	N20° 21' 00.01"W	(1504843.97,641786.55)	(1504836.03,641807.95)
L6	34.47	N52° 07' 59.53"E	(1504844.57,641837.94)	(1504871.78,641859.10)
L7	33.87	N82° 17' 09.49"E	(1504879.65,641862.40)	(1504913.21,641866.95)
L8	35.40	N36° 51' 03.54"E	(1504932.12,641878.06)	(1504953.36,641906.39)
L9	36.56	N12° 53' 01.15"E	(1504956.22,641912.57)	(1504964.37,641948.21)
L10	24.37	N42° 55' 28.73"E	(1504968.35,641955.72)	(1504984.95,641973.57)
L11	38.64	N23° 48' 15.94"E	(1504987.94,641978.12)	(1505003.54,642013.47)
L12	37.05	N56° 45' 33.36"E	(1505009.55,642020.56)	(1505040.54,642040.87)
L13	61.69	N0° 55' 36.10"W	(1505047.95,642054.85)	(1505046.95,642116.53)
L14	42.92	N24° 21' 13.08"E	(1505048.69,642124.92)	(1505066.39,642164.02)
L15	39.28	N56° 05' 09.34"E	(1505130.24,642256.74)	(1505162.84,642278.66)
L16	29.56	S76° 52' 35.75"E	(1505236.73,642294.77)	(1505265.51,642288.06)

Line Table: RT-1				
Line #	Length	Direction	Start Point	End Point
L17	28.92	N73° 11' 09.53"W	(1504919.49,641648.96)	(1504891.80,641657.33)
L18	7.96	N85° 28' 01.57"W	(1504891.80,641657.33)	(1504883.86,641657.96)

Line Table: LT-1				
Line #	Length	Direction	Start Point	End Point
L19	10.08	N74° 33' 10.71"E	(1504754.66,641815.86)	(1504764.38,641818.54)
L20	19.37	S78° 23' 34.73"E	(1504771.45,641818.61)	(1504790.42,641814.72)
L21	19.37	N49° 58' 37.55"E	(1504799.00,641817.05)	(1504813.83,641829.51)
L22	22.15	N74° 08' 11.52"E	(1504816.66,641831.23)	(1504837.97,641837.29)

Line Table: LT-2				
Line #	Length	Direction	Start Point	End Point
L23	61.97	N86° 32' 28.06"E	(1505002.77,642265.59)	(1505064.63,642269.33)
L24	16.92	S78° 24' 04.95"E	(1505064.63,642269.33)	(1505081.20,642265.93)
L25	22.02	N71° 20' 18.44"E	(1505086.08,642266.23)	(1505106.95,642273.28)
L26	25.48	S73° 06' 16.99"E	(1505112.92,642273.37)	(1505137.30,642265.97)

Line Table: Reach 3				
Line #	Length	Direction	Start Point	End Point
L27	8.07	N65° 27' 57.94"E	(1505227.02,642263.88)	(1505234.36,642267.22)
L28	149.46	N25° 43' 20.91"E	(1505302.95,642334.40)	(1505367.82,642469.05)

Curve Table: Reach 1, 2A & 2B					
Curve #	Radius	Length	Chord Direction	Start Point	End Point
C1	13.67	12.66	N9° 53' 31.06"E	(1504881.69,641646.18)	(1504883.79,641658.21)
C2	23.67	9.01	N27° 31' 58.83"W	(1504873.58,641692.39)	(1504869.44,641700.33)
C3	20.28	15.37	N19° 36' 01.74"W	(1504849.28,641723.26)	(1504844.24,641737.40)
C4	27.53	10.80	N9° 06' 55.39"W	(1504845.67,641775.96)	(1504843.97,641786.55)
C5	26.37	33.36	N15° 53' 29.76"E	(1504836.03,641807.95)	(1504844.57,641837.94)
C6	16.40	8.63	N67° 12' 34.51"E	(1504871.78,641859.10)	(1504879.65,641862.40)
C7	28.40	22.52	N59° 34' 06.51"E	(1504913.21,641866.95)	(1504932.12,641878.06)
C8	16.40	6.86	N24° 52' 02.34"E	(1504953.36,641906.39)	(1504956.22,641912.57)
C9	16.40	8.60	N27° 54' 14.94"E	(1504964.37,641948.21)	(1504968.35,641955.72)
C10	16.40	5.47	N33° 21' 52.33"E	(1504984.95,641973.57)	(1504987.94,641978.12)
C11	16.40	9.43	N40° 16' 54.65"E	(1505003.54,642013.47)	(1505009.55,642020.56)
C12	16.40	16.51	N27° 54' 58.63"E	(1505040.54,642040.87)	(1505047.95,642054.85)
C13	19.58	8.64	N11° 42' 48.49"E	(1505046.95,642116.53)	(1505048.69,642124.92)
C14	317.89	113.17	N34° 33' 09.93"E	(1505066.39,642164.02)	(1505130.24,642256.74)
C15	115.40	77.05	N77° 41' 53.08"E	(1505162.84,642278.66)	(1505236.73,642294.77)

Curve Table: LT-1					
Curve #	Radius	Length	Chord Direction	Start Point	End Point
C16	13.57	7.15	N89° 24' 22.58"E	(1504764.38,641818.54)	(1504771.45,641818.61)
C17	10.14	9.20	N74° 45' 29.12"E	(1504790.42,641814.72)	(1504799.00,641817.05)
C18	9.93	3.33	N58° 39' 13.77"E	(1504813.83,641829.51)	(1504816.66,641831.23)

Curve Table: LT-2					
Curve #	Radius	Length	Chord Direction	Start Point	End Point
C19	9.37	4.95	N86° 28' 06.75"E	(1505081.20,642265.93)	(1505086.08,642266.23)
C20	9.78	6.07	N89° 07' 00.72"E	(1505106.95,642273.28)	(1505112.92,642273.37)

Curve Table: Reach 3					
Curve #	Radius	Length	Chord Direction	Start Point	End Point
<tbl_info cols


No.	Reach 1 Structures (Thalweg Station)	Northing:	Easting:	El.	Arm Grade	Description
1	0+46 ROCK STEP	641669.71	1504880.37	103.19		Step
2	0+61 LOG STEP	641684.44	1504875.95	102.77		Step
3	0+77 LOG STEP	641699.37	1504870.13	101.97		Step
4	0+93 LOG STEP	641711.49	1504859.63	101.35		Step
5	1+09 LOG STEP	641723.48	1504849.12	100.74		Step
6	1+25 LOG STEP	641738.32	1504844.23	100.12		Step
7	1+41 LOG STEP	641754.27	1504844.87	99.51		Step
8	1+57 LOG STEP	641770.27	1504845.46	98.89		Step
9	1+73 LOG STEP	641786.09	1504844.12	98.28		Step
10	1+89 LOG STEP	641801.06	1504838.49	97.66		Step
11	2+05 LOG STEP	641816.59	1504834.40	97.05		Step

No.	Reach 2 Structures (Thalweg Station)	Northing:	Easting:	El.	Arm Grade	Description
24	7+46 LOG STEP	642235.56	1505111.05	88.18		Step
25	7+60 LOG STEP	642246.36	1505120.41	87.51		Step
26	7+74 LOG STEP	642256.39	1505129.89	86.83		Step
27	7+88 LOG STEP	642264.42	1505141.66	86.16		Step
28	8+02 LOG STEP	642272.05	1505153.16	85.49		Step
29	8+16 LOG STEP	642279.85	1505164.71	84.81		Step
30	8+30 LOG STEP	642286.13	1505177.25	84.14		Step
31	8+44 LOG STEP	642290.85	1505190.27	83.47		Step
32	8+58 LOG STEP	642294.19	1505204.07	82.79		Step
33	8+72 LOG STEP	642295.49	1505218.14	82.12		Step
34	8+86 LOG STEP	642295.33	1505231.98	81.45		Step


No.	Reach 2 Structures (Thalweg Station)	Northing:	Easting:	El.	Arm Grade	Description
35	100+29 ROCK STEP	641816.24	1504783.00	101.02		Step
36	100+43 LOG STEP	641815.57	1504796.77	100.07		Step
37	100+57 LOG STEP	641824.29	1504807.51	99.12		Step
38	100+71 LOG STEP	641831.92	1504819.08	98.16		Step
39	300+02 LOG STEP	642268.93	1505066.66	92.00		Step
40	300+09 LOG STEP	642267.50	1505073.59	91.51		Step
41	300+16 LOG STEP	642266.17	1505080.38	91.03		Step
42	300+23 LOG STEP	642266.61	1505087.20	90.54		Step
43	300+30 LOG STEP	642268.84	1505093.79	90.06		Step
44	300+37 LOG STEP	642271.08	1505100.42	89.57		Step
45	300+44 LOG STEP	642273.28	1505106.95	89.09		Step
46	300+51 LOG STEP	642273.07	1505113.92	88.60		Step
47	300+58 LOG STEP	642271.03	1505120.62	88.11		Step
48	400+53 ROCK CROSS VANE	642304.48	1505274.10	78.80	4.0%	Arm Tie
49	401+04 ROCK CROSS VANE	642295.74	1505271.86	78.43		Arm Tip
50	401+56 ROCK CROSS VANE	642293.83	1505273.25	78.43		Center
51	402+21 ROCK CROSS VANE	642292.57	1505274.64	78.43		Arm Tip
52	402+38 ROCK CROSS VANE	642294.44	1505283.90	78.81	4.0%	Arm Tie
53	403+04 ROCK CROSS VANE	642344.48	1505300.03	78.02	4.0%	Arm Tie
54	403+56 ROCK CROSS VANE	642335.19	1505301.31	77.64		Arm Tip
55	404+21 ROCK CROSS VANE	642333.85	1505302.78	77.64		Center
56	404+38 ROCK CROSS VANE	642333.11	1505304.24	77.64		Arm Tip
57	405+12 ROCK CROSS VANE	642338.13	1505312.71	78.03	4.0%	Arm Tie
58	406+21 ROCK CROSS VANE	642391.22	1505322.55	77.22	4.0%	Arm Tie
59	406+38 ROCK CROSS VANE	642381.96	1505324.00	76.85		Arm Tip
60	407+21 ROCK CROSS VANE	642381.05	1505325.48	76.85		Center
61	407+38 ROCK CROSS VANE	642380.16	1505327.05	76.85		Arm Tip
62	408+44 ROCK CROSS VANE	642384.92	1505335.06	77.22	4.0%	Arm Tie
63	409+53 ROCK CROSS VANE	642405.36	1505034.47	90.97	4.0%	Arm Tie
64	410+38 ROCK CROSS VANE	642036.83	1505030.79	90.60		Arm Tip
65	411+21 ROCK CROSS VANE	642035.13	1505031.78	90.60		Center
66	412+38 ROCK CROSS VANE	642033.82	1505032.81	90.60		Arm Tip
67	413+56 ROCK CROSS VANE	642035.86	1505042.32	90.99	4.0%	Arm Tie
68	414+04 ROCK CROSS VANE	642140.63	1505049.24	89.84	4.0%	Arm Tie
69	415+21 ROCK CROSS VANE	642131.21	1505049.74	89.46		Arm Tip
70	416+38 ROCK CROSS VANE	642130.53	1505051.23	89.46		Center
71	417+56 ROCK CROSS VANE	642129.88	1505052.51	89.46		Arm Tip
72	418+04 ROCK CROSS VANE	642135.61	1505060.11	89.85	4.0%	Arm Tie
73	419+21 ROCK CROSS VANE	642181.43	1505067.97	89.39	4.0%	Arm Tie
74	420+38 ROCK CROSS VANE	642171.99	1505067.98	89.02		Arm Tip
75	421+56 ROCK CROSS VANE	642171.15	1505069.72	89.02		Center
76	422+04 ROCK CROSS VANE	642170.29	1505071.66	89.02		Arm Tip
77	423+21 ROCK CROSS VANE	642176.21	1505078.96	89.39	4.0%	Arm Tie
78	424+38 ROCK CROSS VANE	642200.41	1505091.87	89.04	4.0%	Arm Tie
79	425+56 ROCK CROSS VANE	642211.23	1505089.82	88.66		Arm Tip
80	426+04 ROCK CROSS VANE	642209.83	1505091.86	88.66		Center
81	427+21 ROCK CROSS VANE	642208.93	1505093.16	88.66		Arm Tip
82	428+38 ROCK CROSS VANE	642213.64	1505101.92	89.06	4.0%	Arm Tie

POINT GUIDE FOR CONTROL POINTS

ROCK AND LOG CROSS VANE





ROCK AND LOG STEP



NOTE: LOOKING DOWNSTREAM GRADE CONTROL VANE STRUCTURE IDS INCREASE FROM LEFT BANK SIDE TO RIGHT BANK SIDE

No.	Reach 3 Structures (Thalweg Station)	Northing:	Easting:	El.	Arm Grade	Description
48	400+53 ROCK CROSS VANE	642304.48	1505274.10	78.80	4.0%	Arm Tie
49	401+04 ROCK CROSS VANE	642295.74	1505271.86	78.43		Arm Tip
50	401+56 ROCK CROSS VANE	642293.83	1505273.25	78.43		Center
51	402+21 ROCK CROSS VANE	642292.57	1505274.64	78.43		Arm Tip
52	402+38 ROCK CROSS VANE	642294.44	1505283.90	78.81	4.0%	Arm Tie
53	403+04 ROCK CROSS VANE	642344.48	1505300.03	78.02	4.0%	Arm Tie
54	403+56 ROCK CROSS VANE	642335.19	1505301.31	77.64		Arm Tip
55	404+21 ROCK CROSS VANE	642333.85	1505302.78	77.64		Center
56	404+38 ROCK CROSS VANE	642333.11	1505304.24	77.64		Arm Tip
57	405+12 ROCK CROSS VANE	642338.13	1505312.71	78.03	4.0%	Arm Tie
58	406+21 ROCK CROSS VANE	642391.22	1505322.55	77.22		



31D NO.:



HCG DWG ID No. :
SCALE : 1 inch

BILLING NO. XXXXXX
EG-SWMENG- XXXXX-XXX #XXXX
<u>PROFESSIONAL CERTIFICATION</u>
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

HARFORD COUNTY, MARYLAND

EDGEGATE VILLAGE PARK STREAM RESTORATION STREAM CROSS SECTIONS

S/C PLAN # XXXXX		Revisions	EDGEMERE VILLAGE PARK STREAM RESTORATION STREAM CROSS SECTIONS		
GP # XXXXX-XXXX			Drawn By :	CA	Scale : <u>AS NOTED</u>
SIGN AND SEAL			Designed By :	CA	Date : <u>JUNE 2025</u>
			Reviewed By :	BWA	
			Drawing No.	XS-01 of XS-03	Sheet No.





31D NO.:

HARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION STREAM CROSS SECTIONS

S/C PLAN # XXXXX		Revisions	EDGEGATER VILLAGE PARK STREAM RESTORATION STREAM CROSS SECTIONS
GP # XXXXX-XXXX			
SIGN AND SEAL			
Drawn By :	CA	Scale :	AS NOTED
Designed By :	CA	Date :	JUNE 2025
Reviewed By :	BWA		
Drawing No.	XS-02	of	XS-03
		Sheet No.	23 of 54

BILLING NO. XXXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
<u>PROFESSIONAL CERTIFICATION</u>
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.



310 NO.:



SCALE : 1 inch

HARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION STREAM CROSS SECTIONS

S/C PLAN # XXXXX	Revisions	EDGEMARSH VILLAGE PARK STREAM RESTORATION STREAM CROSS SECTIONS		
GP # XXXXX-XXXX		Drawn By : CA	Scale : AS NOTED	
SIGN AND SEAL		Designed By : CA	Date : JUNE 2025	
		Reviewed By : BWA		
		Drawing No. XS-03 of XS-03	Sheet No.	24 of 54

BILLING NO. XXXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
<u>PROFESSIONAL CERTIFICATION</u>
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.



1 REACH 1 SECTION VIEWS

SCALE: 1" = 10'
10 0 10 20

SCALE IN FEET 1" = 10'

BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.



HARFORD COUNTY, MARYLAND

EDGEMARSH VILLAGE PARK
STREAM RESTORATION
SECTION VIEW

Scale : AS SHOWN
Date : JUNE 2025

BID No. : HCG DWG ID No. : 1

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	
Drawn By : CA	
Designed By : CA	
Reviewed By : BWA	
Drawing No. SE-01 of SE-12	Sheet No. 25 of 54



1 REACH 1 AND REACH 2A SECTION VIEWS



SCALE: 1" = 10'



SCALE IN FEET 1" = 10'

S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND			
GP # XXXXX-XXXX					
EDGEWATER VILLAGE PARK					
STREAM RESTORATION			SECTION VIEW		
Drawn By : CA	AS SHOWN	Scale : AS SHOWN	Date : JUNE 2025		
Designed By : CA					
Reviewed By : BWA					
Drawing No. SE-03	of SE-12	Sheet No.	27 of 54		

BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.



1 REACH 2A SECTION VIEWS

SCALE: 1" = 10'
10 0 10 20
SCALE IN FEET 1" = 10'

HARFORD COUNTY, MARYLAND
EDGEMARSH VILLAGE PARK
STREAM RESTORATION
SECTION VIEW

S/C PLAN # XXXXX **Revisions**
GP # XXXXX-XXXX


BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX



PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

SIGN AND SEAL

Drawn By : CA **Scale :** AS SHOWN
Designed By : CA **Date :** JUNE 2025
Reviewed By : BWA

Drawing No. SE-04 **of** SE-12 **Sheet No.** 28 of 54








1 REACH 2B SECTION VIEWS

SCALE: 1" = 10'



SCALE IN FEET 1" = 10'

S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND EDgewater VILLAGE PARK STREAM RESTORATION SECTION VIEW	
GP # XXXXX-XXXX			
SIGN AND SEAL			
BILLING NO. XXXXX		Drawn By :	CA
EG-SWMENG- XXXXX-XXXX #XXXX		Designed By :	CA
PROFESSIONAL CERTIFICATION		Reviewed By :	BWA
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.		Drawing No.	SE-06 of SE-12
		Sheet No.	30 of 54






1 REACH 2B SECTION VIEWS

SCALE: 1" = 10'
10 0 10 20
SCALE IN FEET 1" = 10'

S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND EDGEMERE VILLAGE PARK STREAM RESTORATION SECTION VIEW	
GP # XXXXX-XXXX			
SIGN AND SEAL			
BILLING NO. XXXXX EG-SWMENG- XXXXX-XXXX #XXXX PROFESSIONAL CERTIFICATION <small>I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.</small>		Drawn By : CA	Scale : AS SHOWN
		Designed By : CA	Date : JUNE 2025
		Reviewed By : BWA	
		Drawing No. SE-07 of SE-12	Sheet No. 31 of 54

BID No. : HCG DWG ID No. : Scale : 1' from



1 RT-1 SECTION VIEWS

SCALE: 1" = 10'
10 0 10 20

SCALE IN FEET 1" = 10'



BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL

HARFORD COUNTY, MARYLAND

EDGEMARSH VILLAGE PARK
STREAM RESTORATION
SECTION VIEW

Drawn By : CA
Designed By : CA
Reviewed By : BWA
Drawing No. SE-08 of SE-12
Sheet No. 32 of 54





1 LT-1 SECTION VIEWS

SCALE: 1" = 10'
10 0 10 20

SCALE IN FEET 1" = 10'

S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND EDGEWATER VILLAGE PARK STREAM RESTORATION SECTION VIEW	
GP # XXXXX-XXXX			
SIGN AND SEAL			
		BILLING NO. XXXXX	
		EG-SWMENG- XXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION			
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.			
Drawn By : CA	Scale : AS SHOWN		
Designed By : CA	Date : JUNE 2025		
Reviewed By : BWA			
Drawing No. SE-09 of SE-03		Sheet No.	




1 LT-2 SECTION VIEWS

SCALE: 1" = 10'






SCALE IN FEET 1" = 10'

S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND			
GP # XXXXX-XXXX	EDGEWATER VILLAGE PARK				
STREAM RESTORATION					
SECTION VIEWS		Drawn By :	CA		
BILLING NO. XXXXXX		Designed By :	CA		
EG-SWMENG- XXXXXX-XXXX #XXXX		Reviewed By :	BWA		
PROFESSIONAL CERTIFICATION		Drawing No.	SE-10 of SE-12		
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.					
SIGN AND SEAL		Sheet No.	34 of 54		




SCALE IN FEET 1" =





SCALE: 1" = 10'

SCALE IN FEET 1" = 10'

S/C PLAN # XXXXX		Revisions	EDGEGATE VILLAGE PARK STREAM RESTORATION SECTION VIEW		
GP # XXXXX-XXXX					
BILLING NO. XXXXXX					
EG-SWMENG- XXXXX-XXXX #XXXX					
SIGN AND SEAL					
			Drawn By : CA	Scale : AS SHOWN	
			Designed By : CA	Date : JUNE 2025	
			Reviewed By : BWA		
			Drawing No. SE-11 of SE-12	Sheet No.	35 of 54
<p>I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.</p>					



SCALE IN FEET 1" = 20'



1 REACH 3 SECTION VIEWS

SCALE: 1" = 10'






SCALE IN FEET 1" = 10'


S/C PLAN # XXXXX	Revisions	HARFORD COUNTY, MARYLAND EDGEMERE VILLAGE PARK STREAM RESTORATION SECTION VIEW		
GP # XXXXX-XXXX				
SIGN AND SEAL			Drawn By :	CA
			Designed By :	CA
			Reviewed By :	BWA
			Drawing No.	SE-12 of SE-12

BILLING NO. XXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

SCALE : 1" = 10' HCG DWG ID No. : BID No. : 36 of 54




HARFORD COUNTY, MARYLAND	
EDGEMARSH VILLAGE PARK	
STREAM RESTORATION	
STREAM RESTORATION DETAILS	
S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	
BILLING NO. XXXXX	
EG-SWMENG- XXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	
Drawn By : CA	Scale : AS NOTED
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. DE-01 of DE-06	
Sheet No. 37 of 54	




1 LOG CROSS VANE

DE-02 NOT TO SCALE




2 ARMoured UTILITY PROTECTION - WITH PIPE ENCASEMENT

DE-02 NOT TO SCALE



S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	
BILLING NO. XXXXXX	
EG-SWMENG- XXXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE NO. XXXXXX, EXPIRATION DATE: XX/XX/XXXX.	
Drawn By : CA	Scale : AS NOTED
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. DE-02 of DE-06	Sheet No. 38 of 54




HARFORD COUNTY, MARYLAND

EDGEMARSH VILLAGE PARK

STREAM RESTORATION

STREAM RESTORATION DETAILS

S/C PLAN # XXXXX	Revisions	
GP # XXXXX-XXXX	SIGN AND SEAL	
BILLING NO. XXXXX		
EG-SWMENG- XXXXX-XXXX #XXXX		
PROFESSIONAL CERTIFICATION		
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.		
Drawn By : CA	Scale : AS NOTED	
Designed By : CA	Date : JUNE 2025	
Reviewed By : BWA		
Drawing No. DE-03 of DE-06		
Sheet No. 39 of 54		



1
DE-04

CONSTRUCTED RIFFLE

NOT TO SCALE

STREAM SUBSTRATE SPECIFICATIONS					
REACH	D50 (IN.)	% CLASS 0 RIPRAP	% CLASS 1 RIPRAP	% CLASS 2 RIPRAP	PLACEMENT DEPTH (FT)
MAINSTEM (REACH 1, 2A, 2B)	11.7	10%	50%	40%	2.0
REACH 3	11.7	10%	50%	40%	2.0
TRIBUTARIES (RT1, LT1, LT2)	8.5	25%	75%	0%	2.0


STREAM SUBSTRATE NOTES

STREAM SUBSTRATE UTILIZED IN THE BED OF THE STREAM WITHIN THE RIFFLE/RUN/GLIDE TRANSITIONS TO PROVIDE A STABLE SUBSTRATE OR FILL AREA. REACHES CLASSIFIED AS STEP-POOLS WILL RECEIVE THE STREAM SUBSTRATE BED IN THE RIFFLE/RUN/POOL/GLIDE TRANSITIONS TO PROVIDE A STABLE SUBSTRATE OR FILL AREA.


THE STREAM SUBSTRATE MUST MEET THE MATERIAL SPECIFICATIONS PROVIDED IN THE TABLE.

NOTES:

1. STREAM SUBSTRATE FOR EACH STREAM REACH SHALL CONTAIN THE PERCENTAGE BY VOLUME OF THE MATERIALS SPECIFIED IN THE TABLES.
2. STREAM SUBSTRATE WILL BE NATURAL IN COLOR (WHITE, BROWN, YELLOW, TAN OR GRAY).
3. STREAM SUBSTRATE SHALL BE FREE OF IMPURITIES AND CONTAMINANTS.
4. STREAM SUBSTRATE SHALL BE NATURAL AND FREE OF SLAG.
5. SIZING IS BASED ON THE INTERMEDIATE B-AXIS OF THE ROCK.
6. FOR MIN. THICKNESS DEPTHS GREATER THAN 1.5 FEET THE BED SHOULD BE PLACED IN LIFTS NO GREATER THAN 12 INCHES. THE CONTRACTOR SHALL INSPECT THE INSTALLATION OF STREAM SUBSTRATE TO ENSURE THE PLACEMENT IS INSTALLED AS HOMOGENEOUS AS POSSIBLE AND VISUALLY FREE OF LARGE VOIDS.
7. ADDITIONAL AVAILABLE ON SITE SALVAGEABLE STREAM BED MATERIAL SHOULD BE BLENDED INTO THE PROPOSED STREAM SUBSTRATE TO FILL Voids.
8. REFER TO THE GRADING PLAN AND PROFILE FOR THE LIMITS OF PLACEMENT OF THE STREAM SUBSTRATE.






SECTION A-A



SECTION B-B

HARFORD COUNTY, MARYLAND			
EDGEMARSH VILLAGE PARK			
STREAM RESTORATION			
STREAM RESTORATION DETAILS			
S/C PLAN # XXXXX	Revisions		
GP # XXXXX-XXXX			
SIGN AND SEAL			
		Drawn By : CA	Scale : AS NOTED
		Designed By : CA	Date : JUNE 2025
		Reviewed By : BWA	
Drawing No. DE-05 of DE-06			
Sheet No. 41 of 54			

BILLING NO. XXXXXX
EG-SWMENG- XXXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXXX, EXPIRATION DATE: XX/XX/XXXX.



HARFORD COUNTY, MARYLAND

**EDGEWATER VILLAGE PARK
STREAM RESTORATION
STREAM RESTORATION DETAILS**

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL
BILLING NO. XXXXX	
EG-SWMENG- XXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	
Drawn By : CA	Scale : AS NOTED
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. DE-06 of DE-06	
Sheet No. 42 of 54	

SEQUENCE OF CONSTRUCTION

PROJECT INITIATION

- THE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS FROM THE COUNTY AND CONDUCT REQUIRED PRE-CONSTRUCTION MEETINGS AS OUTLINED IN THE CONSTRUCTION SPECIFICATIONS PRIOR TO COMMENCING CONSTRUCTION.
- THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER A MINIMUM OF ONE (1) WEEK PRIOR TO COMMENCING ANY LAND DISTURBING ACTIVITIES FOR VERIFICATION THEY ARE IN ACCORDANCE WITH THE APPROVED PERMITS.
- CONTRACTOR TO FIELD MARK LIMIT OF DISTURBANCE AND TREE PROTECTION FENCING PRIOR TO ANY CLEARING, GRADING, SETTING UP OF STAGING AREA, MARKING STOCKPILE, OR ANY SEDIMENT CONTROL MEASURE INSTALLATION. ONCE ALL TREE PROTECTION DEVICES HAVE BEEN INSTALLED, THE APPLICANT SHALL CONTACT THE COUNTY AND SCHEDULE AN INSPECTION OF THE FOREST PROTECTION DEVICES. A STAFF MEMBER OF THE COUNTY SHALL INSPECT AND APPROVE THE INSTALLATION OF ALL PROTECTION DEVICES BEFORE ANY GRADING ACTIVITIES SHALL BE PERMITTED.
- PLACE CONSTRUCTION CLOSURE AND MAINTENANCE OF TRAFFIC SIGNS AS INDICATED ON THE PLANS TO PREVENT SITE ACCESS DURING ACTIVE CONSTRUCTION.
- THE CONTRACTOR SHALL INSTALL THE EROSION AND SEDIMENT CONTROL MEASURES AND NOTIFY THE PROJECT ENGINEER OF THE COMPLETED INSTALLATION. LIMITED CONSTRUCTION ACCESS ROUTES ARE SPECIFIED ON THE CONSTRUCTION DRAWINGS. ALTERNATIVES OR DEVIATIONS SHALL BE APPROVED BY THE PROJECT ENGINEER AND OWNER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. CONTRACTOR PROPOSED ALTERNATIVES WITH DELINEATION OF ENTRANCE LOCATIONS AND ACCESS PATHS SHALL BE INCLUDED IN THE PROPOSED WORKFLOW PLAN. DEVIATIONS FROM THE PROVIDED ACCESS ROUTES WILL REQUIRE WRITTEN AGREEMENT WITH THE PROPERTY OWNER.
- THE PROJECT ENGINEER SHALL PROVIDE THE NPDES INSPECTOR 48-HOUR NOTIFICATION TO SCHEDULE AN ONSITE PRE-CONSTRUCTION MEETING TO INSPECT THE INSTALLATION OF EROSION AND SEDIMENT MEASURES, PRIOR TO LAND DISTURBANCE.

BEGIN PHASE 1

- BEGIN CLEARING AND GRUBBING WITHIN THE LOD NECESSARY TO BEGIN CONSTRUCTION OF THE PROJECT AREA FOR TEMPORARY ACCESS ROADS AND STABILIZED CONSTRUCTION ENTRANCES AND STOCKPILE LOCATIONS. ALL TREES THAT MEET THE SPECIFICATIONS FOR IN-STREAM STRUCTURE SALVAGED LOGS SHALL BE STORED OFF THE GROUND TO BE USED FOR FUTURE STREAM RESTORATION STRUCTURES. ALL RIP RAP THAT MEETS SPECIFICATIONS FOR IN STREAM USE SHALL BE STORED ON SITE FOR REUSE.
- DUE TO THE ENVIRONMENTALLY SENSITIVE NATURE OF THE SITE AND EXISTING UTILITIES WITHIN THE LOD ALL TEMPORARY ACCESS ROADS SHALL UTILIZE GROUND PROTECTION MEASURES FOR THE ENTIRE LENGTH OF ROAD. MINIMUM GROUND PROTECTION MEASURES REQUIRED FOR LOW SLOPED AREAS INCLUDE LAMINATED MATS, ALSO KNOWN AS TRUCK MATS, ROAD MATS, ACCESS MATS, SWAMP MATS, LOGGING MATS, AND ROADWAY MATS. THE CONTRACTOR MAY COVER MATS WITH A THIN LAYER OF MULCH TO PROTECT MATS AND REDUCE THE RISK OF DAMAGE. IN AREAS OF STEEP SLOPES THAT EXCEED 15% SLOPE ALONG THE PROPOSED TEMPORARY ACCESS ROAD THE GROUND PROTECTION SHOULD INCLUDE INSTALLATION OF CRUSHED AGGREGATE WITH A GEOTEXTILE UNDERLAYER.
- CONSTRUCT NEW SANITARY SEWER UPGRADES PER EDGEWATER VILLAGE SANITARY SEWER REPLACEMENT PLANS.
- CONTRACTOR SHALL SUPPLY AND MAINTAIN AN ONSITE CONCRETE WASHOUT STRUCTURE WHICH SHALL BE ON SITE AND AVAILABLE DURING ALL CONCRETE RELATED

WORK ACTIVITIES

- PROPERLY ENCASE THE SEWER IN CONCRETE PER THE UTILITY PROTECTION DETAIL.
- TEMPORARILY STABILIZE AREA IMPACTED BY SEWER REPLACEMENT.
- BEGIN PHASE 2**
- PHASE 2 WORK CAN BEGIN IN CONJUNCTION WITH PHASE 1
- HARVEST AND STOCKPILE SUITABLE FILL MATERIAL AS NEEDED FROM STATION 6+50 - 8+00. TEMPORARILY STABILIZE AREA. ANY TEMPORARY SITE SHALL BE STABILIZED AT A MAXIMUM 3H:1V SLOPE.
- THE CONTRACTOR SHALL CONSTRUCT THE STREAM IN MAXIMUM 150-FOOT DAILY WORK ZONES, THAT CAN BE COMPLETED IN ONE DAY, TO MINIMIZE THE POTENTIAL OF UNNECESSARY OPEN AND UNSTABLE GROUND AT ANY POINT DURING CONSTRUCTION.
- BASED ON A 3-DAY DRY WEATHER FORECAST, PLACE TEMPORARY SANDBAG DIVERSION AT THE UPSTREAM AND DOWNSTREAM ENDS OF THE WORK AREA, AS INDICATED ON THE PLANS. WHERE INDICATED, STREAM FLOW SHOULD BE PUMPED AROUND THE WORK AREA AND THE PUMP SHOULD BE DISCHARGED ONTO A STABLE VELOCITY DISSIPATOR MADE OF RIPRAP OR SANDBAGS.
- INSTALL DEWATERING PUMP AROUND PRACTICE FOR THE DAILY WORK ZONE AS SHOWN IN THE EROSION & SEDIMENT CONTROL PLANS.
- WATER FROM THE WORK AREA SHOULD BE PUMPED TO A SEDIMENT FILTERING DEVICE, SUCH AS A DEWATERING BASIN, FILTER BAG, OR OTHER APPROVED SOURCE. THE MEASURE SHOULD BE LOCATED SUCH THAT THE WATER DRAINS INTO THE EXISTING CHANNEL. APPROXIMATE LOCATIONS FOR DEWATERING MEASURES ARE INDICATED ON THE PLANS AND THE CONTRACTOR IS RESPONSIBLE FOR ADJUSTING THE LOCATION AS NEEDED TO ENSURE THE WORK AREA IS MAINTAINED IN DRY CONDITION.
- THE CONTRACTOR STAKEOUT SHALL INCLUDE AT MINIMUM PROPOSED CENTERLINE, POINT OF CURVATURE (PC), POINT OF TANGENCY (PT), IN-STREAM STRUCTURE LOCATIONS, AND LOCATIONS OF INVERTS FOR RIFFLE, RUN, POOL, AND GLIDE FEATURES AS APPROPRIATE.
- THE CONTRACTOR SHALL BEGIN ALL INSTREAM STREAM RESTORATION WORK STARTING UPSTREAM AND PROCEED DOWNSTREAM, UNLESS OTHERWISE SPECIFIED OR APPROVED BY THE PROJECT ENGINEER.
- COMMENCE ROUGH CHANNEL GRADING UNTIL EITHER THE STATION OF A PROPOSED IN-STREAM STRUCTURE (AS NOTED ON THE STRUCTURE TABLES IN THE PLANS) OR THE LIMITS OF THE DAILY WORK ZONE ARE REACHED. PROCEED WITH INSTALLATION OF THE IN-STREAM STRUCTURE PER THE STRUCTURE SPECIFICATIONS AND AS SHOWN IN THE PLAN DETAILS.
- FINALIZE THE FLOODPLAIN GRADING WITHIN THE MAXIMUM 150-FOOT DAILY WORK ZONES. AT NO TIME MAY THE STREAM OR FLOODPLAIN CONSTRUCTION OR STABILIZATION BE MORE THAN 2 DAILY WORK ZONES BEHIND SYNC.
- FINALIZE GRADING, EXCAVATE TRENCH, AND PROPERLY INSTALL COIR MATTING ON STREAM BANK TOE OF SLOPE. ADD SPECIFIED STREAM SUBSTRATE MIX FOR CHANNEL BOTTOM TO SPECIFIED DEPTH FOR ALL ROUGH GRADED AREAS TO BRING THE CHANNEL TO FINAL GRADE.
- ONCE FINAL GRADING HAS BEEN ACHIEVED, APPLY TEMPORARY SEEDING, PERMANENT SEEDING, AND MULCH PRIOR TO FINALIZING INSTALLATION OF COIR MATTING BY SECURING WITH STAKES AND KEYING IN FABRIC PER MANUFACTURER RECOMMENDATIONS AND AS SHOWN IN THE PLANS.
- CONTINUE STREAM GRADING AND STRUCTURE INSTALLATION UNTIL ALL GRADING AND IN-STREAM STRUCTURES ARE INSTALLED. IF BEDROCK CONDITIONS ARE ENCOUNTERED WITHIN THE WORK AREA DURING CONSTRUCTION, CONSULT THE OWNER AND PROJECT ENGINEER FOR INVERT ELEVATION ADJUSTMENTS.
- STREAM GRADING AND STRUCTURE CONSTRUCTION SHALL PROCEED AS FOLLOWS:

- MAINSTEM STA 0+00 - 0+32
- RT-1 STA 500+00-500+31
- MAINSTEM STA 0+32-2+31
- INSTALL ARMORED UTILITY PROTECTION WITH PIPE ENCASEMENT FROM STATION 2+31-2+50
- LT-1 HEADWALL - INSTALL FORMWORK, REBAR, AND POUR CONCRETE FOR PROPOSED HEADWALL AS SHOWN ON THE PLANS
- LT-1 STA 100+00 - 100+91
- MAINSTEM STATION 2+55 - 5+84
- INSTALL ARMORED UTILITY PROTECTION WITHOUT PIPE ENCASEMENT FROM STATION 5+84-5+98
- MAINSTEM STATION 5+98- 7+46
- DEMOLISH AND REMOVE 20 LINEAR FEET OF STORM DRAIN AT APPROXIMATELY STA 6+00.
- CAP UPSTREAM AND DOWNSTREAM END OF REMAINING STORM DRAIN.
- LT-2 STA 300+00- 300+75.
- MAINSTEM STA 7+46-9+20
- CONSTRUCT PLUNGE POOL 4
- REACH 3 STATION 400+30- 402+13.87

PROJECT CLOSEOUT

- AS THE WORK FOR EACH REACH COMPLETED, E&SC MEASURES CAN BE REMOVED WITH APPROVAL FROM PROJECT OWNER, ENGINEER, AND THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- ONCE CONSTRUCTION OF PROJECT AREA HAS BEEN COMPLETED, THE CONTRACTOR SHALL PROCEED WITH ARRANGEMENT OF COMPOSING APPROVED RECORD DRAWINGS. CONTRACTOR SHALL FIELD SURVEY ALL INSTALLED WORK. FORWARD THE ELECTRONIC SURVEY TO THE PROJECT ENGINEER FOR VERIFICATION THAT THE PROJECT HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLAN. ELECTRONIC COPY OF THE SURVEY MUST BE ACCOMPANIED BY A HARD COPY OF RECORD DRAWINGS SIGNED AND SEALED BY A MARYLAND REGISTERED LAND SURVEYOR.
- ONCE CONSTRUCTION OF ALL PROJECT AREAS AT THE PROJECT SITE HAVE BEEN COMPLETED, MAINTENANCE OF TRAFFIC DEVICES SHALL BE REMOVED.
- CONTRACTOR SHALL ARRANGE FOR AND OBTAIN ANY REQUIRED FINAL SITE INSPECTIONS AND CERTIFICATIONS FOR PROJECT CLOSEOUT.

BID NO. :

HCG DWG ID No. :


HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK	
STREAM RESTORATION	
SEQUENCE OF CONSTRUCTION	
Drawn By : CA	Scale : AS NOTED
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. SC-01	of SC-01
Sheet No.	


S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	
BILLING NO. XXXXX	
EG-SWMENG- XXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	

SCALE : 1' from

HCG DWG ID No. :

43 of 54






















BILLING NO. XXXXXX
EG-SWMENG- XXXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND LICENSE NO. XXXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	SIGN AND SEAL

HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK STREAM RESTORATION ESC PLAN	
Drawn By :	CA
Designed By :	CA
Reviewed By :	BWA
Drawing No.	ES-02 of ES-02
Sheet No.	45 of 54





HARFORD COUNTY, MARYLAND

EDGEGATER VILLAGE PARK STREAM RESTORATION FSC DETAILS

Drawn By :	CA	Scale :	AS NOTED
Designed By :	CA	Date :	JUNE 2025
Reviewed By :	BWA		
Drawing No.	ED-02	of	ED-03

BILLING NO. XXXXXX
EG-SWMENG- XXXXX-XXXX #XXXX
<u>PROFESSIONAL CERTIFICATION</u>
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

SEDIMENT CONTROL NOTES

- THE CONTRACTOR/OWNER IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS. FURTHER, NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE UNTIL ALL REQUIRED PERMITS HAVE BEEN OBTAINED.
- THE LIMITS OF DISTURBANCE SHALL BE CLEARLY DELINEATED IN THE FIELD PRIOR TO GRADING OF THE SITE TO ENSURE COMPLIANCE WITH APPROVED PLANS. ALL FOREST RETENTION AREAS WILL BE DELINEATED WITH BLAZE ORANGE FENCE AS WELL AS ANY SWM INFILTRATION PRACTICE PRIOR TO ANY CLEARING. WORK BEYOND THE LIMITS OF DISTURBANCE AND IN ANY AREA INSIDE THE FOREST RETENTION AND SWM INFILTRATION AREA IS CONSIDERED A VIOLATION OF THIS PLAN.
- ALL SEDIMENT CONTROL PRACTICES MUST BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITY. UPON COMPLETION OF THE INSTALLATION OF PERIMETER SEDIMENT CONTROL PRACTICES THE SITE MUST BE INSPECTED BY THE DEPARTMENT OF PUBLIC WORKS (DPW). NO ADDITIONAL CONSTRUCTION ACTIVITY WILL BE AUTHORIZED WITHOUT THE APPROVAL OF DPW.
- ALL POINTS OF INGRESS AND EGRESS SHALL BE PROTECTED TO PREVENT TRACKING OF MUD INTO PUBLIC WAYS. DURING CONSTRUCTION, EVERY MEANS WILL BE TAKEN TO CONTROL SOIL EROSION AND SILTATION. IF NECESSARY A WASH RACK MAY NEED TO BE ESTABLISHED.
- EARTH DIKES, SEDIMENT TRAPS, ETC. WILL BE LOCATED AS SHOWN ON THESE DRAWINGS. FIELD CHANGES AND MINOR ADJUSTMENTS ARE PERMISSIBLE AS LONG AS THE INSTALLATION FUNCTIONS AND CONFORMS TO SPECIFICATIONS. THE SITE INSPECTOR PRIOR TO INSTALLATION MUST APPROVE ALL SUCH CHANGES. MAJOR CHANGES TO THE APPROVED PLAN WILL REQUIRE RE-APPROVAL BY THE HARFORD SOIL CONSERVATION DISTRICT.
- FOLLOWING INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN:
 - THREE CALENDAR DAYS ON SLOPES GREATER THAN 3:1, ALL WATERWAYS AND TO THE SURFACE OF ALL PERIMETER CONTROLS.
 - SEVEN CALENDAR DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS OF THE PROJECT SITE.
- DUST CONTROL MUST BE MANAGED AS PART OF ALL SEDIMENT CONTROL PLANS. FAILURE TO DO SO IS A VIOLATION OF THIS PLAN.
- SEDIMENT BASINS MUST BE BUILT TO DESIGN SPECIFICATION AS SHOWN ON THE PLAN. IF THE BASIN IS TO BE USED AT A FUTURE SWM FACILITY, THE BASIN WILL BE BUILT IN ACCORDANCE WITH THE LATEST MD-378 STANDARDS AND SPECIFICATIONS. SPECIFIED MATERIALS MUST BE USED. NO CHANGED OR MODIFICATIONS WILL BE MADE WITHOUT WRITTEN AUTHORIZATION OF THE HARFORD COUNTY SOIL CONSERVATION DISTRICT.
- TEMPORARY FENCING SHALL BE PLACED AROUND ALL SEDIMENT BASINS, TRAPS, AND PONDS DURING CONSTRUCTION AND SITE GRADING.
- AT THE END OF EACH WORKING DAY ALL SEDIMENT CONTROL PRACTICES WILL BE INSPECTED AND LEFT OPERATION. A WEEKLY LOG WILL BE KEPT IN ACCORDANCE WITH NOI/NPDES REGULATIONS. A COPY OF THE APPROVED SEDIMENT CONTROL PLANS SHALL BE AVAILABLE AT THE SITE AT ALL TIMES.
- ENSURE POSITIVE DRAINAGE TO ALL ROAD INLETS DURING ALL PHASES OF ROAD CONSTRUCTION TO ENSURE POSITIVE FLOW TO TRAPS AND OR BASINS.
- CUT AND/OR FILL SHALL BE DONE IN CONFORMANCE WITH 2011 EROSION AND SEDIMENT CONTROL STANDARD AND SPECIFICATIONS FOR LAND GRADING.
- SURFACE FLOWS OVER CUT AND FILL SLOPES SHALL BE CONTROLLED BY EITHER REDIRECTING FLOWS FROM TRaversing THE SLOPES OR BY INSTALLING MECHANICAL DEVICES TO SAFELY CONVEY WATER DOWN SLOPES WITHOUT CAUSING EROSION.
- OFF-SITE WASTE OR BORROW AREAS SHALL HAVE AN APPROVED EROSION AND SEDIMENT CONTROL PLAN PRIOR TO THE IMPORT OR EXPORT OF MATERIAL TO/FROM THE PROJECT SITE.
- ALL MATERIAL ORIGINATING FROM THE DEVELOPMENT OF THE PROPERTY AND DEPOSITED ON THE PUBLIC RIGHT-OF-WAY SHALL BE IMMEDIATELY REMOVED.
- STORM DRAIN INLETS AND OUTLETS SHALL BE PROTECTED PER 2011 EROSION AND SEDIMENT CONTROL STANDARDS AND SPECIFICATIONS
- TOPSOIL, LIMING, FERTILIZING, SEEDING, MULCHING, SOD, ETC. ARE ALL AN ESSENTIAL PART OF THE SEDIMENT CONTROL PLAN AND MUST BE COMPLETED ALONG WITH ALL OTHER PRACTICES
- TRAPS TO BE REMOVED SHALL BE Dewatered AS PER THE 2011 EROSION AND SEDIMENT AND EROSION CONTROL STANDARDS AND SPECIFICATIONS.
- PRIOR TO REMOVAL OF TRAPS OR CONVERSION OF SEDIMENT BASINS TO SWM FACILITIES, THE STORM DRAINS WILL BE FLUSHED.
- SEDIMENT CONTROL PRACTICES WILL BE MAINTAINED UNTIL ALL DISTURBED AREAS FOR WHICH THE PRACTICES WERE INSTALLED HAVE BEEN STABILIZED. SEDIMENT CONTROL PRACTICES MAY BE REMOVED ONLY WITH THE AUTHORIZATION OF THE DPW INSPECTOR. ALL DISTURBED AREAS RESULTING FROM THE REMOVAL OF SEDIMENT CONTROL DEVICES SHALL BE STABILIZED IMMEDIATELY. REMOVAL PRIOR TO INSPECTOR'S APPROVAL CONSTITUTES A VIOLATION.

PERMANENT VEGETATIVE STABILIZATION NOTES

ALL DISTURBED AREAS WHICH ARE NOT BE PAVED, SHALL BE PERMANENTLY STABILIZED AS FOLLOWS:

- SEED BED PREPARATION: LOSEN UPPER THREE INCH BY RAKING, DISCING, OR OTHER ACCEPTABLE MEANS AFTER SPREADING FOUR INCHES OF TOP SOIL
- SOIL AMENDMENTS: APPLY 500 LBS. PER ACRE OF 10-10-10 FERTILIZER AND TWO TONS PER ACRE OF LIME
- SEEDING*:

FOR PERIODS OF MARCH 1 TO MAY 15 AND AUGUST 15 TO OCTOBER 15: SEED WITH 60 LBS. PER ACRE OF TALL FESCUE, 40 LBS. PER ACRE OF KENTUCKY BLUEGRASS, AND 20 LBS. PER ACRE OF PERENNIAL RYEGRASS.

FOR PERIOD OF MAY 16 TO AUGUST 14: SEED WITH 100 LBS. PER ACRE OF TALL FESCUE AND 3 LBS. PER ACRE OF WEEPING LOVEGRASS OR 5 LBS. OF PEARL OR FOXTAIL MILLET.

FOR PERIOD OF OCTOBER 16 TO FEBRUARY 28:

OPTION 1: PROTECT THE SITE BY APPLYING TWO (2) TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING.

OPTION 2: USE SOD, PROVIDED THE GROUND IS SUITABLE AND THAWED; COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATION ADDRESSING "SOD" (PAGES B.23 & B.24).

MULCHING SPECIFICATIONS:

MULCH SHALL BE APPLIED TO ALL SEDED AREAS IMMEDIATELY AFTER SEEDING.

APPLY TWO (2) TONS PER ACRE OF STRAW OVER ALL SEDED AREAS. IF A MULCH ANCHORING TOOL IS TO BE USED, THE RATE SHALL BE INCREASED TO 2.5 TONS PER ACRE. **

MULCH ANCHORING SHALL BE PERFORMED IMMEDIATELY FOLLOWING MULCH APPLICATION TO MINIMIZE LOSS BY WIND AND WATER. THE TYPE OF MULCH ANCHORING USED MUST COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS.

* IF OTHER SEED MIXES ARE TO BE SUBSTITUTED, THEY MUST COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS, B-4-5: "PERMANENT SEEDING", TABLE B-3 (PAGES B.26 TO B.31)

** IF A DIFFERENT TYPE OF MULCH IS TO BE SUBSTITUTED, THEY MUST COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS, B-4-3: "SEEDING AND MULCHING" (PAGES B.15 B.17)

TEMPORARY VEGETATIVE STABILIZATION

A.) SEEDBED PREPARATION:

LOSEN A MINIMUM OF THREE INCHES ALONG UPPER SOIL BY DISCING, RAKING OR OTHER ACCEPTABLE MEANS

B.) SOIL AMENDMENTS:

INCORPORATE 436 LBS. PER ACRE OF 10-20-20 FERTILIZER AND TWO (2) TONS PER ACRE OF LIME BY DISCING OR OTHER ACCEPTABLE MEANS.

C.) SEEDING*:

FOR PERIODS OF MARCH 1 TO APRIL 30 AND AUGUST 15 TO NOVEMBER 15: SEED WITH 2.5 BU. PER ACRE OF CEREAL RYE OR 40 LBS. PER ACRE OF ANNUAL RYEGRASS.

FOR PERIOD OF MAY 1 TO AUGUST 14: SEED WITH 3 LBS. PER ACRE OF WEEPING LOVEGRASS OR 30 LBS. PER ACRE OF PEARL OR FOXTAIL MILLET.

FOR THE PERIOD OF NOVEMBER 16 TO FEBRUARY 28: PROTECT THE SITE BY APPLYING TWO (2) TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING

D.) MULCHING SPECIFICATIONS:

MULCH SHALL BE APPLIED TO ALL SEDED AREAS IMMEDIATELY AFTER SEEDING.

APPLY TWO (2) TONS PER ACRE OF STRAW OVER ALL SEDED AREAS. IF A MULCH ANCHORING TOOL IS TO BE USED, THE RATE SHALL BE INCREASED TO 2.5 TONS PER ACRE. **

MULCH ANCHORING SHALL BE PERFORMED IMMEDIATELY FOLLOWING MULCH APPLICATION TO MINIMIZE LOSS BY WIND AND WATER. THE TYPE OF MULCH ANCHORING USED MUST COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS.

* IF OTHER SEED MIXES ARE TO BE SUBSTITUTED, THEY MUST COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS, B-4-4: "TEMPORARY SEEDING", TABLE B-1 (PAGE B.20)

** IF A DIFFERENT TYPE OF MULCH IS TO BE USED, IT MUST COMPLY WITH THE 2011 MARYLAND STANDARD AND SPECIFICATION, B-4-3: "SEEDING AND MULCHING" (PAGES B.15 - B.17).

BEST MANAGEMENT PRACTICES FOR WORKING IN NONTIDAL WETLANDS, WETLAND BUFFERS, AND 100 YEAR FLOODPLAINS

- NO EXCESS FILL, CONSTRUCTION MATERIAL, OR DEBRIS SHALL BE STOCKPILED OR STORED IN NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR THE 100-YEAR FLOODPLAIN.
- PLACE MATERIALS IN A LOCATION AND MANNER WHICH DOES NOT ADVERSELY IMPACT SURFACE OR SUBSURFACE WATER FLOW INTO OR OUT OF NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR THE 100-YEAR FLOODPLAIN.
- DO NOT USE THE EXCAVATED MATERIAL AS BACKFILL IF IT CONTAINS WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL, OR ANY OTHER DELETERIOUS SUBSTANCE.
- PLACE HEAVY EQUIPMENT ON MATS OR SUITABLY OPERATE THE EQUIPMENT TO PREVENT DAMAGE TO NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR THE 100-YEAR FLOODPLAIN.
- REPAIR AND MAINTAIN ANY SERVICABLE STRUCTURE OR FILL SO THERE IS NO PERMANENT LOSS OF NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR PERMANENT MODIFICATION OF THE 100-YEAR FLOODPLAIN IN EXCESS OF THAT LOST UNDER THE ORIGINALLY AUTHORIZED STRUCTURE OR FILL.
- RECTIFY ANY NONTIDAL WETLANDS, WETLAND BUFFERS, WATERWAYS, OR 100-YEAR FLOODPLAIN TEMPORARILY IMPACTED BY ANY CONSTRUCTION.
- ALL STABILIZATION IN THE NONTIDAL WETLAND AND NONTIDAL WETLAND BUFFER SHALL CONSIST OF THE FOLLOWING SPECIES: ANNUAL RYEGRASS (LOLIUM MULTIFLORUM), MILLET (SETARIA ITALICA), BARLEY (HORDEUM SP.), OATS (UNIOLA SP) AND/OR RYE (SECALE CEREALE). THESE SPECIES WILL ALLOW FOR THE STABILIZATION OF THE SITE WHILE ALSO ALLOWING FOR THE VOLUNTARY REVEGETATION OF NATURAL WETLAND SPECIES. OTHER NON-PERSISTENT VEGETATION MAY BE ACCEPTABLE, BUT MUST BE APPROVED BY THE NONTIDAL WETLANDS AND WATERWAYS DIVISION. KENTUCKY 31 FESCUE SHALL NOT BE UTILIZED IN WETLAND OR BUFFER AREAS. THE AREA SHOULD BE SEDED AND MULCHED TO REDUCE EROSION AFTER CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED.
- AFTER INSTALLATION HAS BEEN COMPLETED, MAKE POST CONSTRUCTION GRADES AND ELEVATIONS THE SAME AS THE ORIGINAL GRADES AND ELEVATIONS IN TEMPORARILY IMPACTED AREAS.
- TO PROTECT AQUATIC SPECIES, IN-STREAM WORK IS PROHIBITED AS DETERMINED BY THE CLASSIFICATION OF THE STREAM:
 - USE I WATERS (WITHOUT YELLOW PERCH): IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD MARCH 1 THROUGH JUNE 15, INCLUSIVE DURING ANY YEAR.
 - USE I WATERS (WITH YELLOW PERCH): IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD FEBRUARY 15 THROUGH JUNE 15, INCLUSIVE DURING ANY YEAR.
 - USE II WATERS: IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD OCTOBER 1 THOROUGH APRIL 30, INCLUSIVE, DURING ANY YEAR.
 - USE IV WATERS: IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD MARCH 1 THROUGH MAY 31, INCLUSIVE, DURING ANY YEAR.
- STORMWATER RUNOFF FROM IMPERVIOUS SURFACES SHALL BE CONTROLLED TO PREVENT THE WASHING OF DEBRIS INTO THE WATERWAY.
- CULVERTS SHALL BE CONSTRUCTED AND ANY RIPRAP PLACED SO AS NOT TO OBSTRUCT THE MOVEMENT OF AQUATIC SPECIES, UNLESS THE PURPOSE OF THE ACTIVITY IS TO IMPOUND WATER.

STANDARD NOTES FOR WORKING IN FLOODPLAIN

4
ED-03
NOT TO SCALE

SITE ANALYSIS
TOTAL SITE AREA: 118957 SF / 2.73 ACRES
TOTAL DISTURBED AREA: 118957 SF / 2.73 ACRES
TOTAL AREA TO BE PAVED: 0.0 SF / 0.0 ACRES
AREA TO BE STABILIZED: 118957 SF / 2.73 ACRES
TOTAL CUT*: 2191 CU YD
TOTAL FILL: 1801 CU YD
TOPSOIL: 614 CU YD
NPDES I.D. POINT N: 641669.2051 E: 1504880.4859'

* ANY EXCESS MATERIAL SHALL BE REMOVED TO A SITE WITHIN CURRENT ENS PLAN AND PERMIT

ENGINEER'S CERTIFICATION

I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE 2011 MARYLAND STANDARD AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.

ENGINEER DATE


OWNER'S CERTIFICATION

IWE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATION OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ONSITE INSPECTION BY THE HARFORD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS, OR AS DEEMED NECESSARY.

OWNER DATE

HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK	
STREAM RESTORATION	
ESC DETAILS	
Drawn By : CA	Scale : AS NOTED
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. ED-03 of ED-03	Sheet No. 48 of 54

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
BILLING NO. XXXXX	
EG-SWMENG- XXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.	




MAINTENANCE OF TRAFFIC PLAN

1 SCALE: 1"=200'

GENERAL NOTES


- ALL TRAFFIC CONTROL DEVICES MUST ADHERE TO THE CURRENT EDITION OF THE MARYLAND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MD MUTCD) AND SHA BOOK OF STANDARDS.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SUPPLY, INSTALL & MAINTAIN ALL TEMPORARY TRAFFIC CONTROL EQUIPMENT FOR THE DURATION OF THE CONTRACT. ALL MAINTENANCE OF TRAFFIC DEVICES AND INSTALLATION OF THE DEVICES WILL BE INSPECTED ON A ROUTINE BASIS BY THE CONTRACTOR'S CERTIFIED TRAFFIC MANAGER. ANY DEFICIENCIES SHALL BE CORRECTED PROMPTLY BY THE CONTRACTOR.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A SAFE INGRESS/EGRESS TO ALL ADJACENT PROPERTIES, ROADWAYS, AND DRIVEWAYS.
- ALL EXISTING SIGNAGE AND PAVEMENT MARKINGS SHALL BE MAINTAINED THROUGHOUT THE DURATION OF THE CONSTRUCTION.



BILLING NO. XXXXXX	
EG-SWMENG- XXXXXX-XXXX #XXXX	
PROFESSIONAL CERTIFICATION	
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXXX, EXPIRATION DATE: XX/XX/XXXX.	

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	


HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK	
STREAM RESTORATION	
MAINTENANCE OF TRAFFIC	
Drawn By : CA	Scale : 1" = 100'
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. MT-01 of MT-01	
Sheet No. 49 of 54	



CHARFORD COUNTY MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION LANDSCAPING PLAN

Drawn By :	CA	Scale :	1" = 20'
Designed By :	CA	Date :	JUNE 2025
Reviewed By :	BWA		
Drawing No.	LP-01	of	LP-02



ZONE 1 UPLAND TREE, SHRUB AND SEED MIX

ZONE 1 UPLAND HERBACEOUS SEED MIX

ZONE 2 RIPARIAN TREE, SHRUB AND SEED MIX

ZONE 2 RIPARIAN SEED MIX

ZONE 3 STREAMBANK SEED MIX AND STREAM BANK LIVE STAKE

ZONE 4 TURFGRASS SEED

SCALE IN FEET 1" =

LOD SDX SDX

BILLING NO. XXXXXX

EG-SWMENG- XXXXX-XXXX #XXXX

PROFESSIONAL CERTIFICATION



I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Rev
GP # XXXXX-XXXX	
SIGN AND SEAL	

31D NO.:

HCG DWG ID No. :
SCALE : 1 inch

SCALE : 1 inc



- ZONE 1 UPLAND TREE, SHRUB AND SEED MIX
- ZONE 1 UPLAND HERBACEOUS SEED MIX
- ZONE 2 RIPARIAN TREE, SHRUB AND SEED MIX
- ZONE 2 RIPARIAN SEED MIX
- ZONE 3 STREAMBANK SEED MIX AND STREAM BANK LIVE STAKES
- ZONE 4 TURFGRASS SEED

SCALE IN FEET 1" = 20'

BILLING NO. XXXXXX

EG-SWMENG- XXXXXX-XXXX #XXXX

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

S/C PLAN # XXXXX	Revisions	
GP # XXXXX-XXXX		
SIGN AND SEAL		

HARFORD COUNTY MARYLAND

EDGEWATER VILLAGE PARK STREAM RESTORATION LANDSCAPING PLAN

CA	Scale : <u>1" = 20'</u>
CA	Date : <u>JUNE 2025</u>

Drawn By :	CA		
Designed By :	CA		
Reviewed By :	BWA		
Drawing No.	LP-02	of	LP-02

100

ZONE 1: UPLAND SEED MIX - 1.79 ACRES			
ERNMX-731 OR APPROVED EQUAL, 20 LBS/ACRE			
SCIENTIFIC NAME	COMMON NAME	TYPE	%TOTAL COMPOSITION
<i>SCHIZACHYRIUM SCOPARIUM</i>	LITTLE BLUESTEM	HERB	65.90%
<i>ELYMUS VIRGINICUS</i>	VIRGINIA WILDRYE	HERB	17.00%
<i>RUDBECKIA HIRTA</i>	BLACKEYED SUSAN	HERB	3.00%
<i>LESPEDEZA VIRGINICA</i>	SLENDER LESPEDEZA	HERB	2.50%
<i>ASCLEPIAS TUBEROSA</i>	BUTTERFLY MILKWEED	HERB	2.00%
<i>CHAMAECRISTA FASCICULATA</i>	PARTRIDGE PEA	HERB	1.50%
<i>SENNA HEBECARPA</i>	WILD SENNA	HERB	1.50%
<i>ASTER PILOSUS</i>	HEATH ASTER	HERB	1.20%
<i>PYCNANTHEMUM TENUIFOLIUM</i>	NARROWLEAF MOUNTAINMINT	HERB	1.20%
<i>AQUILEGIA CANDENSIS</i>	EASTERN COLUMBINE	HERB	1.00%
<i>GEUM CANADENSE</i>	WHITE AVENS	HERB	1.00%
<i>CHAMAECRISTA NICTITANS</i>	SENSITIVE PEA	HERB	0.50%
<i>SISYRINCHIUM ANGUSTIFOLIUM</i>	NARROWLEAF BLUE EYED GRASS	HERB	0.50%
<i>OENOTHERA FRUTICOSA</i>	SUNDROPS	HERB	0.30%
<i>SOLIDAGO BICOLOR</i>	WHITE GOLDENROD	HERB	0.30%
<i>SOLIDAGO NEMORALIS</i>	GRAY GOLDENROD	HERB	0.30%
<i>ASTER LATERIFLORUS</i>	CALICO ASTER	HERB	0.20%
<i>SOLIDAGO JUNcea</i>	EARLY GOLDENROD	HERB	0.10%

ZONE 1: UPLAND TREE AND SHRUB MIX - 1.48 ACRES

SCIENTIFIC NAME	COMMON NAME	TYPE	#7 CONTAINER	#5 CONTAINER	#2 CONTAINER
QUERCUS ALBA	WHITE OAK	SINGLE STEM TREE	26	13	0
POPULUS GRANDIDENTATA	BIG TOOTH ASPEN	SINGLE STEM TREE	16	12	0
LIQUIDAMBAR STYRACIFLUA	AMERICAN SWEETGUM	SINGLE STEM TREE	14	10	0
QUERCUS RUBRA	RED OAK	SINGLE STEM TREE	30	12	0
QUERCUS PALUSTRIS	PIN OAK	SINGLE STEM TREE	32	13	0
LIRIODENDRON TULIPIFERA	TULIP TREE	SINGLE STEM TREE	30	13	0
ACER RUBRUM	RED MAPLE	SINGLE STEM TREE	25	13	0
VIBURNUM ACERIFOLIUM	MAPLELEAF VIBURNUM	SHRUB	0	0	15
VACCINIUM VACILLANS	LOWBUSH BLUEBERRY	SHRUB	0	0	14
		TOTAL	173	86	29

ZONE 2: RIPARIAN SEED MIX - 0.45 ACRES

ERNMX-732 OR APPROVED EQUAL, 20 LBS/ ACRE

SCIENTIFIC NAME	COMMON NAME	TYPE	%TOTAL COMPOSITION
<i>SORGHastrum nutans</i>	INDIANGRASS	HERB	39.70%
<i>elymus virginicus</i>	VIRGINIA WILDRYE	HERB	20.00%
<i>Panicum virgatum</i>	SWITCHGRASS	HERB	18.00%
<i>Panicum rigidulum</i>	REDTOP PANICGRASS	HERB	10.00%
<i>Chamaecrista fasciculata</i>	PARTRIDGE PEA	HERB	3.00%
<i>Rudbeckia hirta</i>	BLACKEYED SUSAN	HERB	3.00%
<i>Helianthus helianthoides</i>	OXEYE SUNFLOWER	HERB	2.00%
<i>Asclepias incarnata</i>	SWAMP MILKWEED	HERB	1.00%
<i>Vernonia noveboracensis</i>	NEW YORK IRONWEED	HERB	0.90%
<i>Eupatorium perfoliatum</i>	BONESET	HERB	0.80%
<i>Helemium autumnale</i>	COMMON SNEEZEWEEED	HERB	0.80%
<i>Solidago rugosa</i>	WRINKLELEAF GOLDENROD	HERB	0.80%

ZONE 2: RIPARIAN TREE AND SHRUB MIX - 0.40 ACRES





SCIENTIFIC NAME	COMMON NAME	TYPE	#7 CONTAINER	#5 CONTAINER	#2 CONTAINER
LIQUIDAMBAR STYRACIFLUA	AMERICAN SWEETGUM	SINGLE STEM TREE	8	4	0
ACER RUBRUM	RED MAPLE	SINGLE STEM TREE	7	4	0
BETULA NIGRA	RIVER BIRCH	SINGLE STEM TREE	3	2	0
PLATANUS OCCIDENTALIS	AMERICAN SYCAMORE	SINGLE STEM TREE	7	3	0
QUERCUS PHELLOS	WILLOW OAK	SINGLE STEM TREE	7	3	0
ALNUS SERRULATA	SMOOTH ALDER	MULTI STEM TREE	7	3	0
QUERCUS BICOLOR	SWAMP WHITE OAK	SINGLE STEM TREE	7	3	0
LINDERA BENZOIN	SPICEBUSH	SHRUB	0	0	8
		TOTAL	47	23	8

STREAMBANK SEED MIX - 0.12 ACRES			
ERNMX-733 OR APPROVED EQUAL, 20 LBS/ACRE			
SCIENTIFIC NAME	COMMON NAME	TYPE	%TOTAL COMPOSITION
<i>CAREX VULPINOIDEA</i>	FOX SEDGE	HERB	25.00%
<i>ELYMUS VIRGINICUS</i>	VIRGINIA WILDRYE	HERB	18.00%
<i>PANICUM RIGIDULUM</i>	REDTOP PANICGRASS	HERB	17.00%
<i>CAREX LURIDA</i>	LURID SEDGE	HERB	16.70%
<i>CAREX SCOPARIA</i>	BLUNT BROOM SEDGE	HERB	10.00%
<i>CAREX CRINITA</i>	FRINGED SEDGE	HERB	3.00%
<i>JUNCUS EFFUSUS</i>	SOFT RUSH	HERB	3.00%
<i>ASCLEPIAS INCARNATA</i>	SWAMP MILKWEED	HERB	2.00%
<i>EUPATORIUM PERfoliatum</i>	BONESET	HERB	1.00%
<i>HELENIUM AUTUMNALE</i>	COMMON SNEEZEWEED	HERB	1.00%
<i>JUNCUS TENUIS</i>	PATH RUSH	HERB	1.00%
<i>VERNONIA NOVEBORACENSIS</i>	NEW YORK IRONWEED	HERB	1.00%
<i>SOLIDAGO RUGOSA</i>	WRINKLELEAF GOLDENROD	HERB	0.70%
<i>MIMULUS RINGENS</i>	SQUARE STEMMED MONKEYFLOWER	HERB	0.30%
<i>SCIRPUS CYPERINUS</i>	WOOLGRASS	HERB	0.30%

ZONE 3: STREAMBANK LIVE STAKES MIX - 0.12 ACRES		
SCIENTIFIC NAME	COMMON NAME	QUANTITY
<i>SALIX NIGRA</i>	BLACK WILLOW	148
<i>CORNUS AMOMUM</i>	SILKY DOGWOOD	148
<i>CORNUS SERICEA</i>	RED OSIER DOGWOOD	148
<i>SALIX SERICEA</i>	SILKY WILLOW	147
	TOTAL	591

ZONE 4: TURF SEED	
AREA	UNITS
1,581	SQUARE FEET

1. QUANTITIES ARE BASED ON ESTIMATED PLANTING AREA OF 2.39 ACRES. ANY ADDITIONAL DISTURBANCE REQUIRING PLANTING SHALL BE SEEDED AND PLANTED AT THE RATE SPECIFIED FOR UPLAND SEED MIX.
2. SEEDING SHALL OCCUR PRIOR TO INSTALLATION OF EROSION CONTROL COIR MATTING FABRICS AND LIVE STAKE PLANTING.
3. LIVE STAKES SHALL BE INSTALLED ALONG NEWLY GRADED BANKS WITHIN PLANTING ZONE 3 AS INDICATED ON THE LANDSCAPING PLANS. THE DENSITY OF LIVE STAKES IS BASED ON AN ESTIMATED AREA OF STREAM BANK AND SPACED ACCORDING TO THE LIVE STAKING DETAIL.
4. LIVE STAKES WILL BE PLANTED WITH 2 ROWS ON EACH SPECIFIED STREAM BANK AT 3'X3' SPACING.
5. TREES AND SHRUBS SHALL BE SPACED 15 FT ON CENTER IN OFFSETTING ROWS.
6. MULCHING SHALL BE PERFORMED WITHIN 48 HOURS OF SEEDING. GRAIN STRAW MULCH SHOULD BE APPLIED ON SEEDED AREAS AT A RATE OF 2 TONS PER ACRE AND APPLIED UNIFORMLY.
7. SPECIES LISTED ON LD-01 SHOULD BE PLANTED. IF UNAVAILABLE, SUBSTITUTIONS MAY BE ALLOWED BASED ON REVIEW AND APPROVAL OF THE PROPOSED MATERIAL AND LOCAL NURSERY SUPPLY
8. UPLAND SEED MIX SHALL BE APPLIED EVENLY AT A RATE OF 20 LBS PER ACRE WITH A COVER CROP OF OATS AT 100 LBS PER ACRE BETWEEN JANUARY 1 TO APRIL 30, BROWN TOP MILLET AT 30 LBS PER ACRE BETWEEN MAY 1 TO AUGUST 31 OR GRAIN RYE AT 100 LBS PER ACRE BETWEEN SEPTEMBER 1 TO DECEMBER 31.
9. RIPARIAN SEED MIX SHALL BE APPLIED EVENLY AT A RATE OF 20 LBS PER ACRE WITH A COVER CROP OF GRAIN OATS AT 100 LBS PER ACRE BETWEEN JANUARY 1 TO APRIL 30, BROWN TOP MILLET AT 30 LBS PER ACRE BETWEEN MAY 1 TO AUGUST 31, OR GRAIN RYE AT 100 LBS PER ACRE BETWEEN SEPTEMBER 1 TO DECEMBER 31.
10. ALL SINGLE STEM TREES LOCATED WITHIN ZONE 1 SHALL RECEIVE BLACK HIGH DENSITY POLYETHYLENE DEER PROTECTION SHELTERS 4' IN HEIGHT BY 4" IN DIAMETER MOUNTED AS DEPICTED IN THE TYPICAL DETAIL PROVIDED.
11. ALL SHRUB PLANTINGS AND MULTI STEM TREES LOCATED WITHIN ZONE 1 SHALL BE ENCLOSED USING 4' TALL, 14 GAUGE GALVANIZED, WELDED WIRE FENCE SECURED TO 6' METAL T-POSTS DRIVE 2' INTO THE GROUND.
12. INDIVIDUAL TREES WITHIN THE LOD THAT ARE NOT MARKED AS REMOVAL AND NOT WITHIN A DESIGNATED AREA OF FOREST RETENTION SHALL BE PROTECTED WITH TREE PLANKING CONTINUOUSLY AROUND THOSE TREES.
13. CONTRACTOR SHALL USE LOW PRESSURE EQUIPMENT OR HAND GRADING WHEN GRADING WITHIN CRITICAL ROOT ZONES OF TREES THAT ARE MARKED TO BE SAVED.
14. FOREST RETENTION SIGNAGE SHALL BE STAKED ALONG THE EXISTING HIGH VISIBILITY FENCING OR SILT FENCE ALONG PORTIONS OF THE LOD MARKED AS FOREST RETENTION AREA. SIGN SHALL BE SPACE APPROXIMATELY 100 FEET APART WHERE POSSIBLE, WITH MAXIMUM OF 150 FEET APART.
15. CONTRACTOR SHALL REFER TO THE EDGEWATER VILLAGE STREAM RESTORATION CONSTRUCTION SPECIFICATIONS REGARDING FOREST/TREE PROTECTION METHODS. INITIAL PLANTING SHALL BE SUPERVISED BY A LICENSED TREE CARE PROFESSIONAL
16. NO TREES SHALL BE PLANTED WITHIN 15 FEET OF ANY EXISTING UTILITIES ON SITE



S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	


BILLING NO. XXXXXX
EG-SWMENG- XXXXXX-XXXX #XXXX
PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. XXXXXX, EXPIRATION DATE: XX/XX/XXXX.

HARFORD COUNTY, MARYLAND	
EDGEWATER VILLAGE PARK STREAM RESTORATION LANDSCAPING DETAILS	
Drawn By : CA	Scale : AS NOTED
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. LD-02 of LD-02	
Sheet No. 53 of 54	



DRAINAGE AREAS		
POI	DRAINAGE AREA (SQ. MI)	PERCENT IMPERVIOUS (%)
REACH 1	0.05	40%
REACH 2A	0.08	33%
REACH 2B	0.09	33%
LT-1	0.02	28.3%
LT-2	0.01	11.9%
REACH 3	0.11	33.0%

DRAINAGE AREA BOUNDARY
 SUB-DRAINAGE AREA BOUNDARY
 POINT OF INTEREST (POI)



BILLING NO. XXXXXX
 EG-SWMENG- XXXXXX-XXXX #XXXX
 PROFESSIONAL CERTIFICATION
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME,
 AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
 THE STATE OF MARYLAND. LICENSE NO. XXXXX, EXPIRATION DATE: XX/XX/XXXX.

HARFORD COUNTY, MARYLAND

EDGEWATER VILLAGE PARK
STREAM RESTORATION
DRAINAGE AREA

S/C PLAN # XXXXX	Revisions
GP # XXXXX-XXXX	
SIGN AND SEAL	
Drawn By : CA	Scale : 1"=140'
Designed By : CA	Date : JUNE 2025
Reviewed By : BWA	
Drawing No. DA-01 of DA-01	
Sheet No. 54 of 54	

HCG DWG ID No. :
SCALE 1"=140' HCG DWG ID No. :
Sheet No. 54 of 54